

2018 MS4 Annual Report



ANNUAL MUNICIPAL SEPARATE STORM SEWER REPORT

Background information

1. The name and permit number of the program submitting the annual report.

Norfolk State University, Permit # VAR 040097

2. The annual report permit year.

Permit Year July 1, 2017 to June 30, 2018

3. Modifications to any operator's department's roles and responsibilities.

The Facilities Management Department has replaced the positions of:

- No replacements have been made.

4. Number of new MS4 outfalls and associated acreage by HUC added during the permit year.

No new outfalls were added during the permit year. The existing outfalls and associated acreages by HUC are as follows:

Outfall Name	Acreage	HUC	Description
Outfall #1	±3.4 Acres	JL 54	Flows east into the City line under Ballentine Avenue
Pipes #2 to 8	±18.0 Acres	JL 54	Flow south into a perimeter ditch
Outfall #9	±104.8 Acres	JL 54	Is a large box culvert which flows to the south border
Outfall #10	±3.3 Acres	JL 54	Flows south to the City line under Brambleton Avenue
Outfall #11	±1.2 Acres	JL 54	Flows west to the City line under Park Avenue

An overlay map displaying these structures are in the attached appendix A.



Signed certification in accordance with 4 VAC 50-60-370.

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Jotoks Date Signature



6. The status of compliance with permit conditions, an assessment of the appropriateness of the identified best management practices including an assessment of the appropriateness of the identified BMPs in addressing discharges into waters that identified as impaired in the 2012 305(b)/303(d) Water Quality Assessment Integrated Report and progress towards achieving the identified measurable goals for each of the minimum control measures.

-See attached chart for additional information regarding this item.

7. The results of information collected and analyzed, including monitoring data, if any, during the reporting period.

-See attached chart for additional information regarding this item.

8. A summary of the stormwater activities the operator plans to undertake during the next reporting cycle.

- The University has retained a consultant to assist with updating a prior Stormwater Management Master Plan for the campus which includes specific directions for current and future stormwater best management practices. The proposed Stormwater Management Master Plan has been submitted to DEQ and comments are currently being addressed to conform to new state regulations and TMDL requirements. A resubmittal of the updated Campus Stormwater Master Plan will be submitted to DEQ for review by late 2018.

-See attached chart for additional information regarding this item.

9. Any changes in any identified best management practices or measurable goals for any of the minimum control measures including steps to be taken to address any deficiencies.

-See attached chart for additional information regarding this item.

Minimum Control Measure #1: Public Education and Outreach on Stormwater Impacts

This measure requires the University to educate the public about the potential impact of stormwater discharges from the University. The University will show the impact it has on surrounding bodies of water, emphasizing the precautions to be taken to reduce pollutants in stormwater runoff. The University considers the campus community as its public and a critical stakeholder in the University's Stormwater Management Plan. Staff receive work orders that directly address physical conditions that can be the source of stormwater pollutants. Multiple Best Management Practices (BMP)s are associated with this Minimum Control Measure. All BMPs defined under this measure were implemented during the first permitting year and continuously since that time.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
1A. High Priority Water Quality Issues:	Target Audience - 162 Housekeeping and	Training on the University's	Show updated presentation to staff
1 Bus Wash Facility - Prevent oils and grease from entering the storm sewer	grounds employees of which 76 Grounds	conservation initiatives, including	and students and other interested
system. Design and construction of needed bus wash water inlet structure to be	Staff Member (50%) attended and received	stormwater pollution prevention was	parties. An expanded program of
tied into the sanitary sewer system.	training. Additionally, newly added staff	completed and held on 2/14/18 and	training in 2019 will include police
2 Material Storage (Mulch, sand, dirt) - Prevent sediment and material being	have received orientation training that	7/25/17, covering the 3 high priority	officers and students and additional
carried with storm runoff to storm sewer system. Design and construction of a	includes stormwater pollution prevention.	water quality issues and additional	faculty. NSU will target its staff
material storage bays with E & S control measures.	Approximately 400 students in residence	stormwater pollution prevention	members (162 +/-) for the next
3 BMP and Outfall maintenance - Prevent vegetative matter from depositing	halls and at student orientations received	information. In addition, NSU has	reporting year in hopes of increasing
and accumulating in Stormwater Management Facilitates or draining to storm	Stormwater pollution prevention brochures.	retained the services of a private	attendance 80% to 85%. Retain the
sewer system.		consultant to design measures to	services of a private consultant to aid
A presentation on the University's conservation initiatives, including stormwater		mitigate the 3 high priority water	in a presentation to staff to further
pollution prevention will be presented to the grounds staff, students and other		quality issues.	educate them on the importunate of
interested parties, to increase awareness of stormwater and pollution prevention			proper maintenance to protect the
measures and High Priority Water Quality Issues. This includes understanding of			storm sewers.
the differences between stormwater and sanitary sewer systems and will be			
presented annually.			

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
1B. The University's website is a source of information on the numerous	To provide the public with easy access to	The 2017 MS4 Report is currently	Continue to post Annual Report and
programs. Among the topics under Facilities Management is information on	basic information on the various aspects of	available on the University's Website -	Program.
pollution prevention and stormwater management. (Additional links to other	the University's concern for the natural	https://www.nsu.edu/getattachment/A	Stormwater Management Website is
local programs and the City of Norfolk initiatives aimed at improving water	environment. The program and annual	bout/Administrative-Offices-	Pending review and approval 2019.
quality are to be incorporated.)	report will be posted annually.	Services/Facilities-	
		Management/Departments/Environme	
		ntal-Health,-Safety,-and-Risk-	
		Management/2017-MS4-Annual-	
		Report.pdf.aspx	
		A copy of the 2017 MS4 Annual Report	
		and Program Plan will be uploaded	
		when completed. A technical staff	
		member was utilized to upgrade the	
		departments current site. A draft copy	
		of both the department website as well	
		as the additional Stormwater	
		Management website was submitted as	
		part of the 2013 Annual Report. The	
		draft has not yet been approved due to	
		administrative changes.	
1C. Post stormwater pollution prevention information in the NSU Spartan E-	One to Two page ad type inclusion to reach	NSU has a the Spartan E-Daily Web	University staff plan to work with
Dailey Email.	student body, staff, and faculty on a semi-	Email. The University Email covers a	Spartan E-Daily staff to developing
	annual basis.	variety of topics, including sports,	articles to include during the next
		future events, guest speakers, and	permit year.
		political topics of interest. In 2018, no	
		stormwater pollution prevention topics	
		were covered.	

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
1D. NSU's Director of Environmental Health, Safety and Risk Management Office and University Architect and Inspectors to take DEQ E&S Inspector Course and obtain certification. (Land disturbance construction sites)	NSU's Director of Environmental Health, Safety and Risk Management Office and University Architect to take the DEQ E&S and Stormwater Inspector Courses and corresponding examinations as per the Annual Standards and Specifications.	The University Architect has completed the DEQ Combined E&S and Stormwater Management Courses in the 2017-2018 reporting year. The University Architect is scheduled to take the Combined Stormwater Exam in October and Combined E&S Exam in late 2018.	University Architect to apply for and take corresponding exams and maintain any required certifications.
1E. Stormwater pollution prevention brochures are to promote interest in protecting the natural environment of the campus and related wetlands and rivers.	After approval by senior management, the brochures are to be printed in sufficient volume for the campus community. The brochures shall be available at strategic locations on campus.	The distribution of brochures has been done. A copy of the final version was submitted as part of the 2013 MS4 Report and has not changed since.	Continue to distribute to the students as outlined.
1F. Students have been invited to assist with attaching storm drain markers to stormwater inlets. This project will depend on weather conditions, and the students' academic schedules.	To encourage student/faculty/staff participation and recognition of the stormwater management system. This task will be performed until all inlets on campus have a marker.	100 markers were installed by a consultant in June 2011. The condition of the markers was verified. Approximately 7 new markers are required for structures that have been repaired and/or replaced and is scheduled to take place in late 2018.	Inspect all the markers and replace with new markers if damaged or missing.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
1G. Preparation of a SWPPP (Stormwater Pollution Prevention Plan) for the University's Maintenance Facility .	Norfolk State University has retained the services of a private consultant for the preparation of a SWPPP (Stormwater Pollution Prevention Plan) for the Maintenance Facility that identifies methods for the prevention of sediment and pollutants from entering the storm sewer system. The concern is controlling any sediment, debris and oils from potentially entering the storm sewer system. The SWPPP identifies methods for the prevention of sediment and pollutants from entering the storm sewer system.	Preparation of the SWPPP has been completed as of September 2015 and has been implemented.	Maintain SWPPP documents and update as required based on updates from DEQ.
1H. Design of new Bus Wash Facility for the University's Maintenance Facility.	Norfolk State University has retained the services of a private consultant for the design of a new Bus Wash Facility for the University's Maintenance Facility. The concern is controlling any oils and grease from potentially entering the storm sewer system.	This will be addressed with the installation of a new drop inlet that is tied to the sanitary system. As buses are washed the Inlet structure will be opened via a hatched cover, where wash water from the buses can be collected and sent through the sanitary sewer system. When washing is complete the hatch cover of the inlet is closed, so storm events can pass by the structure and drain to the storm system. Planning, design, and construction completed in late 2016. Review of functionality has taken place and needed corrective pavement modifications are currently underway that will allow the new hinged hatch covered drain inlet to be more efficient at capturing bus wash water.	Oversee modifications of the pavementt within the facility. Continue with Inspection and cleaning per the SWPPP.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year

Minimum Control Measure #2: Public Involvement/Participation

This measure requires the University to encourage the public to become involved in the protection of stormwater runoff and related sewer systems. As a State University and a campus open to the general public, NSU has provided program basics on its website, conferred with faculty, and made presentations to students. Multiple BMPs are associated with this Minimum Control Measure. All BMPs defined under this measure were implemented during the first permitting year and continuously since that time, unless specifically stated otherwise.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
2A. Students will be invited to participate in a tree planting program.	To encourage student/faculty/staff	The Tree Planting Program was not	Plan out a new area to implement
	awareness and participation to provide soil	participated in during the 2017-2018	the program and advertise on
	stabilization, reduce heat island effect,	permit year.	Spartan E-Daily to increase student
	sediment and pollution from getting in		group involvement.
	storm drains. This will occur annually.		
2B. Prepare for Earth Day Activities.	Students will be encouraged to participate	The University did not have an Earthday	Schedule events for Earth Day for
	and attendance will be taken. This process	activity for the reporting year.	the upcoming year.
	will occur annually and was started in 2013.		

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
2C. The University's website is a source of information on the status of the MS4	To annually provide public access to the	The 2017 MS4 Report is currently	Continue to post Annual Report and
Program and all annual reports. Make copies of reports available on website.	permit via the University's website. Increase	available on the University's Website -	Program.
	their knowledge of stormwater regulations	https://www.nsu.edu/getattachment/A	Stormwater Management Website is
	and NSU's efforts to improve the local water	bout/Administrative-Offices-	Pending review and approval in
	quality.	Services/Facilities-	2019.
		Management/Departments/Environme	
		ntal-Health,-Safety,-and-Risk-	
		Management/2017-MS4-Annual-	
		Report.pdf.aspx	
		A copy of the 2017 MS4 Annual Report	
		and Program Plan will be uploaded	
		when completed. A technical staff	
		member was utilized to upgrade the	
		departments current site. A draft copy	
		of both the department website as well	
		as the additional Stormwater	
		Management website was submitted as	
		part of the 2013 Annual Report. The	
		draft has not yet been approved due to	
		administrative changes.	
2D. Involvement/Participation of Public, Students and Staff: Conduct a	To increase Public, Student and Staff	Housekeeping and grounds employees,	Update presentations for staff and
presentation on stormwater pollution prevention to Facilities Management Staff	awareness of stormwater and pollution	of which 76, (50%) attended, received	students and other interested
and Students.	prevention measures. This includes	training on 2/14/18 and 7/25/17.	parties. Continue training in next
	understanding of the differences between	Additionally, approximately 400	reporting year.
	stormwater and sanitary sewer systems and	students in residence halls and student	
	allowable discharges, and will be conducted	orientations received Stormwater	
	annually to biannually.	pollution prevention brochures.	

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year		
Minimum Control Measure #3: Illicit Discharge Detection and Elimination					
This measure requires the University to detect and eliminate illicit discharges into	the MS4. The University is aware of potentia	I sources of illicit discharges and has mad	e their elimination a high priority.		
The following discharges are exempt from discharge prohibitions established by t	his Minimum Control Measure:				
 Water line flushing or other potable water sources 	Water line flushing or other potable water sources				
 Landscape irrigation or lawn watering 					
Diverted stream flows					
Rising ground water					
 Ground water infiltration to storm drains 					
 Uncontaminated pumped ground water 					
• Foundation or footing drains (not including active groundwater dewatering syst	ems)				
Crawl space pumps					
 Air conditioning condensation 					
• Springs					
 Natural riparian habitat or wetland flows 					
 Swimming pools (if de-chlorinated - typically less than one PPM chlorine) 					
• Fire fighting activities					
 Any other water source not containing Pollutants. 					
Materials used by the equipment maintenance staff, vegetative nutrients, housel	eeping cleaning solvents, chemicals used in a	cademic and research laboratories have b	een identified as potential pollutants.		
Separate procedures have been established for each of these exposures. Multiple	BMPs are associated with this Minimum Con	trol Measure. All BMPs defined under this	measure were implemented during		
the first permitting year and continued since that time, unless specifically stated	otherwise.				
Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year		
3A. Equipment maintenance: As much as possible, motorized unlicensed	To make equipment operators more	Active. Grounds personnel are trained	Continue plan as is but reinforce it		
equipment will be stored under a shed roof to help minimize the amount of	accountable for the cleanliness of the	in keeping debris out of stormwater	with the development of more		
stormwater runoff from the equipment. This equipment can develop lubricant	equipment and reduce the possibility of	drains. A roof was installed over	specific procedures to clarify		
and fuel stains which could produce sheen on waters entering stormwater	petrochemical residue and debris entering	equipment in maintenance yard to	employee responsibilities.		
drains. Accumulations of grass clippings, leaves, dirt and loose debris are to be	the stormwater sewer system. Operators	prevent any oils from equipment			
removed from the equipment, and swept up to prevent their inadvertent entry	will adhere to policies outlined in this plan.	entering storm sewers during rain			
into stormwater inlets.		events. In addition, the various fluid			
		product cabinets have been removed			
		from the yard.			

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
3B. Motor vehicle refueling: The University has an underground gasoline storage tank for use in state vehicles. Refueling most of those vehicles is performed by the vehicle maintenance staff who have been instructed not to "top-off" the vehicle tank for fear of overflow and spilling onto the pavement. To help prevent incidents, the nozzle has been replaced with one that will close automatically; access to the hose is restricted by locking the nozzle in place, turning off the gasoline pump and restricting refueling to a few hours in the morning when the mechanic is available to oversee the procedure.	Prevent gasoline from entering the stormwater drains, staining the pavement and reducing the risk of fire. The University will ensure that no unauthorized use of the gasoline tank will occur.	Active	Continue plan as is.
3C. Vegetative nutrients: The University has contracted with a consultant to assist with a nutrient management program. The program includes soil tests, assessments of vegetation and specified application amounts.	To maintain healthy lawns and plantings while reducing spillage on pavements that can enter stormwater inlets and adversely affect marine life.	The nutrient plan has been updated and approved by DCR in August 2017. The plan will be active through 2019. It is implemented and kept with the program records.	Apply and maintain new nutrient management plan.
3D. Dumping: Develop procedures to detect and address non-stormwater discharges, including illegal dumping, will include the University Police patrolling the campus and the presence of facilities groundskeepers, tradesmen and shuttle bus drivers. These individuals are to report observations and incidents that could result in illicit discharges, or conditions that could result in non-stormwater contamination. In addition to these detection methods, the main outfall from campus has a large screen that prevents solids from entering connecting sewers. The University will coordinate with the city to assure this structure remains functional.	To prevent illegal dumping from entering the stormwater drains, which could impair water quality. Incidents of dumping will be documented and provided.	NSU grounds staff and Campus police patrol the campus regularly. No illicit discharges were reported. The draft policy for Illicit discharge is still being reviewed and considered by the University and is expected to be incorporated in 2019.	Continue monitoring. Initiate and maintain the formal policy, if the draft policy is approved. Amend policy if required and resubmit changes to DEQ for review and approval.
3E. Penalties: A policy proposal shall be drafted addressing the seriousness of illicit discharges on campus, and explaining the possible adverse impact of hazardous materials on the natural environment. The policy shall apply to all members of the campus community and visitors. Technical and legal reviews will be involved and may specify assessments of penalties by a faculty or student conduct board.	If approved, the policy would be made public through an extensive advertising campaign and a "grace" period clearly stated for all to become aware of the policy.	The draft policy is still being reviewed and considered by the University and is expected to be incorporated in 2019.	Initiate and maintain the formal policy, if the draft policy is approved. Amend policy if required and resubmit changes to DEQ for review and approval.
3F. Removal of grease and oil accumulations from parking lots will require the use of pressure-washing, deployment of petrochemical absorbents around the cleanup site and in front of any affected stormwater inlets.	To prevent illicit discharges from entering the University's stormwater system.	No incidents were reported in the 2017- 2018 reporting year.	Continue to monitor parking lot areas.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
3G. In the event that an illicit discharge is identified, it will be reported to DEQ in the Annual Report.	To prevent illicit discharges from entering the University's stormwater system. Identified illicit discharges will be reported annually.	No incidents were reported in the 2017- 2018 reporting year.	Continue plan as is.
3H. Dry weather Screening. Stormwater Outfall inspection: This section includes details on how to find an illicit discharge in the field and the appropriate laboratory strategies to identify particular pollutants. The Outfall Reconnaissance Inventory (ORI) is the most proven method for screening campus stormwater outfalls. The ORI consists of walking all of the campus outfalls to document where they are and their condition. The field team should be able to find where continuous and intermittent stream flows exist. They will take note of any outfalls with discharges of very high turbidity, strong odors, unnatural colors or an extreme case of pH on a field litmus test strip. When obvious discharges are found, the field crew will take note and start working upstream to find where the source is and eliminate it. While traversing the campus, field crews should be looking for other more common illicit discharges like oil spills, un-permitted car washing or other harmful liquid spills. If these are encountered the appropriate abatement agency should be notified. The following table provides a step by step process for conducting an ORI.	To identify potential illicit discharges that could impair water quality. All outfalls to be inspected and inspection checklist kept onsite. All campus outfalls will be initially inspected by the end of the third permit year and quarterly thereafter. Inspections will be documented.	The 11 Outfalls were inspected with no major incidents reported. It was recorded that regular maintenance of overgrown vegetation was needed to be cut back and removed. Inspection Reports have been completed and recorded in the program.	Continue plan as is.
3I. Students have been advised not to change any of the fluids used in their motor vehicles while on campus. These include motor oil, transmission fluid, anti freeze, gasoline or diesel and windshield washer fluids.	To minimize the accumulations of drippings and stains in parking lots and campus streets that can become part of stormwater runoff. The campus will be reminded electronically each semester.	No incidents were reported in the 2017- 2018 reporting year.	Continue plan as is.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
3J. A list of any written notifications of physical interconnection given to other MS4 holders.	To make adjoining MS4 entities aware that there is interconnecting storm systems.	City of Norfolk is the only interconnected MS4 entity. Written notification was sent out to the Environmental Programs Manger - June Whitehurst on September 28, 2015.	Issue new notification if changes in interconnected MS4 should occur.
Minimum Control Measure #4: Construction Site Stormwater Runoff Control			
The University has adopted state mandated procedures to reduce pollutants in st permittees address the situation of another government entity being held respon oversight has passed to the Department of Environmental Quality as of the issuar management plans reviewed by DEQ; however, DEQ will does not review Erosion	ormwater runoff from entering the stormwate sible for the permittee satisfying some of the ce of the General Permit June 30, 2013. Public and Sediment Control Plans. The two options	er inlets on campus during construction p state permit requirements. Virginia Storn c institutions of higher education will con for Erosion and Sediment Control review	rojects. The permit requires that nwater Management regulatory tinue to have stormwater are: implementation of an internal
Erosion and Sediment Control review process, or review by the locality. NSU has r	eviewed both options and will submit Erosion	and Sediment Control Plans to the City of	f Norfolk for review.
Dranged DMD	Macourable Cool and Effectiveness	Compliance Status	Diana for Nout Dormit Voor
4A. Maintain compliance with Virginia Erosion and Sediment Control and Stormwater Laws for Construction projects: Included in affected projects with a general contractor, is a section dedicated to slope protection and erosion control.	To adhere to all laws for erosion, sediment control, and stormwater management. The University Architect will perform inspections to ensure compliance.	Requirements for complying with Virginia E&S are specified in contract including protection of slopes and erosion control. In addition, NSU has had Annual Standards and Specifications (AS&S) prepared, which describe the University's procedures for all land disturbance projects. The AS&S document has been submitted and approved by DEQ during the 2017 permitting year. The AS&S is currently being updated and will be submitted to DEQ in late 2018. The updated document will be included with next years annual report and is kept with the MS4 Program.	Continue plan as is.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
4B. The University holds the general contractor responsible for maintaining the job site to the satisfaction of the University and all applicable regulations.	To provide a safe working environment and eliminate damages to the environment. This will be included in the inspection and documented within the MS4 Program records.	The general contractor is held responsible for the entire project and applicable regulations via their contract with the University. No incidents observed or reported.	Continue plan as is.
4C. The contractor is required to schedule work in a manner that best provides slope protection and erosion controls by installing grass, ditches or other means to prevent runoff into stormwater drains.	To prevent erosion on the construction site. This will be included in the inspection and documented.	The general contractor has coordinated their tasks to minimize erosion and slope protection with the use silt fences and vehicle traffic control.	Continue plan as is.
4D. The contractor must clean out any drains that become contaminated with construction site runoff.	To eliminate future contamination of stormwater entering previously contaminated drains on an as-needed basis. Documentation of cleaning will be provided.	No drains were adversely affected during the 2017-2018 reporting year.	Continue plan as is.
4E. The contractor will be responsible for any damage to streams or other natural areas or wetlands by the addition of soil, rock, or topsoil, whether deposited by poor construction practice, sedimentation, or wind, and vegetation matter such as whole trees or any part thereof, or remnants from burning or other clearing processes, and waste construction materials such as concrete, broken pipe, equipment parts and any other additions which could be detrimental to said areas.	To protect the surrounding areas from damage due to poor construction practices. The University Architect will perform inspections to ensure compliance and will enforce penalties as needed.	The contractor has been held responsible for minimizing any impact on the local natural features. Waste construction materials were controlled. No incidents observed.	Continue plan as is.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
4F. Any damages will be assessed by the University based on site inspections.	To eliminate and repair damages to the	NSU's Director of Environmental Health,	Continue plan as is. Update any
Currently the City of Norfolk's Environmental Division inspect projects with land	surrounding areas. Inspections will take	Safety and Risk Management Office has	certifications as required.
disturbance every 5 business days and after rain events. The contractor will act	place every 5 business days and after rain	completed the E&S and Stormwater	
as soon as possible to prevent further damage and correct existing damage at no	events (to be compliant with MS4 Permit -	Inspector Courses. The University	
cost to the University. Should the University choose to do so, a remediation	TMDL requirements) and damages will be	Architect has completed the DEQ E&S	
contractor will correct the damage and their fees deducted from the contractor's	reviewed and assessed by the University as	and Stormwater inspector, reviewer,	
payment.	needed.	and administrator training courses and	
		is scheduled to take exams in October	
		and December. As part of the Annual	
		Standards and Inspections the	
		University provide inspections for	
		Campus projects. No remediation	
		contractor was required in the permit	
		year.	

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
4G. The contractor will anticipate site inspections by the erosion and sediment	During the 2017-2018 reporting year, the	In the 2017-2018 reporting year, the	Continue plan as is.
control reviewing authority (City Inspector and University Architect).	transition of inspections from the City of	City of Norfolk's Environmental Division	
Current projects requiring SWPPP and University Inspections of E & S Measures:	Norfolk's Environmental Division to the	inspected the Brown Hall construction	
Brown Hall Building and Site Improvements, Residential Facility, and Synthetic	University Architect took place. Inspections	project a reported 10 times. The	
Turf Football Field.	were performed by the City of Norfolk's	University Architect inspected the	
	Environmental Division through September	Residential Facility construction project	
	2017, at which point the University	a reported 4 times. The Synthetic Turf	
	Architect performed inspections and	Football Field construction project only	
	recorded the proper documentation.	required limited inlet protection and	
		protected construction access (in a	
		highly visible location on the campus),	
		which was maintained for the minimal	
		duration of the project. No inspection	
		reports were created for the synthetic	
		turf field project; however, the project	
		was closely overseen by the University	
		Architect and project consultant, with	
		no issues to report. Recorded	
		inspection reports are included with	
		this years annual report and will be	
		kept in the program records.	
4H. The inspector for the erosion and sediment control reviewing authority will	To ensure all areas of the site are properly	The City Inspector and University	Continue plan as is.
be allowed access to all areas of the construction site.	monitored and examined. The inspector will	Architect has had full access to all	
	document all considered locations.	sectors of the construction site.	

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
4I. All conditions or practices noted by the inspector, that could result in deteriorated slope protection or erosion control, will be immediately corrected.	To prevent damage to the construction site, the inspector will document damages and take immediate action.	The general contractor has been responsive to requests from the City Inspector and University Architect. Minor comments were noted and addressed within the required time frames. The University Architect is handling follow up inspections.	Continue plan as is.
4J. If the inspector for the erosion and sediment control reviewing authority submits a report to the University or contractor, all infractions or penalties will be addressed by the contractor at no expense to the University.	To make the contractor liable for all infractions and penalties caused by damages. The University will document all infractions and penalties.	No infractions or penalties were recorded.	Continue plan as is.
4K. At the agreed conclusion of a project, all temporary erosion control systems will be removed, and inspection of adjacent stormwater inlets and drains conducted. The contractor will remove all materials, sediment or vegetation that has entered due to activities related to the construction project when approved to remove measures by the inspector.	To ensure proper clean-up of site upon completion and removal of erosion control systems. Inspection documentation will be provided.	The new Brown Hall Building project started in 2015 and is expected to be completed late 2017, with final site work completed in late 2018. The new Residential Facility began construction in the spring of 2018 and is expected to have construction completed in late 2019. The Synthetic Turf Field project began construction in the summer of 2018 and was completed and fully stabilized within 2 months with no reported issues. All erosion control measures for active projects shall be installed and maintained until the site is stabilized and inspectors have signed off that measures can be removed, with the site paved, and a plantings/grass lawn installed as specified.	Continue plan as is.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
4L. For sites in excess of 2500 sf, the contractor will ensure compliance with all the requirements of VR 680-14-19 (VSMP).	Inspections will ensure the contractor follow requirements.	The general contractor has demonstrated compliance with the requirements of the contract. Regular inspection by the University Architect shall continue to maintain compliance.	Continue plan as is.
4M. The University reserves the right to require all architects, engineers and related consultants to obtain appropriate certifications as specified under the Erosion and Sediment Control law.	The University shall request to receive documentation of appropriate certifications.	Appropriate documentation and certifications have been provided as requested.	Continue plan as is.
4N. Contractor will provide the University with legible copies of all correspondence, reports, meeting minutes, etc. that involve stormwater issues.	The University will review all stormwater practice correspondence.	Site inspection reports submitted by inspectors have been reviewed and kept in file.	Continue plan as is.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
Minimum Control Measure #5: Post-Construction Stormwater Management in N	lew Development and Re-Development		
The University will develop, implement and enforce procedures to address storm	water runoff from completed construction site	es. Multiple BMPs are associated with thi	s Minimum Control Measure. All BMPs
defined under this measure will be continued to be implemented each permit yea	ar.		
Proposed BMP		Compliance Status	Plans for Next Permit Year
5A. Compliance with Virginia Erosion and Sediment Control and Stormwater	To prevent pollution of stormwater and	These items are required within the	Continue plan as is.
Laws:	maintain healthy waterways. The inspector	construction contracts for all current	
• The location, size and routing of stormwater will be designed, approved and	will ensure all new erosion and sediment	and new construction on campus.	
constructed in accordance with existing regulations. Tie-ins to existing structures	control processes will be properly		
will be permitted if engineering studies can prove that such configurations are	documented and approved.		
within current capacities and do not inhibit severe stormwater flows.			
 The University will implement strategies that include structural and 			
nonstructural best management practices appropriate for the campus and			
surrounding environments. In contracts with consultants, emphasis will be			
placed on replicating pre-construction runoff characteristics and site hydrology.			
Among the prominent concerns are the runoff from local city streets and the			
outfalls from the campus.			
Any additional maintenance requirements of the new structure will be assigned to the respective tradesmen. If warranted, formal proventive maintenance			
procedures will be scheduled and modified as warranted by experience			
efficiency and employee safety			
Work orders and inspections of stormwater structures will be documented and			
copies sent to the Office of Environmental Health. Discrepancies will be			
recorded and corrective measures identified, performed and documented.			
Timely completion of these functions will be a factor in the tradesmen's			
performance appraisals.			
 New construction activities will secure a VSMP permit. 			

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
5B. Outside consultants have been scheduled to conduct inspections of campus stormwater basins. Inspections are documented and include clearing of soil/sand, removal of debris, checks for erosion, reporting of sheen in standing water, and the removal of leaves and floating debris. Periodic inspections will be added to the preventive maintenance list.	To verify basins are clean and capable of retaining and draining. This will be done quarterly and documentation will be provided.	These items are required within the construction contracts for all current and new construction on campus.	Continue plan as is.
5C. Develop a Stormwater Master Plan: For State owned property, stormwater regulations are determined and enforced at the State level by the Virginia Department of Environmental Quality (DEQ). The Master Plan was developed to ensure compliance with current regulations.	To supplement the Current Campus Master Plan by providing a guideline for development on campus, and updating it as projects are completed. A copy can be provided upon request.	The University has retained a consultant to assist with updating the existing campus storm water master plan for the campus which includes specific directions for current and future stormwater best management practices. The stormwater master plan was submitted to DEQ in the summer of 2018. Comments were received that will be addressed and the master plan will be resubmitted in late 2018.	The proposed Comprehensive Stormwater Master Plan for Norfolk State University shall be updated to conform with new regulations. A formal re-submittal of the updated Campus Comprehensive Stormwater Master Plan will be submitted to DEQ for review by late 2018. Update the master plan as projects come on line and include updates in the 2019 MS4 Annual report.
5D. Develop a Stormwater Management Facility Record to include: Treatment area, type of BMP, and Hydrologic Unit Code. Should also include inspection reports and checklist.	Create a plan that will be continuously updated with new construction projects and new SWMF. This plan will be updated and submitted with the annual report.	See Appendix A below for a list of current BMPs on campus. NSU has retained the services of a consultant to assist with the preparation of a SWMF Record documents and map. Inspection reports have been completed and kept with the program records.	Update SWMF Record for any changes to existing BMP facilities and incorporate new BMP facilities as they come on line. Adjust and perform inspections respectively.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
Minimum Control Measure #6: Pollution prevention/good housekeeping for mu	nicipal operations		
The University has been performing functions that contribute to the prevention o stormwater pollution include oil/grease stains in parking lots, fuel spills, lawn & g documentation, training and expansion in some areas will contribute to an increa defined under this measure will be implemented beginning in the first permit yea	f pollutants from entering stormwater inlets a arden nutrients on pavement, exposed bulk st se in the efficiency of the overall program. Mu r.	nd adversely affecting the natural environ orage piles and common floatable trash. Itiple BMPs are associated with this Minin	nment. Potential sources of It is recognized greater num Control Measure. All BMPs
Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
6A. Development and Implementation of Dailey Operation Procedures	Eliminate sources of illicit materials polluting surface waters. Dailey Good House keeping procedures are included in the new Facilities Maintenance SWPPP.	Preparation of the SWPPP containing Good House Keeping Procedures completed in September 2015 is being implemented. A copy will be kept in the program records.	Continue plan, update SWPPP as required based on updates from DEQ.
6B. Development and Implementation of required SWPPPs	Norfolk State University has retained the services of a private consultant for the preparation of a SWPPP (Stormwater Pollution Prevention Plan) for the Maintenance Facility that identifies methods for the prevention of sediment and pollutants from entering the storm sewer system. The concern is controlling any sediment, debris and oils from potentially entering the storm sewer system. The SWPPP identifies methods for the prevention of sediment and pollutants from entering the storm sewer system.	Preparation of the SWPPP for Brown Hall has been completed as of September 2015 and has been implemented. Preparation of the SWPPP for the Synthetic Turf Football Field project has been completed as of June 2018 and has been implemented. The project SWPPP is included with this Annual Report. The project has been completed and stabilized. Preparation of the SWPPP for the Residential Facility has been completed as of June 2018 and has been implemented. The project SWPPP is included with this Annual Report.	Maintain SWPPP documents and update as required based on updates from DEQ.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
6C. Development and Implementation of turf and landscape Nutrient	Maintain the minimum appropriate levels of	The nutrient plan 2017-2019 was	Continue to follow and maintain the
Management Plan. The University has chosen to select a consultant from a list,	fertilizers and to prevent excess from	updated and submitted in 2017 and is	Nutrient Management Plan.
originally provided by the DCR. After soil conditions have been sampled and	entering storm sewer system and causing	included in the Program Plan. NSU	
tested, specific fertilizer mixes will be administered by the University to maintain	downstream pollution. Nutrient	currently has 12.88 Acres of athletic	
the lawns and flower beds. The application of fertilizers and herbicides will	Management is applicable for all locations	field turf and decorative landscaped	
strictly follow the recommendations provided by the consultant, and will be fully	containing turf and or planted areas within	areas that 100% is accounted for in the	
documented. Those employees assigned to apply the fertilizers and herbicides	the University.	nutrient management plan.	
will be certified to perform those tasks.			
6D. Required Employee Training	Increase staff awareness and procedures for	NSU's Director of Environmental Health,	Continue plan as is.
	stormwater and pollution prevention	Safety and Risk Management Office has	
	measures.	represented multiple training seminars	
		for in-house training of Facilities	
		Maintenance Staff with regard to	
		Stormwater Pollution Prevention and	
		Good Housekeeping. The Training	
		Calendar of events and topics of	
		discussion are filed in the Program Plan.	
		Stormwater Pollution and BMP	
		Maintenance training was held on	
		2/14/18, and 7/25/17. 83, Grounds	
		Staff Members (50%) attended and	
		received training. The Director and	
		University Architect have completed	
		the DEQ Combined Administrative,	
		Erosion and Sediment Control and	
		Stormwater Management Courses	
		during the 2016/2017/2018 permit	
		year. The University Architect is	
		scheduled to take the Combined	
		Stormwater examination in October	
		2018 and the Combined Erosion and	
		Sediment Control Exam in late 2018.	

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
6E. Tradesmen have been instructed to immediately cleanup releases of any materials they are using and report any quantity that may have entered the stormwater sewer system.	Increase awareness for stormwater runoff and eliminate sources of illicit materials polluting surface waters.	Requirements added to work profile.	Continue plan as is.
6F. Groundskeepers have been instructed to pick-up debris and floatables to prevent shredding by lawn mowers and entering the stormwater sewer system.	Reduce the amount of pollutants in the stormwater, and promote the free flowing of stormwater in the sewer lines.	Requirements added to work profile.	Continue plan as is.
6G. Absorbent materials are kept available, and a fully enclosed hazardous materials storage shed is used for the staging of hazardous wastes, including contaminated absorbents and personal protective equipment.	Tradesmen and faculty to store hazardous wastes isolated from the weather and unauthorized personnel. Documentation of the location of the storage shed will be provided.	Completed. Storage shed is in the southeast corner of lot #4.	No further plans.
6H. Creation of a Hazardous Substance Policy: The discharge of hazardous substances or oil into the stormwater sewers has been prevented through the creation of a hazardous materials policy. The policy includes the periodic removal of hazardous wastes from the academic chemistry, biology and medical laboratories, along with chemical wastes from the research facilities. Hazardous substances and wastes from facility maintenance operations are controlled by storing the materials in flammable storage cabinets, keeping a limited amount on campus, and using an approved hazardous waste hauler to over pack stale or contaminated cans, bottles, etc. Temporary storage on campus is within a specially manufactured hazardous material shed until transport to a recycler, incinerator or approved landfill can be arranged by the hazardous waste transporter. Reporting, response and disposal requirements have been explained to staff as part of the Hazard Communication Training required by OSHA Standard 29 CFR 1910.1200.	Prevent hazardous materials from entering the University's stormwater sewer system and other downstream waters. A copy of this policy will be submitted.	Proposed F.M. Policies 49.03.08- 49.03.12. The proposed policy is in draft form and must be routed through the management ranks for approval. It is expected to be approved in 2019	Copies of approved policy will be forwarded once approved.
6I. Emergency generators, boilers, and hot water heaters have been converted to natural gas.	Prevent hazardous materials from entering the University's stormwater sewer system and other downstream waters.	Boilers and hot water heaters have been converted to natural gas. All emergency generators are powered by natural gas with the exception of one generator at the McDemmond Center which is powered by diesel fuel.	No further plans.

Proposed BMP	Measurable Goal and Effectiveness	Compliance Status	Plans for Next Permit Year
6J. A company with expertise in hazardous materials has been contracted to provide emergency response to incidents requiring additional resources and equipment. They have the added responsibility of over packing primary containers and arranging for transportation to approved disposal sites, recyclers or incinerators.	Assure a release is adequately contained and remediated, storm drains are protected, staff personnel do not become contaminated and disposal protocols are strictly followed.	Semi-annual hazardous material removal completed.	Continue plan as is. Documentation will be provided if necessary.
6K. All trash receptacles will be emptied and refilled with new trash bags when they become full, after the event ends and after the crowds leave. All stormwater inlets in the general area of the events will be checked and trash of all types removed from the inlet. An estimate of the amount of trash collected will be recorded and sites of the greatest accumulations noted.	Reduce the amount of pollutants in the stormwater.	Post event inspections to be scheduled with staff.	Continue plan as is.
6L. Exterior storage: Certain material storage practices include bulk piles of mulch, topsoil, sand and salt. It was recognized that heavy rains can cause the loose materials to flow into street gutters and eventually into stormwater inlets. Currently salt (for icing conditions) and urea fertilizer are received in bags and stored in a grounded storage container. If other lawn and garden supplies cannot be purchased in bags, then provisions will be considered to store such materials under an impervious cover.	Reduce the amount of pollutants in the stormwater. Norfolk State University has retained the services of a private consultant to design for a new series of storage bays for bulk material storage. The design will include adequate containment to prevent materials from spreading out side of the storage bay area.	Construction was completed in late 2016. Maintenance and inspection shall take place as required per the SWPPP for the Maintenance Facility.	Continue with Inspection and Cleaning per the SWPPP.
6M. Education of Staff: Conduct a presentation on stormwater pollution prevention to Facilities Management Staff and have staff complete pollution prevention training.	Increase staff awareness of stormwater and pollution prevention measures and proper BMP and Outfall maintenance. This includes understanding of the differences and appropriate maintenance between the various stormwater BMP types on campus.	Stormwater Pollution and BMP Maintenance training was held on 2/14/18, and 7/25/17. 76, Grounds Staff Member (50%) attended and received training.	Continue plan as is.
6N. Development of on-site BMP Maintenance and Inspection Procedures.	Increase staff awareness of stormwater and pollution prevention measures. This includes the preparation of on-site BMP Maintenance and Inspection Procedures.	On-site BMP Maintenance and Inspection Procedures have been created and implemented. Procedures are maintained within the program.	Continue plan as is. Update as necessary.



10. Notice that the operator is relying on another government entity to satisfy some of the permit obligations.

- The University receives technical and regulatory assistance from the Department of Environmental Quality. DEQ reviews individual capital improvement projects for compliance with Virginia Stormwater Management regulations. DEQ also assists in establishing requirements for the Stormwater Master Plan.

- The University reviews technical and regulatory assistance provided by The City of Norfolk Environmental Services Department for the review of Erosion and Sediment (E & S) Control Plans and E & S Control Site Inspections.

11. The approval status of any programs pursuant to section II C of the General Permit (if applicable), or the progress towards achieving full approval of these programs.

- Not applicable.

12. Regulated land-disturbing activities data tracked under Section II B 4 c of the General *Permit.*

Approximate Location	Area (Acres)
New Classroom Building (Brown Hall)	10.79 +/-
New Residential Facility	5.63 +/-
Synthetic Turf Football Field	2.04 +/-
Total	18.46 +/-

Table 1: Current Campus Land Disturbing Activities

13. All known permanent stormwater management facility data tracked under Section II B 5 b (6) of the General Permit submitted in a database format to be prescribed by the department. Upon filing of this list, subsequent reports shall only include those new stormwater management facilities that have been brought online.

- No new stormwater management facilities have been brought on line. See Table 2 below for a list of current facilities.

Approximate Location	Description	HUC
Lot 10	Retention Basin	JL 54
Spartan Suites	Infiltration Trench	JL 54
Lot 17	Detention Basin	JL 54
Lot 7	Grassed Swale	JL 54
Lot 30	Detention Basin	JL 54
Wilder Performing Arts	Grassed Swale -West	JL 54

Table 2: Current Campus Stormwater Basins



Wilder Performing Arts	Grassed Swale -East	JL 54
Hamm Fine Arts	Detention Basin	JL 54
Lots 2 and 3	Retention Basin	JL 54
Student Center	Bioretention	JL 54
Student Center	Underground Storage	JL 54

14. A list of any new or terminated signed agreements between the operator and any applicable third parties where the operator has entered into an agreement in order to implement minimum control measures or portions of minimum control measures.

- The University has a contract with Burns & McDonnell, who serve as a stormwater management consultant.

15. Copies of any written comments received during a public comment period regarding the MS4 Program Plan or any modifications.

- No written comments have been received.



- Outfall Location Maps
- Stormwater Facility Management Database
 New Project SWPPP: Synthetic Turf Field and Residential Facility
 Land Disturbance Project Inspection Reports





Norfolk State University Outfalls Locations Exhibit 1 Not to Scale







Norfolk State University

Outfalls Locations

Exhibit 2

Not to Scale

Receiving Waters from all Outfalls: Eastern Branch Elizabeth River Lower. HUC - JL54



				Norfol	k State Univers	ity Stormwater	Managemen	t Facility Da	tabase (Ope	rator Owned)			
SWMF Unique Identifier	Туре	Location (Latitude/ Longitude)	Date Implemented	Last Inspection	Quantity of Inspections Annually	Quantity of Enforcement Actions	Total Acres Treated	Pervious Acres	Impervious Acres	Receiving Waters	HUC	Receiving Waters Impaired	Applicable TMDL
Outfall 1 / Lot 10	Retention Basin	36.846428 / 76.253033	6/30/2005	9/23/2015	1		3.25	0.49	2.76	Eastern Branch Elizabeth River	JL54	Yes	Chesapeake Bay / Elizabeth River
Spartan Suites	Infiltration Trench	36.8501580/ 76.257531	6/30/2005	9/23/2015	1		1.71	0.34	1.37	Eastern Branch Elizabeth River	JL54	Yes	Chesapeake Bay / Elizabeth River
Lot 17	Detention Basin	36.850353 / 76.262378	6/30/2005	9/23/2015	1		1.08	0.22	0.86	Eastern Branch Elizabeth River	JL54	Yes	Chesapeake Bay / Elizabeth River
Lot 30	Detention Basin	36.850319/ 76.265239	6/30/2005	9/23/2015	1		1.54	0.64	0.9	Eastern Branch Elizabeth River	JL54	Yes	Chesapeake Bay / Elizabeth River
Hamm Fine Arts - North	Grassed Swale (2)	26.848036 / 76.268158	6/30/2005	9/23/2015	1		1.23	0.47	0.76	Eastern Branch Elizabeth River	JL54	Yes	Chesapeake Bay / Elizabeth River
Hamm Fine Arts - South	Detention Basin	26.847419 / 76.267342	6/30/2005	9/23/2015	1		0.84	0.2	0.64	Eastern Branch Elizabeth River	JL54	Yes	Chesapeake Bay / Elizabeth River
Lot 2 and 3	Retention Basin	36.846333 / 76.268153	6/30/2005	9/23/2015	1		0.59	0.12	0.47	Eastern Branch Elizabeth River	JL54	Yes	Chesapeake Bay / Elizabeth River
Student Success Center	Bio Retention	36.8486 / 76.262544	4/1/2010	9/23/2015	1		1.23	0.25	0.98	Eastern Branch Elizabeth River	JL54	Yes	Chesapeake Bay / Elizabeth River
Student Service Center	Underground Stormwater Detention	36.8486 / 76.26254	1/1/2014	9/23/2015	1		1.36	0.28	1.08	Eastern Branch Elizabeth River	JL54	Yes	Chesapeake Bay / Elizabeth River
Nursing Classroom	Grassed Swale	36.847831 / 76.264339	1/1/2014	9/23/2015	1		1.06	0.79	0.27	Eastern Branch Elizabeth River	JL54	Yes	Chesapeake Bay / Elizabeth River

DEPARTMENT OF ENVIRONMENTAL QUALITY CONSTRUCTION ACTIVITY OPERATOR PERMIT FEE FORM

(Please Type or Print All Information)

Instructions: Applicants for a Construction Activity Individual Permit are required to pay permit application fees. Fees are also required for registration for coverage under a Construction Activity General Permit. Fees must be paid when applications for state permit issuance, reissuance, modification or transfer are submitted. Applications will be considered incomplete if the proper fee is not paid and will not be processed until the fee is received.

The fee schedule for state permits is included with this form. Fees for state permit issuance, reissuance, maintenance, modification and transfer are included. Once you have determined the fee for the type of application you are submitting, complete this form. The original copy of the form and your check or money order payable to "Treasurer of Virginia" should be mailed to:

Department of Environmental Quality Receipts Control P.O. Box 1104 Richmond, VA 23218

A copy of this form and a copy of your check or money order should accompany the permit application (or registration statement). You should retain a copy for your records.

Construction Activity Operator:

Name: R.A.D. Spo	rts				
Contact: James Dohe	erty				
Mailing Address: 171	VFW Drive				
City: Rockland		State:_State:_State:	Zip:(02370	Phone: 781-871-4400 Ext.205
Email address (if availa	ble):jpd@radsports	.com			
Name and Location of	f the Construction Act	tivity:			
Name: Norfolk Sta	te University, Will	iam Price Synth	etic ⁻	Furf Foo	tball Field
City: Norfolk			State:	VA	Zip: 23504
County:					
Type of State Permit: (from Fee Schedule)	Construction Activ	ity Individual Permit		X Cons	ruction Activity General Permit
Type of Action:	X New Issuance	Reissuance		Maint	enance
	Modification	Transfer			
Amount of Fee Submi	itted (from Fee Schedu	ie):_ \$2,700.00			
Existing General Pern	nit Registration Numb	er (if applicable):	N/A		
	FOR DE	Q USE ONLY			
Date:		DC #:			

CONSTRUCTION ACTIVITY PERMIT FEE SCHEDULE

A. Individual Permits. The fee for filing a state permit application for a Construction Activity Individual Permit issued by the Board is as follows: (NOTE: Individual permittees pay an annual permit maintenance fee instead of a reapplication fee. The permittee is billed separately by DEQ for the annual permit maintenance fee.)

TYPE OF STATE PERMIT	ISSUANCE
Individual Permit for Discharges from Construction Activities	\$15,000

B. Registration Statements. The fee for filing a state permit application (registration statement) for coverage under a Construction Activity General Permit issued by the Board, including a state or federal agency that does not administer a project in accordance with approved annual standards and specifications, is as follows:

TYPE OF STATE PERMIT	ISSUANCE
General / Stormwater Management - Small Construction Activity/Land Clearing (Areas within common plans of development or sale with land-disturbance acreage less than one acre)	\$290
General / Stormwater Management - Small Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than one acre and less than five acres)	\$2;700)
General / Stormwater Management - Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than five acres and less than 10 acres)	\$3,400
General / Stormwater Management - Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than 10 acres and less than 50 acres)	\$4,500
General / Stormwater Management - Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than 50 acres and less than 100 acres)	\$6,100
General / Stormwater Management - Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than 100 acres)	\$9,600

The fee for filing a state permit application (registration statement) for coverage under a Construction Activity General Permit issued by the Board for a state or federal agency that administers a project in accordance with approved annual standards and specifications is as follows:

TYPE OF STATE PERMIT	ISSUANCE
Construction General / Stormwater Management – Phase I Land Clearing ("Large" Construction Activity – Sites or common plans of development or sale equal to or greater than 5 acres)	\$750
Construction General / Stormwater Management – Phase II Land Clearing ("Small" Construction Activity – Sites or common plans of development or sale equal to or greater than 1 acre and less than 5 acres)	\$450

c



19975 J 1028

R.A.D. SPORTS + ROCKLAND, MA 02370

÷

.D. SPORTS + ROCKL	AND, MA 02370						270	0 (1 (1
Check#: 72869	Date:	07/13/2018	Vendor#:	10605 Tre	ssurer of Virginia		j S	7 2 3
Invoice#	Job/Description		Balai	nce	Retain	Discount	This Check	
071318	181001 William Price	е F	2,700	00'			2,700.00	

Registration Statement

•	regionation oratement
Seneral VDNES Dan	sit for Dirohawaaa of Régummente a trans of the second second
CHORAL AT DEC 1 CH	in the Discharges of Stormwater from Construction Activities (VAR10)

	Regist General VPDES Permit for Discharges of	ration Statement Stormwater from C	onstruction Activities (VAR10)
	(Please Type	or Print All Information)	
1	Construction Activity Operator: (General permit cover signed by the appropriate person associated with this oper Name: R.A.D. Sports	age will be issued to this erator.)	operator. The Certification in Item #12 must b
**** * * *	Contact: James Doherty		
	Mailing Address: 171 VFW Drive		
	City: Rockland State:	MA 7in 02370	Phone: 781-871-4400 Ext.205
	Email address (if available): jpd@radsports.com	······································	
	Indicate if DEQ may transmit general permit corresponde		
2.	Existing General Permit Registration Number /for ren	ewals only.	
3.	Name and Location of the Construction Activity:	chata omyr.	
	Name: Norfolk State University, William Price Synthetic	Turf Football Field	
	Address (if available): 700 Park Avenue		
	City: Norfolk	State: VA	73504
	County (if not located within a City):	Otale,	
	Latitude (decimal degrees); 36.8469725	Longitude (decimatidad	epril: -76 2598196
	Name and Location of all Off-site Support Activities to	be covered under the o	eneral permit:
	Name:	oo ooveren anner me g	
	Address (if available):		······································
	City:	State	Zip/
	County (if not located within a City):		Δ.μ.
	Latitude (decimal decrees):	l ongitude (decimal degr	\-
			COCV
4.	Status of the Construction Activity (check only one):	Ferderal C State C D	
4, 5.	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field	Federal State Pi Industrial, residential, ac	ublic 🕅 Private 🛄 uricultural, oil and gas, etc.):
4, 5. 6,	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field Name of the Receiving Water(s) and Hydrologic Unit (Federal State Pi Industrial, residential, ag	ublic X Private
4, 5. 6 <i>.</i>	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field Name of the Receiving Water(s) and Hydrologic Unit (Name: Eastern Branch Elizabeth River	Federal State Pi Industrial, residential, ag	ublic X Private
4, 5. 6 <i>,</i>	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field Name of the Receiving Water(s) and Hydrologic Unit (Name: Eastern Branch Elizabeth River HUC: JA41	Federal State Pi Industrial, residential, ag code (HUC): Name:	ees): ublic X Private pricultural, oil and gas, etc.):
4, 5. 6, 7.	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field Name of the Receiving Water(s) and Hydrologic Unit (Name: Eastern Branch Elizabeth River HUC: JA41 If the discharge is through a Municipal Separate Storm City of Norfolk	Federal State Pi Industrial, residential, ag Code (HUC): Name: HUC: Sewer System (MS4), th	ees): ublic X Private pricultural, oil and gas, etc.): ne name of the MS4 operator:
4, 5. 6, 7. 8,	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field Name of the Receiving Water(s) and Hydrologic Unit (Name: Eastern Branch Elizabeth River HUC: JA41 If the discharge is through a Municipal Separate Storm City of Norfolk Estimated Project Start and Completion Date:	Federal State Pi Industrial, residential, ag Code (HUC): Name: HUC: Sewer System (MS4), th	ees): ublic X Private pricultural, oil and gas, etc.): ne name of the MS4 operator:
4, 5. 6. 7.	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field Name of the Receiving Water(s) and Hydrologic Unit C Name: Eastern Branch Elizabeth River HUC: JA41 If the discharge is through a Municipal Separate Storn City of Norfolk Estimated Project Start and Completion Date: Start Date (mm/dd/vyvy): 6/20/2018	Federal State Pi Industrial, residential, ag Code (HUC): HUC: HUC: Sewer System (MS4), the Completion Date	ees): ublic X Private pricultural, oil and gas, etc.): ne name of the MS4 operator:
4, 5, 6, 7, 8,	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field Name of the Receiving Water(s) and Hydrologic Unit (Name: Eastern Branch Elizabeth River HUC: JA41 If the discharge is through a Municipal Separate Storm City of Norfolk Estimated Project Start and Completion Date: Start Date (mm/dd/yyyy): 6/20/2018 Total Land Area of Development (to the nearest one-h	Federal State Pi Industrial, residential, ag code (HUC): HUC: Sewer System (MS4), th Completion Date undredth acre): 2.05 acr	ees): ublic X Private pricultural, oil and gas, etc.): ne name of the MS4 operator: e (mm/dd/yyyy):
4, 5. 6, 7, 8. 9.	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field Name of the Receiving Water(s) and Hydrologic Unit (Name: Eastern Branch Elizabeth River HUC: JA41 If the discharge is through a Municipal Separate Storm City of Norfolk Estimated Project Start and Completion Date: Start Date (mm/dd/yyyy): 6/20/2018 Total Land Area of Development (to the nearest one-h Estimated Area to be Disturbed (to the nearest one-h	Federal State Pi Industrial, residential, ag code (HUC): HUC: Sewer System (MS4), th Completion Date undredth acre): 2.05 acro	ees): ublic X Private pricultural, oil and gas, etc.): ne name of the MS4 operator: (mm/dd/yyyy):
4, 5. 6. 7. 8. 9.	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field Name of the Receiving Water(s) and Hydrologic Unit C Name: Eastern Branch Elizabeth River HUC: JA41 If the discharge is through a Municipal Separate Storm City of Norfolk Estimated Project Start and Completion Date: Start Date (mm/dd/yyyy): 6/20/2018 Total Land Area of Development (to the nearest one-hu Estimated Area to be Disturbed (to the nearest one-hu	Federal State Pi Industrial, residential, ag code (HUC): HUC: Sewer System (MS4), th Completion Date undredth acre): 2.05 acro ndredth acre): 2.05 acro	ees): ublic X Private pricultural, oil and gas, etc.): ne name of the MS4 operator: e (mm/dd/yyyy):
4, 5. 6, 7. 8. 9. 10. 11.	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field Name of the Receiving Water(s) and Hydrologic Unit Content Name: Eastern Branch Elizabeth River HUC: JA41 If the discharge is through a Municipal Separate Storm City of Norfolk Estimated Project Start and Completion Date: Start Date (mm/dd/yyyy): 6/20/2018 Total Land Area of Development (to the nearest one-hults the area to be disturbed part of a larger common plate Astormwater pollution prevention plan (SWPPP) multiples Permit for Discharges of Stormwater from Content of Stormwater	Federal State Principles (Southal degr Federal State Principles (MUC): Name:	ees): ublic X Private pricultural, oil and gas, etc.): ne name of the MS4 operator: e (mm/dd/yyyy):
4, 5. 6, 7, 8, 9, 10, 11, 12,	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field Name of the Receiving Water(s) and Hydrologic Unit Content Name: Eastern Branch Elizabeth River HUC: JA41 If the discharge is through a Municipal Separate Storm City of Norfolk Estimated Project Start and Completion Date: Start Date (mm/dd/yyyy): 6/20/2018 Total Land Area of Development (to the nearest one-hulls the area to be disturbed part of a larger common plan A stormwater pollution prevention plan (SWPPP) multiples Permit for Discharges of Stormwater from Collegy signing this Registration Statement the operator is certification: "I certify under penalty of law that I have r and all attachments were prepared in accordance with a sevaluated the information submitted. Based on my inquidirectly responsible for gathering the information, the in accurate, and complete. I am aware that there are signifiend and imprisonment for knowing violations."	Federal State Principle State Principle State Principle State Principle State Principle State State Principle State Principle State State Principle State Principle State Principle State State Principle Stat	ees):
4, 5. 6, 7. 8, 9, 10, 11.	Status of the Construction Activity (check only one): Nature of the Construction Activity (e.g., commercial, Synthetic Turf Football Field Name of the Receiving Water(s) and Hydrologic Unit C Name: Eastern Branch Elizabeth River HUC: JA41 If the discharge is through a Municipal Separate Storm City of Norfolk Estimated Project Start and Completion Date: Start Date (mm/dd/yyyy): 6/20/2018 Total Land Area of Development (to the nearest one-hulls the area to be Disturbed (to the nearest one-hulls the area to be disturbed part of a larger common plan (SWPPP) multiples Permit for Discharges of Stormwater from Co- By signing this Registration Statement the operator is Certification: "I certify under penalty of law that I have rand all attachments were prepared in accordance with a seculuated the information submitted. Based on my inquid directly responsible for gathering the information, the in accurate, and complete. I am aware that there are signifi fine and imprisonment for knowing violations."	Federal State Principle State Principle State Principle State Principle State Principle State State Principle State Principle State State Principle State Principle State Principle State State Principle Stat	ees):

(Please sign/in INK. This Certification must be signed by the appropriate person associated with the operator identified in Item #1.)_____

COMMONWEALTH OF VIRGINIA

State Water Control Board

629 East Main Street, Richmond, Virginia 23219

RESPONSIBLE LAND DISTURBER

James Patrick Doherty

CERTIFICATE NUMBER RLD05491

EXPIRATION DATE 11/18/2019






Virginia Stormwater Management Program-Stormwater Pollution Prevention Plan (SWPPP)

Norfolk State University New Residential Facility

Norfolk, Virginia

PREPARED FOR

Norfolk State University 700 Park Ave Norfolk, VA 23504

PREPARED BY



4500 Main Street, Suite 400 Virginia Beach, VA 23462 757.490.0132

June 5, 2018



Table of Contents

Introduction	.1
Plan Purpose	1
Background-Construction General Permit	2
SWPPP Coordinator and Duties	.5
SWPPP Coordinator	5
SWPPP Administration	.7
General Information	7
Incorporation of Other Plans	7
Plan Availability	7
Plan Updates	8
Contractor Responsibilities	8
Specific Requirements	9
Site Description	9
General Project Phasing	9
Controls and Measures1	0
Maintenance1	2
Inspections1	2
Spill Prevention and Response Plan1	3
Concrete Washdown Areas1	4
Portable Bathrooms1	4
Storage/Staging and Waste Management Areas1	4
Non-Storm Water Discharges1	5
Water Quality Protection1	5
Post-Construction Stormwater Management Measures1	5
Nutrient Offset Credits1	5
Total Maximum Daily Load (TMDL)1	5
Contractor Certification1	6
References Ref-	·1

Appendices

Appendix	Description			
A	Site Location Map			
В	Storm Water Construction General Permit			
С	Forms: Notice of Registration and Notice of Termination			
D	Notice of Project Completion			
E	Record of Land Disturbance			
F	Record of Inspections			
G	Record of Contractor Certification			
Н	Water Quality Protection			
I	Details of Best Management Practices			
J	ESC & SWM Approval Letters			
К	Site Plans (11" x 17" reductions)			
L	Amendment Log			

Vhb

Introduction

Plan Purpose

This Storm Water Pollution Prevention Plan (SWPPP) has been developed in accordance with the requirements of the Virginia Stormwater Management Program (VSMP) General Permit for Discharges of Stormwater from Construction Activities (Permit), as defined in General Permit No. VAR10 Effective Date: July 1, 2014 Expiration Date: June 30, 2019. The purpose of this SWPPP is to:

- 1. Identify potential sources of pollution that may reasonably be expected to affect the quality of storm water discharges from the construction site, and,
- 2. To describe and ensure the implementation of practices that will be used to reduce pollutants in storm water discharges from the construction site and to assure compliance with the conditions of the Permit.

Implementation of the components of this SWPPP is required as a condition of the Permit (Appendix B). The Department of Environmental Quality (DEQ) has been granted authority to administer the VSMP program and is therefore the regulatory authority overseeing the implementation of this SWPPP.

Pursuant to VSMP Regulation, Section 56 (9 VAC 25-880-70), this SWPPP must meet the following requirements:

- Minimize discharge of pollutants from equipment and vehicle washing, wheel wash water and other wash waters. Wash waters must be treated prior to discharge;
- 2. Minimize exposure of all materials on site to precipitation and stormwater;
- 3. Minimize discharge of pollutants from spills and leaks and implement chemical spill and leak prevention and response procedures;
- 4. Best management practices (BMPs) to prohibit wastewater from washout of concrete mixers and equipment, unless managed by appropriate control;
- 5. BMPs to prohibit wastewater from washout and cleanout of equipment containing stucco, paint, form release oils, curing compounds, and other construction materials;





- 6. BMPs to prohibit discharges of fuels, oils or other pollutants used in vehicle/equipment operation/ maintenance;
- 7. BMPs to prohibit discharges of soaps or solvents used in vehicle/equipment washing;
- 8. Discharges from dewatering activities are prohibited unless managed by appropriate controls.

Background – Construction General Permit

In 1972, Congress passed the Federal Water Pollution Control Act (FWPCA), also known as the Clean Water Act (CWA), to restore and maintain the quality of the nation's waterways. The ultimate goal was to make sure those rivers and streams were fishable, swimmable, and drinkable. In 1987, the Water Quality Act (WQA) added provisions to the CWA that allowed the EPA to govern storm water discharges from construction sites. In 1990, the EPA promulgated rules establishing Phase I of the NPDES storm water program. Phase I addresses, among other discharges, discharges from large construction activities disturbing 5 acres or more of land. In 1998, the EPA published the final notice for General Permits for Storm Water Discharges from Construction Activities (63 Federal Register, February 14, 1998). The general permit includes provisions for development of a SWPPP to maximize the potential benefits of pollution prevention and erosion and sediment control measures at construction sites. Phase II of the NPDES storm water program covers small construction activities disturbing between 1 and 5 acres. Phase II became final on December 8, 1999 with small construction permit applications due by March 10, 2003. Specific compliance dates were to be set by the NPDES permitting authority in each State. The Virginia Department of Environmental Quality amended the General Virginia Pollution Discharge Elimination System (VPDES) Permit Regulations for Discharges of Storm Water from Construction Activities (9 VAC 25-180-10 et seq.) to conform with the EPA Phase II final rule and became effective December 4, 2002. The 2004 Virginia General Assembly passed House Bill 1177 transferring regulatory authority from the State Water Control Board to the Soil and Water Conservation Board and transferred oversight of the programs from the department of Environmental Quality to the Department of Conservation and Recreation. This transfer became effective January 29, 2005. Program oversight was transferred again from the Department of Conservation and Recreation to the Department of Environmental Quality effective July 1, 2013. The General Permit for Discharges of Stormwater from Construction Activities, in accordance with 9 VAC 25-880, is effective starting July 2014 and applies to all VSMP Permits for Discharge of Stormwater from Construction Activities issued after July 1, 2014.

The General Permit has a fixed term of 5 years from the effective date of July 1, 2014 and is required for all "Small Construction Activity" projects that will disturb 1 acre or greater and less than 5 acres of total land area, and for "Large Construction Activity" projects that disturb 5 acres or more of total land area. To obtain a Permit, operators



must submit a Registration Statement (Appendix C) prior to the commencement of construction activities (clearing, grading, or other activities that result in soil disturbance).

The Permit authorizes the discharge of storm water from construction activities until the Permit's expiration date on June 30, 2019. The Permit also authorizes certain non-storm water discharges, provided the conditions contained in the Permit (Part I D.2) are met.

To terminate coverage under the General Permit, a Notice of Termination (Appendix C) must be submitted to the DEQ within 30 days of one of the following conditions:

- 1. Necessary post-construction control measures included in the SWPPP for the site are in place and functioning effectively and final stabilization has been achieved on all portions of the site for which the operator is responsible;
- 2. Another operator has assumed control over all areas of the site that have not been finally stabilized and obtained coverage for the ongoing discharge;
- 3. Coverage under an alternative VPDES or State permit has been obtained; or
- 4. For residential construction only, temporary stabilization has been completed and the residence has been transferred to the homeowner.

Coverage under the Permit will be deemed terminated at midnight on the date the Notice of Termination is submitted.



This page intentionally left blank.

vhb

2 SWPPP Coordinator and Duties

SWPPP Coordinator

The construction site SWPPP coordinator for the facility is the undersigned contractor representative. The contractor will be responsible for maintenance of and compliance with the SWPPP. The SWPPP coordinator duties include the following:

- Implement the SWPPP;
- Oversee maintenance practices identified in the SWPPP;
- Implement and oversee employee training;
- Conduct or provide for inspection and monitoring activities;
- Identify other potential pollutant sources and make sure they are added to this SWPPP;
- Identify any deficiencies in this SWPPP and make sure they are corrected; and
- Ensure that any changes in construction plans are addressed in this SWPPP.
- Ensure that the SWPPP is available for review in accordance with the Plan Administration requirements in Chapter 3.
- Respond to regulatory agency requests for information about the construction site as it relates to the SWPPP and coverage under this permit.

Mr. John Johnson with SB Ballard Construction Company (phone number 757-440-5555), will be responsible for conducting inspections for quality control.

Contractor Agreement

Contractor Representative Name

Signature

Title

Date



This page intentionally left blank.

Vhb

3

SWPPP Administration

General Information

Incorporation of Other Plans

The Norfolk State University (NSU) New Residential Facility project incorporates by reference other plans developed for this construction activity. The construction plans comply with current City requirements regarding erosion and sediment control and storm water management and comply with State regulatory requirements as presented in the *Virginia Erosion and Sediment Control Handbook, Third Edition and Virginia Stormwater Management Handbook, First Edition.* All plans incorporated by reference into this SWPPP are enforceable under the Permit.

Plan Availability

In accordance with Section II B of the Permit:

Copies of this SWPPP must be retained on site, or at another location easily accessible during normal business hours, from the date of commencement of construction activity to the date of final stabilization, along with copies of the registration statement, permit, and acknowledgement letter from the permit issuing authority.

Operators with day to day operational control over SWPPP implementation shall have a copy of the SWPPP available on site for use by all operators identified as having responsibilities to carry out provisions contained in this SWPPP. The SWPPP shall be made available to the DEQ, permit-issuing authority, and operator of the municipal separate storm sewer system (MS4) receiving discharges from the site for review at the time of an on-site inspection. If an on-site location is unavailable to store the SWPPP when no personnel are present, a sign must be posted near the main construction entrance indicating the SWPPP's location.

The Operator shall make the SWPPP and all updates available upon request to the DEQ, the permit-issuing authority, EPA, a state or local agency approving erosion and



sediment control plans, grading plans, and stormwater management plans, local government officials, or the operator of a MS4 receiving discharges from the site.

A sign must be posted near the main entrance of the construction site containing the following information:

- A copy of the permit coverage letter with the registration number for the construction activity;
- Internet address at which a copy of the SWPPP can be found or the location of the hard copy with a name and telephone number for arranging a viewing of the document.

Plan Updates

The Operator shall amend this SWPPP whenever there is a change in design, construction, operation, or maintenance of the construction site that has a significant effect on the potential for the discharge of pollutants to surface waters and that has not been addressed in the normal implementation of this SWPPP. The Operator must also update this SWPPP whenever it is found to be ineffective in meeting the requirements of the Permit.

If approval is required by the permit-issuing authority, revisions shall be made within 7 calendar days of approval. Implementation of these additional or modified control measures must be accomplished as described in Permit Section II D.3.b. Revisions to the SWPPP must be dated and signed in accordance with Permit Section III K.2, but are not required to be certified in accordance with Permit Section III K.4 The SWPPP must clearly identify the contractor(s) or subcontractor(s) that will implement and maintain each measure identified in the SWPPP. The SWPPP shall be revised to identify any new contractor that will implement a measure.

Contractor Responsibilities

The contractor shall be responsible for executing the conditions of the VSMP Permit as defined in Section III (Appendix B) of the Permit. Specifically, the contractor shall be responsible for maintaining a complete record of monitoring, field reports and investigations, notices of noncompliance, etc.



Specific Requirements

Site Description

The proposed development, the NSU New Residential Facility, is located at the northeast quadrant of the NSU campus in the city of Norfolk, Virginia. The building site is currently an existing gravel parking lot and formerly Norfolk City Hospital. The proposed project consists of two residence halls (North Hall and South Hall) each with 302 beds for a total of 604 beds and a central amenity area. The site is bound by Corprew Avenue to the north, campus parking lots and Majestic Avenue to the east, Spartan Suites Apartments to the south, and the NSU Police Building to the west.

The existing terrain of the site is relatively flat with slopes around 1-3%. Site elevations (Based on NAVD88(92)(City of Norfolk 2000), Vertical Datum) range from approximately 12.4 feet at the south end of the site to 15.7 feet in the center of the site.

The project will disturb approximately 5.6 acres. A site location map is included as Appendix A. Plans showing the proposed scope of work are included in Appendix K. The site drains to Ohio Creek which is located within the the Eastern Branch of the Elizabeth River watershed (HUC JL-54), a tributary to the even larger Chesapeake Bay watershed. The site generally drains from the center to the perimeter of the property. Runoff on the south end of the project site is collected through the campus storm drainage system. The remainder drains towards Corprew Avenue. The proposed development will decrease the impervious area of the site by more than 20% and will decrease the amount of runoff flowing overland onto Corprew Avenue.

General Project Phasing

Site development will occur in three overlapping stages:

- 1. Site Preparation,
- 2. Construction, and
- 3. Final grading and Stabilization.

Dates of major grading activities will be recorded on plans included in Appendix K.



Site Preparation Stage

Prior to beginning any construction activities, erosion control fencing will be installed as shown on the attached project plans. The contractor shall use existing pavement to access the site, as indicated on the plans included in Appendix K.

The erosion control barriers will be inspected and maintained routinely throughout the duration of the project. Following the installation of erosion and sedimentation controls, the site clearing and grading activities will occur. The erosion control barriers will be inspected and maintained routinely throughout the duration of the project.

Construction Stage

The proposed NSU New Residential Facility will be constructed during this phase. Prior to construction of the NSU New Residential Facility, demolition of indicated utilities, trees and shrubs, and the existing parking lot will occur. Immediately after the area has been cleared, construction will begin. Newly constructed and existing storm drain inlets will be protected with inlet protection and/or silt fence. Silt fence will also be placed around any stockpiles created from movement of extracted topsoil. All erosion and sediment control measures for the site will be constructed and maintained in accordance with current Virginia Erosion and Sedimentation Control Handbook.

Final Grading and Stabilization Stage

Final site grading and stabilization will be completed as soon as practicable to eliminate exposed soils and potential sources of erosion. Areas to be paved will be covered by bituminous pavement after final subgrades are established. All litter, as well as debris generated by construction activities, will be removed from the site and adjacent undeveloped areas.

Controls and Measures

The Permit requires the use of various types of controls and measures to control pollutants in storm water discharges from the project site. The Permit specifically requires the implementation of erosion and sediment control practices (both structural and non-structural), storm water management practices, and other specific controls to reduce pollutants. In general, controls employed in this project were selected to meet and/or exceed State and local requirements and are detailed in the referenced design plans (Appendix K). The design plans for this project contain detailed information regarding various types of controls used in this project. Table 2 summarizes where the detailed information can be found in the design plans:



Type of Control Measure	Plan Sheet No.		
Frosion and Sediment Control Notes and	C1 02		
	01.02		
Narrative			
Erosion and Sediment Control Plan	C3.00 & C3.01		
Details	C7.00		

Table 2: Control Measures – Included in the Design Documents

Several requirements of the Permit relating to controls (Section II D.2.d, Appendix B) are not included in the referenced design plans. A description of these required items is presented below, along with how they are addressed in this SWPPP:

- a) A record of the dates when major grading activities occur, when construction activities temporarily or permanently cease on a portion of the site, and when stabilization measures are initiated shall be maintained and included in Appendix E of this SWPPP.
- b) If sediment escapes the construction site, off-site accumulations of sediment must be removed. Litter, construction debris, and construction chemicals shall be prevented from becoming a pollutant source in stormwater discharges. Solid materials, including building materials, garbage, and debris shall be cleaned up daily. If appropriate, a description of construction and waste materials to be stored onsite shall be added to this SWPPP. Descriptions of pollution from areas other than those designated construction will also be included. Onsite containers will be provided for collection of waste materials, debris, and rubbish. The Contractor will prevent the accumulation of wastes, which create hazardous conditions. Solid waste materials removed from the site shall be transported in a manner that will prevent spillage and legally disposed of at public or private waste disposal facilities. Volatile wastes will be stored in covered metal containers and removed from the premises daily. The disposal of volatile wastes in storm or sanitary drains is prohibited.
- c) Certain materials stored and/or used onsite that must be controlled to prevent discharge to surface waters. The Contractor will store apparatus, materials, supplies and equipment in an orderly fashion. Materials will be stored and protected in accordance with the manufacturer's recommendations and requirements of the project specifications. The Contractor will completely remove temporary materials and equipment when their use is no longer required.
- d) Other potential pollution sources such as the storage of fertilizers or chemicals; vehicle fueling, sanitary waste facilities, etc. will be managed in a manner consistent with local and state regulations. Fertilizers shall be applied in accordance with manufacturer's recommendations, the landscape specifications, or an approved nutrient management plan and shall not be applied during rainfall events. Any refueling and storage of hazardous materials, chemicals, fuels, and lubricant oil will be conducted in flat open areas to reduce the risk of spillage. Portable lavatories that are to be located on-site



will be serviced on a regular basis by a contractor. They are to be located in upland areas away from direct contact with surface waters.

e) Inspections shall be held every 10 business days and no later than 48 hours following a measurable storm event. These inspections shall be conducted by "qualified personnel". The inspection report should encompass the requirements detailed in Section II.D.4.e.

In addition, Appendix I includes all Erosion and sediment control measures as detailed in the *Virginia Erosion and Sediment Control Handbook, Third Edition* as well as an additional measure for a concrete washout area. The contractor is responsible for recording all potential pollutants associated with construction activities and must submit the record to the owner for review and approval prior to proceeding with construction activities. This record is included in Appendix H: Water Quality Protection. Minimum Erosion and Sediment Control Measures are indicated on the site plans (Appendix K) and may include but are not limited to the following measures:

- Silt fencing
- Tree protection
- Construction site entrance
- Concrete washout area
- Dust control
- Dewatering methods

- Safety fence
- Straw bales
- Storm Drain inlet protection
- Topsoiling
- Temporary and permanent seeding
- Soil stabilization blanket matting

Soil stabilization shall be applied to denuded areas within 7 days after final grade is reached.

Maintenance

Maintenance of temporary and permanent erosion and sediment control facilities shall be carried out in accordance with Section 1.7 of the Virginia Erosion and Sediment Control Regulations (VR 625-02-00, Ref. 1) and Section II D.3 of the Permit (Appendix B). During the period that the project site is under construction, the contractor will be responsible for maintenance of the temporary erosion and sediment control facilities. The site contractor shall inspect the erosion and sediment control facilities on a regular basis, especially after periods of rainfall, and repair any damage immediately. Furthermore, a readily available supply of erosion and sediment control materials will be maintained by the contractor at all times. Detailed descriptions of the maintenance procedures are contained in the project design plans and are incorporated in this SWPPP by reference.

Inspections

The SWPPP Coordinator shall appoint appropriate personnel, who are familiar with all aspects of this SWPPP and the employed control practices, to perform regular inspections of the construction site. Inspections shall include review of all disturbed



areas, structural and non-structural control measures, material storage areas, and vehicular access points. Inspections are to be performed at least once every 10 business days and within 48 hours after any rainfall event producing more than 0.25" of rain in a 24 hour period. Areas that already have been stabilized or where runoff is unlikely due to frozen or snow covered ground shall be inspected at least on a monthly basis.

Inspections are intended to identify areas where the pollutant control measures at the site are ineffective and are allowing pollutants to enter surface waters. Receiving waters shall be inspected to ascertain whether control measures are effective in preventing significant impacts. Locations where vehicles enter or exit the site shall be inspected for evidence of offsite sediment tracking.

If as a result of the inspection, the site conditions and/or control measures are found to have changed, this SWPPP shall be updated within a period of 7 calendar days. If control measures need to be modified to assure effectiveness or if additional measures are determined necessary, implementation shall be completed prior to the next anticipated storm event or as soon as practicable.

A report summarizing the inspections and the subsequent maintenance activities must be completed and maintained as part of this SWPPP. The inspection forms are included in Appendix F. Required elements include major observations (including information on control measure performance and incidents of non-compliance), and information on the inspecting personnel. If an inspection does not identify any incidents or noncompliance, then the certification statement contained in the inspection form will apply.

Spill Prevention and Response Plan

Vehicles and equipment will be maintained off-site. All vehicles and equipment including subcontractor vehicles will be checked for leaking oil and fluids. Vehicles leaking fluids will not be allowed on-site. Drip pans will be placed under all vehicles and equipment that are parked overnight. Hazardous materials will be stored in accordance with local and federal regulations. Spill kits will be within the materials storage area and concrete washout areas. All spills will be cleaned up immediately upon discovery. Spent absorbent materials and rags will be hauled off-site immediately after the spill is cleaned up for disposal. Spills large enough to discharge to surface water will be reported to NSU. Material safety data sheets, a material inventory, and emergency contact information will be maintained at the on-site project trailer.

These spill prevention measures will be implemented once construction begins on-site. All personnel will be instructed, during tailgate training sessions, regarding the correct procedures for spill prevention and control. Notices that state these practices will be



posted in the office trailer, and the individual who manages day-to-day site operations will be responsible for seeing that these procedures are followed.

Concrete Washdown Areas

A designated temporary above-ground concrete washdown area will be constructed at the location approved by the Contractor and NSU inspector. Volume shall be sufficient to contain all liquid and concrete waste generated by washout operations. The washout area shall be lined with plastic sheeting at least 10 mils thick and free of holes and tears. Signs will be posted marking the location of the washout area to ensure that concrete equipment operators use the proper facility.

Concrete pours will not be conducted during or before an anticipated storm event. All excess concrete and concrete washout slurries from the concrete mixer trucks and chutes will be discharged to the washout area or hauled off-site for disposal. When the temporary washout area is no longer needed for the project, the hardened concrete and materials used to construct the areas will be removed and disposed of in accordance with local and federal regulations. Washout areas shall then be backfilled, graded, and stabilized with erosion control measures.

Portable Bathrooms

Portable bathrooms are to be located away from streets, gutters, waterways, and storm drains. Secondary containment techniques such as dikes, berms, curbing, or other containment methods shall be implemented to prevent spills from spreading and to protect groundwater and down grade storm inlets.

Storage/Staging and Waste Management Areas

Fuel containers are to be double-walled. The staging area for this project is to be located as indicated on the site logistics plan with appropriate erosion and sedimentation control measures for protection along the perimeter. Paints, solvents, pesticides, fuels, oils, other hazardous materials, or building materials that have the potential to contaminate stormwater shall be stored indoors or have a cover provided for them. Secondary containment techniques such as dikes, berms, curbing, or other containment methods should be in place to prevent spills from spreading and to protect groundwater and down grade storm inlets.

Dumpsters shall be located away from streets, gutters, waterways, and storm drains. They should be covered to prevent precipitation from entering container. Liquids are



not to be disposed of in dumpsters. Locations of the proposed dumpsters and liquid disposal areas will be coordinated between the contractor and the NSU inspector and shown on an exhibit. A copy of the exhibit shall be incorporated into the SWPPP.

Non-Storm Water Discharges

All discharges for this Site will be comprised entirely of storm water associated with construction activity. At this time, non-storm water discharges are not part of this project. The contractor shall be responsible for notifying the DEQ of any non-storm water discharges other than those authorized in Section 1, D.2. In the event that non-storm water discharges become part of the project, the SWPPP may be updated.

Water Quality Protection

The permittee must select, install, implement and maintain best management practices (BMPs) at the construction site that minimize pollutants in the discharge as necessary to meet applicable water quality standards, as presented in Section 1 H of the permit (Appendix B).

Post-Construction Stormwater Management Measures

No post-construction BMPs for water quantity and quality control are proposed with this project. Water quality and water quantity requirements are met with reductions in impervious area.

Nutrient Offset Credits

Nutrient offset credits will not be obtained for this site.

Total Maximum Daily Load (TMDL)

The project does not discharge directly to a waterbody with an approved Total Maximum Daily Load (TMDL). It should be noted that the Elizabeth River is listed on the 2016 Impaired Waters- 303(d) list as needing a total maximum daily load study with TMDL. The Impaired Waters list describes multiple impairment groups for the Elizabeth River. Aquatic life-dissolved oxygen, open-water aquatic life-dissolved oxygen, Enterococcus, and Estuarine Bioassessments are listed as a few of the water body's impairments. This water body is listed as a Category 5 and 4 water body.



Contractor Certification

All contractors and/or sub-contractors who have responsibility for implementing and maintaining the controls identified in this SWPPP must sign the certification statement contained in Appendix G. The person signing the certification must meet the signatory requirements, as presented in Permit Section III K (Appendix B). The certifications must be maintained as part of this SWPPP.



Virginia Erosion and Sediment Control Handbook. Third Edition. Virginia Department of Conservation and Recreation, 1992.

whb

Site Plans titled Norfolk State University New Residential Facility, dated June 1, 2018 prepared by VHB.



This page intentionally left blank.



Construction Operators' Cooperative Agreement

The cooperative agreement describes stormwater responsibilities for NSU and its undersigned contractor (Contractor) regarding the NSU New Residential Facility. The construction operators below agree to abide by the following condition throughout the duration of the project, effective the date of signature.

This project is subject to the Virginia Stormwater Management Program (VSMP) General Permit for Storm Water Discharges Associated with Industrial Activity (Permit), as defined in General Permit No. VAR10 Effective Date: July 1, 2014 Expiration Date: June 30, 2019. The goal of this permit is to prevent the discharge of pollutants associated with construction activity from entering the storm drain system or surface waters. Vanasse Hangen Brustlin, Inc. has developed a SWPPP for the NSU New Residential Facility project and the SWPPP has been reviewed by NSU (owner) and the City of Norfolk. The SWPPP is available for review at the construction site.

Owner Responsibilities:

- Complete periodic inspections of construction activities
- Be involved with any changes in the SWPPP

Contractor Responsibilities:

- Maintain SWPPP documentation
- Conduct and document inspections on a weekly basis and within 24 hours of the end of a storm event
- Provide copies of the inspection reports to owner within 24 hours of each inspection. Any non-compliances must be immediately reported to owner
- Maintain compliance with applicable section of the SWPPP, including installation of erosion and sediment controls. Any BMP changes that will require a change to the SWPPP must be communicated immediately to owner.
- Maintain erosion and sediment control BMPs in all areas of the site under its day-to-day control.
- (If applicable) Provide adequately designated concrete washout areas throughout the construction project and properly dispose of the concrete, mortar, grout, or other construction materials collected here.



- Maintain the cleanliness of the streets and storm drain inlet protection BMPs throughout the construction project. Sweep streets as needed, especially before rain events. Inspect and replace storm drain inlet protection BMPs as necessary.
- Maintain a clean site. Trash and debris must be picked up and properly disposed of daily.
- Each operator is responsible for advising employees and subcontractors working on this project of the requirements of the SWPPP. Particulate emphasis will be placed on ensuring employees and subcontractors do not damage BMPs and do not introduce pollutants into the storm drain system. All personnel working on-site should have stormwater training.

Agreement

The undersigned agree to abide by the terms and conditions of this cooperative agreement as described above.

Owner

Operator Name

Title

Contractor

Operator Name

Title

Signature

Signature

Date

Date



Delegation of Authority

In accordance with the General VPDES Permit for Discharges of Stormwater from Construction Activities, the individuals or positions with delegated authority to sign inspection reports and/or amend this SWPPP must be identified. If the individual or position identified on the Title Sheet of the SWPPP changes or additional individuals or positions are given this responsibility after the preconstruction meeting occurs, the changes/additions must be noted below.

Delegation of Authority

I, ______ (name), hereby designate the person or specifically described position below to be a duly authorized representative for the purpose of overseeing compliance with environmental requirements, including the VPDES "General Permit for Storm Water Discharges Associated with Construction Activity" (General Permit), at the

NSU New Residential Facility construction site.

Owner Signature:	
J	

Name of Operator: _____

Company: _____

Phone Number: ______



Owner Certification

"I acknowledge under the penalty of law that this document and all attachments were prepared on my behalf in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Company:			
Address:			
-			
Phone:			
Name:			
	Printed	Title	
Signature:			
-			
Date:			



Appendix A Site Location Map

والمعاري المعاد والمعادي والمعاد

T



Vanasse Hangen Brustlin, Inc.

Figure 1: Site Location Map



Appendix B Stormwater General Permit



COMMONWEALTH of VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY

General Permit No.: VAR10

Effective Date: July 1, 2014

Expiration Date: June 30, 2019

GENERAL VPDES PERMIT FOR DISCHARGES OF STORMWATER FROM CONSTRUCTION ACTIVITIES

AUTHORIZATION TO DISCHARGE UNDER THE VIRGINIA STORMWATER MANAGEMENT PROGRAM AND THE VIRGINIA STORMWATER MANAGEMENT ACT

In compliance with the provisions of the Clean Water Act, as amended, and pursuant to the Virginia Stormwater Management Act and regulations adopted pursuant thereto, operators of construction activities are authorized to discharge to surface waters within the boundaries of the Commonwealth of Virginia, except those specifically named in State Water Control Board regulations that prohibit such discharges.

The authorized discharge shall be in accordance with this cover page, Part I - Discharge Authorization and Special Conditions, Part II - Stormwater Pollution Prevention Plan, and Part III - Conditions Applicable to All VPDES Permits as set forth herein.

PART I

DISCHARGE AUTHORIZATION AND SPECIAL CONDITIONS

- A. Coverage under this general permit.
- 1. During the period beginning with the date of coverage under this general permit and lasting until the general permit's expiration date, the operator is authorized to discharge stormwater from construction activities.
- 2. This general permit also authorizes stormwater discharges from support activities (e.g., concrete or asphalt batch plants, equipment staging yards, material storage areas, excavated material disposal areas, borrow areas) located on-site or off-site provided that:
 - a. The support activity is directly related to the construction activity that is required to have general permit coverage for discharges of stormwater from construction activities;
 - b. The support activity is not a commercial operation, nor does it serve multiple unrelated construction activities by different operators;
 - c. The support activity does not operate beyond the completion of the last construction activity it supports;
 - d. The support activity is identified in the registration statement at the time of general permit coverage;
 - e. Appropriate control measures are identified in a stormwater pollution prevention plan and implemented to address the discharges from the support activity areas; and
 - f. All applicable state, federal, and local approvals are obtained for the support activity.
- B. Limitations on coverage.
- Post-construction discharges. This general permit does not authorize stormwater discharges that originate from the site after construction activities have been completed and the site, including any support activity sites covered under the general permit registration, has undergone final stabilization. Post-construction industrial stormwater discharges may need to be covered by a separate VPDES permit.
- 2. Discharges mixed with nonstormwater. This general permit does not authorize discharges that are mixed with sources of nonstormwater, other than those discharges that are identified in Part I E (Authorized nonstormwater discharges) and are in compliance with this general permit.
- 3. Discharges covered by another state permit. This general permit does not authorize discharges of stormwater from construction activities that have been covered under an individual permit or required to obtain coverage under an alternative general permit.
- 4. Impaired waters and TMDL limitation. Discharges of stormwater from construction activities to surface waters identified as impaired in the 2012 § 305(b)/303(d) Water Quality Assessment Integrated Report or for which a TMDL wasteload allocation has been established and approved prior to the term of this general permit for (i) sediment or a sediment-related parameter (i.e., total suspended solids or turbidity) or (ii) nutrients (i.e., nitrogen or phosphorus) are not eligible for coverage under this general permit unless the operator develops, implements, and maintains a SWPPP that minimizes the pollutants of concern and, when applicable, is consistent with the assumptions and requirements of the approved TMDL wasteload allocations. In addition, the operator shall implement the following items:

- a. The impaired water(s), approved TMDL(s), and pollutant(s) of concern, when applicable, shall be identified in the SWPPP;
- b. Permanent or temporary soil stabilization shall be applied to denuded areas within seven days after final grade is reached on any portion of the site;
- c. Nutrients shall be applied in accordance with manufacturer's recommendations or an approved nutrient management plan and shall not be applied during rainfall events; and
- d. The applicable SWPPP inspection requirements specified in Part II F 2 shall be amended as follows:
 - (1) Inspections shall be conducted at a frequency of (i) at least once every four business days or (ii) at least once every five business days and no later than 48 hours following a measurable storm event. In the event that a measurable storm event occurs when there are more than 48 hours between business days, the inspection shall be conducted on the next business day; and
 - (2) Representative inspections used by utility line installation, pipeline construction, or other similar linear construction activities shall inspect all outfalls discharging to surface waters identified as impaired or for which a TMDL wasteload allocation has been established and approved prior to the term of this general permit.
- Exceptional waters limitation. Discharges of stormwater from construction activities not previously covered under the general permit issued in 2009 to exceptional waters identified in 9VAC25-260-30 A 3 c are not eligible for coverage under this general permit unless the operator implements the following:
 - a. The exceptional water(s) shall be identified in the SWPPP;
 - b. Permanent or temporary soil stabilization shall be applied to denuded areas within seven days after final grade is reached on any portion of the site;
 - c. Nutrients shall be applied in accordance with manufacturer's recommendations or an approved nutrient management plan and shall not be applied during rainfall events; and
 - d. The applicable SWPPP inspection requirements specified in Part II F 2 shall be amended as follows:
 - (1) Inspections shall be conducted at a frequency of (i) at least once every four business days or (ii) at least once every five business days and no later than 48 hours following a measurable storm event. In the event that a measurable storm event occurs when there are more than 48 hours between business days, the inspection shall be conducted on the next business day; and
 - (2) Representative inspections used by utility line installation, pipeline construction, or other similar linear construction activities shall inspect all outfalls discharging to exceptional waters.
- 6. There shall be no discharge of floating solids or visible foam in other than trace amounts.

C. Commingled discharges. Discharges authorized by this general permit may be commingled with other sources of stormwater that are not required to be covered under a state permit, so long as the commingled discharge is in compliance with this general permit. Discharges authorized by a separate state or VPDES permit may be commingled with discharges authorized by this general permit so long as all such discharges comply with all applicable state and VPDES permit requirements.

D. Prohibition of nonstormwater discharges. Except as provided in Parts I A 2, I C, and I E, all discharges covered by this general permit shall be composed entirely of stormwater associated with construction activities. All other discharges including the following are prohibited:

- 1. Wastewater from washout of concrete;
- 2. Wastewater from the washout and cleanout of stucco, paint, form release oils, curing compounds, and other construction materials;
- 3. Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance;
- 4. Oils, toxic substances, or hazardous substances from spills or other releases; and
- 5. Soaps, solvents, or detergents used in equipment and vehicle washing.

E. Authorized nonstormwater discharges. The following nonstormwater discharges from construction activities are authorized by this general permit when discharged in compliance with this general permit:

- 1. Discharges from firefighting activities;
- 2. Fire hydrant flushings;
- 3. Waters used to wash vehicles or equipment where soaps, solvents, or detergents have not been used and the wash water has been filtered, settled, or similarly treated prior to discharge;
- 4. Water used to control dust that has been filtered, settled, or similarly treated prior to discharge;
- 5. Potable water sources, including uncontaminated waterline flushings;
- 6. Routine external building wash down where soaps, solvents or detergents have not been used and the wash water has been filtered, settled, or similarly treated prior to discharge;
- 7. Pavement wash waters where spills or leaks of toxic or hazardous materials have not occurred (or where all spilled or leaked material has been removed prior to washing); where soaps, solvents, or detergents have not been used; and where the wash water has been filtered, settled, or similarly treated prior to discharge;
- 8. Uncontaminated air conditioning or compressor condensate;
- 9. Uncontaminated ground water or spring water;
- 10. Foundation or footing drains where flows are not contaminated with process materials such as solvents;
- 11. Uncontaminated excavation dewatering, including dewatering of trenches and excavations that have been filtered, settled, or similarly treated prior to discharge; and
- 12. Landscape irrigation.
- F. Termination of general permit coverage.
- 1. The operator of the construction activity shall submit a notice of termination in accordance with 9VAC25-880-60 to the VSMP authority after one or more of the following conditions have been met:

- a. Necessary permanent control measures included in the SWPPP for the site are in place and functioning effectively and final stabilization has been achieved on all portions of the site for which the operator is responsible. When applicable, long term responsibility and maintenance requirements shall be recorded in the local land records prior to the submission of a notice of termination;
- b. Another operator has assumed control over all areas of the site that have not been finally stabilized and obtained coverage for the ongoing discharge;
- c. Coverage under an alternative VPDES or state permit has been obtained; or
- d. For residential construction only, temporary soil stabilization has been completed and the residence has been transferred to the homeowner.
- 2. The notice of termination should be submitted no later than 30 days after one of the above conditions in subdivision 1 of this subsection is met. Authorization to discharge terminates at midnight on the date that the notice of termination is submitted for the conditions set forth in subdivisions 1 b through 1 d of this subsection. Termination of authorizations to discharge for the conditions set forth in subdivision 1 a of this subsection shall be effective upon notification from the department that the provisions of subdivision 1 a of this subsection have been met or 60 days after submittal of the notice of termination, whichever occurs first.
- 3. The notice of termination shall be signed in accordance with Part III K of this general permit.
- G. Water quality protection.
- 1. The operator must select, install, implement and maintain control measures as identified in the SWPPP at the construction site that minimize pollutants in the discharge as necessary to ensure that the operator's discharge does not cause or contribute to an excursion above any applicable water quality standard.
- 2. If it is determined by the department that the operator's discharges are causing, have reasonable potential to cause, or are contributing to an excursion above any applicable water quality standard, the department, in consultation with the VSMP authority, may take appropriate enforcement action and require the operator to:
 - a. Modify or implement additional control measures in accordance with Part II B to adequately address the identified water quality concerns;
 - b. Submit valid and verifiable data and information that are representative of ambient conditions and indicate that the receiving water is attaining water quality standards; or
 - c. Submit an individual permit application in accordance with 9VAC25-870-410 B 3.

All written responses required under this chapter must include a signed certification consistent with Part III K.

PART II

STORMWATER POLLUTION PREVENTION PLAN

A stormwater pollution prevention plan (SWPPP) shall be developed prior to the submission of a registration statement and implemented for the construction activity, including any support activity, covered by this general permit. SWPPPs shall be prepared in accordance with good engineering practices. Construction activities that are part of a larger common plan of development or sale and disturb less than one acre may utilize a SWPPP template provided by the department and need not provide a separate stormwater management plan if one has been prepared and implemented for the larger common plan of development or sale.

The SWPPP requirements of this general permit may be fulfilled by incorporating by reference other plans such as a spill prevention control and countermeasure (SPCC) plan developed for the site under § 311 of the federal Clean Water Act or best management practices (BMP) programs otherwise required for the facility provided that the incorporated plan meets or exceeds the SWPPP requirements of Part II A. All plans incorporated by reference into the SWPPP become enforceable under this general permit. If a plan incorporated by reference does not contain all of the required elements of the SWPPP, the operator must develop the missing elements and include them in the SWPPP.

Any operator that was authorized to discharge under the general permit issued in 2009, and that intends to continue coverage under this general permit, shall update its stormwater pollution prevention plan to comply with the requirements of this general permit no later than 60 days after the date of coverage under this general permit.

A. Stormwater pollution prevention plan contents. The SWPPP shall include the following items:

- 1. General information.
 - a. A signed copy of the registration statement, if required, for coverage under the general VPDES permit for discharges of stormwater from construction activities;
 - b. Upon receipt, a copy of the notice of coverage under the general VPDES permit for discharges of stormwater from construction activities (i.e., notice of coverage letter);
 - c. Upon receipt, a copy of the general VPDES permit for discharges of stormwater from construction activities;
 - d. A narrative description of the nature of the construction activity, including the function of the project (e.g., low density residential, shopping mall, highway, etc.);
 - e. A legible site plan identifying:
 - (1) Directions of stormwater flow and approximate slopes anticipated after major grading activities;
 - (2) Limits of land disturbance including steep slopes and natural buffers around surface waters that will not be disturbed;
 - (3) Locations of major structural and nonstructural control measures, including sediment basins and traps, perimeter dikes, sediment barriers, and other measures intended to filter, settle, or similarly treat sediment, that will be installed between disturbed areas and the undisturbed vegetated areas in order to increase sediment removal and maximize stormwater infiltration;
 - (4) Locations of surface waters;

- (5) Locations where concentrated stormwater is discharged;
- (6) Locations of support activities, when applicable and when required by the VSMP authority, including but not limited to (i) areas where equipment and vehicle washing, wheel wash water, and other wash water is to occur; (ii) storage areas for chemicals such as acids, fuels, fertilizers, and other lawn care chemicals; (iii) concrete wash out areas; (iv) vehicle fueling and maintenance areas; (v) sanitary waste facilities, including those temporarily placed on the construction site; and (vi) construction waste storage; and
- (7) When applicable, the location of the on-site rain gauge or the methodology established in consultation with the VSMP authority used to identify measurable storm events for inspection purposes.
- 2. Erosion and sediment control plan.
 - a. An erosion and sediment control plan approved by the VESCP authority as authorized under the Erosion and Sediment Control Regulations (9VAC25-840), an "agreement in lieu of a plan" as defined in 9VAC25-840-10 from the VESCP authority, or an erosion and sediment control plan prepared in accordance with annual standards and specifications approved by the department. Any operator proposing a new stormwater discharge from construction activities that is not required to obtain erosion and sediment control plan approval from a VESCP authority or does not adopt department-approved annual standards and specifications shall submit the erosion and sediment control plan to the department for review and approval.
 - b. All erosion and sediment control plans shall include a statement describing the maintenance responsibilities required for the erosion and sediment controls used.
 - c. A properly implemented approved erosion and sediment control plan, "agreement in lieu of a plan," or erosion and sediment control plan prepared in accordance with department-approved annual standards and specifications, adequately:
 - (1) Controls the volume and velocity of stormwater runoff within the site to minimize soil erosion;
 - (2) Controls stormwater discharges, including peak flow rates and total stormwater volume, to minimize erosion at outlets and to minimize downstream channel and stream bank erosion;
 - (3) Minimizes the amount of soil exposed during the construction activity;
 - (4) Minimizes the disturbance of steep slopes;
 - (5) Minimizes sediment discharges from the site in a manner that addresses (i) the amount, frequency, intensity, and duration of precipitation; (ii) the nature of resulting stormwater runoff; and (iii) soil characteristics, including the range of soil particle sizes present on the site;
 - (6) Provides and maintains natural buffers around surface waters, directs stormwater to vegetated areas to increase sediment removal, and maximizes stormwater infiltration, unless infeasible;
 - (7) Minimizes soil compaction and, unless infeasible, preserves topsoil;
 - (8) Ensures that stabilization of disturbed areas will be initiated immediately whenever any clearing, grading, excavating, or other land-disturbing activities have permanently ceased on any portion of the site, or temporarily ceased on any portion of the site and will not resume for a period exceeding 14 days; and

- (9) Utilizes outlet structures that withdraw stormwater from the surface (i.e., above the permanent pool or wet storage water surface elevation), unless infeasible, when discharging from sediment basins or sediment traps.
- 3. Stormwater management plan.
 - a. New construction activities. A stormwater management plan approved by the VSMP authority as authorized under the Virginia Stormwater Management Program (VSMP) Regulation (9VAC25-870), or an "agreement in lieu of a stormwater management plan" as defined in 9VAC25-870-10 from the VSMP authority, or a stormwater management plan prepared in accordance with annual standards and specifications approved by the department. Any operator proposing a new stormwater discharge from construction activities that is not required to obtain stormwater management plan approved from a VSMP authority or does not adopt department-approved annual standards and specifications shall submit the stormwater management plan to the department for review and approval.
 - b. Existing construction activities. Any operator that was authorized to discharge under the general permit issued in 2009, and that intends to continue coverage under this general permit, shall ensure compliance with the requirements of 9VAC25-870-93 through 9VAC25-870-99 of the VSMP Regulation, including but not limited to the water quality and quantity requirements. The SWPPP shall include a description of, and all necessary calculations supporting, all post-construction stormwater management measures that will be installed prior to the completion of the construction process to control pollutants in stormwater discharges after construction operations have been completed. Structural measures should be placed on upland soils to the degree possible. Such measures must be designed and installed in accordance with applicable VESCP authority, VSMP authority, state, and federal requirements, and any necessary permits must be obtained.
- 4. Pollution prevention plan. A pollution prevention plan that addresses potential pollutant-generating activities that may reasonably be expected to affect the quality of stormwater discharges from the construction activity, including any support activity. The pollution prevention plan shall:
 - a. Identify the potential pollutant-generating activities and the pollutant that is expected to be exposed to stormwater;
 - b. Describe the location where the potential pollutant-generating activities will occur, or if identified on the site plan, reference the site plan;
 - Identify all nonstormwater discharges, as authorized in Part I E of this general permit, that are or will be commingled with stormwater discharges from the construction activity, including any applicable support activity;
 - d. Identify the person responsible for implementing the pollution prevention practice or practices for each pollutant-generating activity (if other than the person listed as the qualified personnel);
 - e. Describe the pollution prevention practices and procedures that will be implemented to:
 - (1) Prevent and respond to leaks, spills, and other releases including (i) procedures for expeditiously stopping, containing, and cleaning up spills, leaks, and other releases; and (ii) procedures for reporting leaks, spills, and other releases in accordance with Part III G;
 - (2) Prevent the discharge of spilled and leaked fuels and chemicals from vehicle fueling and maintenance activities (e.g., providing secondary containment such as spill berms, decks, spill containment pallets, providing cover where appropriate, and having spill kits readily available);
- (3) Prevent the discharge of soaps, solvents, detergents, and wash water from construction materials, including the clean-up of stucco, paint, form release oils, and curing compounds (e.g., providing (i) cover (e.g., plastic sheeting or temporary roofs) to prevent contact with stormwater; (ii) collection and proper disposal in a manner to prevent contact with stormwater; and (iii) a similarly effective means designed to prevent discharge of these pollutants);
- (4) Minimize the discharge of pollutants from vehicle and equipment washing, wheel wash water, and other types of washing (e.g., locating activities away from surface waters and stormwater inlets or conveyance and directing wash waters to sediment basins or traps, using filtration devices such as filter bags or sand filters, or using similarly effective controls);
- (5) Direct concrete wash water into a leak-proof container or leak-proof settling basin. The container or basin shall be designed so that no overflows can occur due to inadequate sizing or precipitation. Hardened concrete wastes shall be removed and disposed of in a manner consistent with the handling of other construction wastes. Liquid concrete wastes shall be removed and disposed of in a manner consistent with the handling of other consistent with the handling of other construction wastes waters and shall not be discharged to surface waters;
- (6) Minimize the discharge of pollutants from storage, handling, and disposal of construction products, materials, and wastes including (i) building products such as asphalt sealants, copper flashing, roofing materials, adhesives, and concrete admixtures; (ii) pesticides, herbicides, insecticides, fertilizers, and landscape materials; and (iii) construction and domestic wastes such as packaging materials, scrap construction materials, masonry products, timber, pipe and electrical cuttings, plastics, Styrofoam, concrete, and other trash or building materials;
- (7) Prevent the discharge of fuels, oils, and other petroleum products, hazardous or toxic wastes, and sanitary wastes; and
- (8) Address any other discharge from the potential pollutant-generating activities not addressed above; and
- f. Describe procedures for providing pollution prevention awareness of all applicable wastes, including any wash water, disposal practices, and applicable disposal locations of such wastes, to personnel in order to comply with the conditions of this general permit. The operator shall implement the procedures described in the SWPPP.
- 5. SWPPP requirements for discharges to impaired waters, surface waters with an applicable TMDL wasteload allocation established and approved prior to the term of this general permit, and exceptional waters. The SWPPP shall:
 - a. Identify the impaired water(s), approved TMDL(s), pollutant(s) of concern, and exceptional waters identified in 9VAC25-260-30 A 3 c, when applicable;
 - b. Provide clear direction that:
 - (1) Permanent or temporary soil stabilization shall be applied to denuded areas within seven days after final grade is reached on any portion of the site;
 - (2) Nutrients shall be applied in accordance with manufacturer's recommendations or an approved nutrient management plan and shall not be applied during rainfall events; and
 - (3) A modified inspection schedule shall be implemented in accordance with Part I B 4 or Part I B 5.

- 6. Qualified personnel. The name, phone number, and qualifications of the qualified personnel conducting inspections required by this general permit.
- 7. Delegation of authority. The individuals or positions with delegated authority, in accordance with Part III K, to sign inspection reports or modify the SWPPP.
- 8. SWPPP signature. The SWPPP shall be signed and dated in accordance with Part III K.
- B. SWPPP amendments, modification, and updates.
- 1. The operator shall amend the SWPPP whenever there is a change in the design, construction, operation, or maintenance that has a significant effect on the discharge of pollutants to surface waters and that has not been previously addressed in the SWPPP.
- 2. The SWPPP must be amended if, during inspections or investigations by the operator's qualified personnel, or by local, state, or federal officials, it is determined that the existing control measures are ineffective in minimizing pollutants in discharges from the construction activity. Revisions to the SWPPP shall include additional or modified control measures designed and implemented to correct problems identified. If approval by the VESCP authority, VSMP authority, or department is necessary for the control measure, revisions to the SWPPP shall be completed no later than seven calendar days following approval. Implementation of these additional or modified control measures must be accomplished as described in Part II G.
- 3. The SWPPP must clearly identify the contractor(s) that will implement and maintain each control measure identified in the SWPPP. The SWPPP shall be amended to identify any new contractor that will implement and maintain a control measure.
- 4. The operator shall update the SWPPP no later than seven days following any modification to its implementation. All modifications or updates to the SWPPP shall be noted and shall include the following items:
 - a. A record of dates when:
 - (1) Major grading activities occur;
 - (2) Construction activities temporarily or permanently cease on a portion of the site; and
 - (3) Stabilization measures are initiated;
 - Documentation of replaced or modified controls where periodic inspections or other information have indicated that the controls have been used inappropriately or incorrectly and where modified as soon as possible;
 - c. Areas that have reached final stabilization and where no further SWPPP or inspection requirements apply;
 - d. All properties that are no longer under the legal control of the operator and the dates on which the operator no longer had legal control over each property;
 - e. The date of any prohibited discharges, the discharge volume released, and what actions were taken to minimize the impact of the release;
 - f. Measures taken to prevent the reoccurrence of any prohibited discharge; and
 - g. Measures taken to address any evidence identified as a result of an inspection required under Part II F.

5. Amendments, modifications, or updates to the SWPPP shall be signed in accordance with Part III K.

C. Public Notification. Upon commencement of land disturbance, the operator shall post conspicuously a copy of the notice of coverage letter near the main entrance of the construction activity. For linear projects, the operator shall post the notice of coverage letter at a publicly accessible location near an active part of the construction project (e.g., where a pipeline crosses a public road). The operator shall maintain the posted information until termination of general permit coverage as specified in Part I F.

D. SWPPP availability.

- 1. Operators with day-to-day operational control over SWPPP implementation shall have a copy of the SWPPP available at a central location on-site for use by those identified as having responsibilities under the SWPPP whenever they are on the construction site.
- 2. The operator shall make the SWPPP and all amendments, modifications, and updates available upon request to the department, the VSMP authority, the EPA, the VESCP authority, local government officials, or the operator of a municipal separate storm sewer system receiving discharges from the construction activity. If an on-site location is unavailable to store the SWPPP when no personnel are present, notice of the SWPPP's location must be posted near the main entrance of the construction site.
- 3. The operator shall make the SWPPP available for public review in an electronic format or in hard copy. Information for public access to the SWPPP shall be posted and maintained in accordance with Part II C. If not provided electronically, public access to the SWPPP may be arranged upon request at a time and at a publicly accessible location convenient to the operator or his designee but shall be no less than once per month and shall be during normal business hours. Information not required to be contained within the SWPPP by this general permit is not required to be released.

E. SWPPP implementation. The operator shall implement the SWPPP and subsequent amendments, modifications, and updates from commencement of land disturbance until termination of general permit coverage as specified in Part I F.

- All control measures must be properly maintained in effective operating condition in accordance with good engineering practices and, where applicable, manufacturer specifications. If a site inspection required by Part II F identifies a control measure that is not operating effectively, corrective action(s) shall be completed as soon as practicable, but no later than seven days after discovery or a longer period as established by the VSMP authority, to maintain the continued effectiveness of the control measures.
- 2. If site inspections required by Part II F identify an existing control measure that needs to be modified or if an additional control measure is necessary for any reason, implementation shall be completed prior to the next anticipated measurable storm event. If implementation prior to the next anticipated measurable storm event is impracticable, then alternative control measures shall be implemented as soon as practicable, but no later than seven days after discovery or a longer period as established by the VSMP authority.
- F. SWPPP Inspections.
- 1. Personnel responsible for on-site and off-site inspections. Inspections required by this general permit shall be conducted by the qualified personnel identified by the operator in the SWPPP. The operator is responsible for insuring that the qualified personnel conduct the inspection.
- 2. Inspection schedule.
 - a. Inspections shall be conducted at a frequency of:

- (1) At least once every five business days; or
- (2) At least once every 10 business days and no later than 48 hours following a measurable storm event. In the event that a measurable storm event occurs when there are more than 48 hours between business days, the inspection shall be conducted no later than the next business day.
- b. Where areas have been temporarily stabilized or land-disturbing activities will be suspended due to continuous frozen ground conditions and stormwater discharges are unlikely, the inspection frequency may be reduced to once per month. If weather conditions (such as above freezing temperatures or rain or snow events) make discharges likely, the operator shall immediately resume the regular inspection frequency.
- c. Representative inspections may be utilized for utility line installation, pipeline construction, or other similar linear construction activities provided that:
 - Temporary or permanent soil stabilization has been installed and vehicle access may compromise the temporary or permanent soil stabilization and potentially cause additional land disturbance increasing the potential for erosion;
 - (2) Inspections occur on the same frequency as other construction activities;
 - (3) Control measures are inspected along the construction site 0.25 miles above and below each access point (i.e., where a roadway, undisturbed right-of-way, or other similar feature intersects the construction activity and access does not compromise temporary or permanent soil stabilization); and
 - (4) Inspection locations are provided in the report required by Part II F.
- 3. Inspection requirements.
 - a. As part of the inspection, the qualified personnel shall:
 - (1) Record the date and time of the inspection and when applicable the date and rainfall amount of the last measurable storm event;
 - (2) Record the information and a description of any discharges occurring at the time of the inspection;
 - (3) Record any land-disturbing activities that have occurred outside of the approved erosion and sediment control plan;
 - (4) Inspect the following for installation in accordance with the approved erosion and sediment control plan, identification of any maintenance needs, and evaluation of effectiveness in minimizing sediment discharge, including whether the control has been inappropriately or incorrectly used:
 - (a) All perimeter erosion and sediment controls, such as silt fence;
 - (b) Soil stockpiles, when applicable, and borrow areas for stabilization or sediment trapping measures;
 - (c) Completed earthen structures, such as dams, dikes, ditches, and diversions for stabilization;

- (d) Cut and fill slopes;
- (e) Sediment basins and traps, sediment barriers, and other measures installed to control sediment discharge from stormwater;
- (f) Temporary or permanent channel, flume, or other slope drain structures installed to convey concentrated runoff down cut and fill slopes;
- (g) Storm inlets that have been made operational to ensure that sediment laden stormwater does not enter without first being filtered or similarly treated; and
- (h) Construction vehicle access routes that intersect or access paved roads for minimizing sediment tracking;
- (5) Inspect areas that have reached final grade or that will remain dormant for more than 14 days for initiation of stabilization activities;
- (6) Inspect areas that have reached final grade or that will remain dormant for more than 14 days for completion of stabilization activities within seven days of reaching grade or stopping work;
- (7) Inspect for evidence that the approved erosion and sediment control plan, "agreement in lieu of a plan," or erosion and sediment control plan prepared in accordance with departmentapproved annual standards and specifications has not been properly implemented. This includes but is not limited to:
 - (a) Concentrated flows of stormwater in conveyances such as rills, rivulets or channels that have not been filtered, settled, or similarly treated prior to discharge, or evidence thereof;
 - (b) Sediment laden or turbid flows of stormwater that have not been filtered or settled to remove sediments prior to discharge;
 - (c) Sediment deposition in areas that drain to unprotected stormwater inlets or catch basins that discharge to surface waters. Inlets and catch basins with failing sediments controls due to improper installation, lack of maintenance, or inadequate design are considered unprotected;
 - (d) Sediment deposition on any property (including public and private streets) outside of the construction activity covered by this general permit;
 - (e) Required stabilization has not been initiated or completed on portions of the site;
 - (f) Sediment basins without adequate wet or dry storage volume or sediment basins that allow the discharge of stormwater from below the surface of the wet storage portion of the basin;
 - (g) Sediment traps without adequate wet or dry storage or sediment traps that allow the discharge of stormwater from below the surface of the wet storage portion of the trap; and
 - (h) Land disturbance outside of the approved area to be disturbed;
- (8) Inspect pollutant generating activities identified in the pollution prevention plan for the proper implementation, maintenance and effectiveness of the procedures and practices;
- (9) Identify any pollutant generating activities not identified in the pollution prevention plan; and

- (10) Identify and document the presence of any evidence of the discharge of pollutants prohibited by this general permit.
- 4. Inspection report. Each inspection report shall include the following items:
 - a. The date and time of the inspection and when applicable, the date and rainfall amount of the last measurable storm event;
 - b. Summarized findings of the inspection;
 - c. The location(s) of prohibited discharges;
 - d. The location(s) of control measures that require maintenance;
 - e. The location(s) of control measures that failed to operate as designed or proved inadequate or inappropriate for a particular location;
 - f. The location(s) where any evidence identified under Part II F 3 a (7) exists;
 - g. The location(s) where any additional control measure is needed that did not exist at the time of inspection;
 - h. A list of corrective actions required (including any changes to the SWPPP that are necessary) as a result of the inspection or to maintain permit compliance;
 - i. Documentation of any corrective actions required from a previous inspection that have not been implemented; and
 - j. The date and signature of the qualified personnel and the operator or its duly authorized representative.

The inspection report and any actions taken in accordance with Part II must be retained by the operator as part of the SWPPP for at least three years from the date that general permit coverage expires or is terminated. The inspection report shall identify any incidents of noncompliance. Where an inspection report does not identify any incidents of noncompliance, the report shall contain a certification that the construction activity is in compliance with the SWPPP and this general permit. The report shall be signed in accordance with Part III K of this general permit.

- G. Corrective actions.
- The operator shall implement the corrective action(s) identified as a result of an inspection as soon as practicable but no later than seven days after discovery or a longer period as approved by the VSMP authority. If approval of a corrective action by a regulatory authority (e.g., VSMP authority, VESCP authority, or the department) is necessary, additional control measures shall be implemented to minimize pollutants in stormwater discharges until such approvals can be obtained.
- 2. The operator may be required to remove accumulated sediment deposits located outside of the construction activity covered by this general permit as soon as practicable in order to minimize environmental impacts. The operator shall notify the VSMP authority and the department as well as obtain all applicable federal, state, and local authorizations, approvals, and permits prior to the removal of sediments accumulated in surface waters including wetlands.

PART III

CONDITIONS APPLICABLE TO ALL VPDES PERMITS

NOTE: Discharge monitoring is not required for this general permit. If the operator chooses to monitor stormwater discharges or control measures, the operator must comply with the requirements of subsections A, B, and C, as appropriate.

A. Monitoring.

- 1. Samples and measurements taken for the purpose of monitoring shall be representative of the monitoring activity.
- 2. Monitoring shall be conducted according to procedures approved under 40 CFR Part 136 or alternative methods approved by the U.S. Environmental Protection Agency, unless other procedures have been specified in this general permit. Analyses performed according to test procedures approved under 40 CFR Part 136 shall be performed by an environmental laboratory certified under regulations adopted by the Department of General Services (1VAC30-45 or 1VAC30-46).
- 3. The operator shall periodically calibrate and perform maintenance procedures on all monitoring and analytical instrumentation at intervals that will ensure accuracy of measurements.

B. Records.

- 1. Monitoring records and reports shall include:
 - a. The date, exact place, and time of sampling or measurements;
 - b. The individual(s) who performed the sampling or measurements;
 - c. The date(s) and time(s) analyses were performed;
 - d. The individual(s) who performed the analyses;
 - e. The analytical techniques or methods used; and
 - f. The results of such analyses.
- 2. The operator shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by this general permit, and records of all data used to complete the registration statement for this general permit, for a period of at least three years from the date of the sample, measurement, report or request for coverage. This period of retention shall be extended automatically during the course of any unresolved litigation regarding the regulated activity or regarding control standards applicable to the operator, or as requested by the board.
- C. Reporting monitoring results.
- 1. The operator shall update the SWPPP to include the results of the monitoring as may be performed in accordance with this general permit, unless another reporting schedule is specified elsewhere in this general permit.
- 2. Monitoring results shall be reported on a discharge monitoring report (DMR); on forms provided, approved or specified by the department; or in any format provided that the date, location, parameter, method, and result of the monitoring activity are included.

- 3. If the operator monitors any pollutant specifically addressed by this general permit more frequently than required by this general permit using test procedures approved under 40 CFR Part 136 or using other test procedures approved by the U.S. Environmental Protection Agency or using procedures specified in this general permit, the results of this monitoring shall be included in the calculation and reporting of the data submitted in the DMR or reporting form specified by the department.
- 4. Calculations for all limitations which require averaging of measurements shall utilize an arithmetic mean unless otherwise specified in this general permit.

D. Duty to provide information. The operator shall furnish, within a reasonable time, any information which the board may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this general permit or to determine compliance with this general permit. The board, department, EPA, or VSMP authority may require the operator to furnish, upon request, such plans, specifications, and other pertinent information as may be necessary to determine the effect of the wastes from his discharge on the quality of surface waters, or such other information as may be necessary to accomplish the purposes of the CWA and the Virginia Stormwater Management Act. The operator shall also furnish to the board, department, EPA, or VSMP authority, upon request, copies of records required to be kept by this general permit.

E. Compliance schedule reports. Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of this general permit shall be submitted no later than 14 days following each schedule date.

F. Unauthorized stormwater discharges. Pursuant to § 62.1-44.5 of the Code of Virginia, except in compliance with a state permit issued by the department, it shall be unlawful to cause a stormwater discharge from a construction activity.

G. Reports of unauthorized discharges. Any operator who discharges or causes or allows a discharge of sewage, industrial waste, other wastes or any noxious or deleterious substance or a hazardous substance or oil in an amount equal to or in excess of a reportable quantity established under either 40 CFR Part 110, 40 CFR Part 117, 40 CFR Part 302, or § 62.1-44.34:19 of the Code of Virginia that occurs during a 24-hour period into or upon surface waters or who discharges or causes or allows a discharge that may reasonably be expected to enter surface waters, shall notify the Department of Environmental Quality of the discharge immediately upon discovery of the discharge, but in no case later than within 24 hours after said discovery. A written report of the unauthorized discharge shall be submitted to the department and the VSMP authority within five days of discovery of the discharge. The written report shall contain:

- 1. A description of the nature and location of the discharge;
- 2. The cause of the discharge;
- 3. The date on which the discharge occurred;
- 4. The length of time that the discharge continued;
- 5. The volume of the discharge;
- 6. If the discharge is continuing, how long it is expected to continue;
- 7. If the discharge is continuing, what the expected total volume of the discharge will be; and
- 8. Any steps planned or taken to reduce, eliminate and prevent a recurrence of the present discharge or any future discharges not authorized by this general permit.

Discharges reportable to the department and the VSMP authority under the immediate reporting requirements of other regulations are exempted from this requirement.

H. Reports of unusual or extraordinary discharges. If any unusual or extraordinary discharge including a "bypass" or "upset," as defined herein, should occur from a facility and the discharge enters or could be expected to enter surface waters, the operator shall promptly notify, in no case later than within 24 hours, the department and the VSMP authority by telephone after the discovery of the discharge. This notification shall provide all available details of the incident, including any adverse effects on aquatic life and the known number of fish killed. The operator shall reduce the report to writing and shall submit it to the department and the VSMP authority within five days of discovery of the discharge in accordance with Part III 1 2. Unusual and extraordinary discharges include but are not limited to any discharge resulting from:

- 1. Unusual spillage of materials resulting directly or indirectly from processing operations;
- 2. Breakdown of processing or accessory equipment;
- 3. Failure or taking out of service of some or all of the facilities; and
- 4. Flooding or other acts of nature.

I. Reports of noncompliance. The operator shall report any noncompliance which may adversely affect surface waters or may endanger public health.

- 1. An oral report to the department and the VSMP authority shall be provided within 24 hours from the time the operator becomes aware of the circumstances. The following shall be included as information that shall be reported within 24 hours under this subdivision:
 - a. Any unanticipated bypass; and
 - b. Any upset that causes a discharge to surface waters.
- 2. A written report shall be submitted within five days and shall contain:
 - a. A description of the noncompliance and its cause;
 - b. The period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and
 - c. Steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.

The department may waive the written report on a case-by-case basis for reports of noncompliance under Part III I if the oral report has been received within 24 hours and no adverse impact on surface waters has been reported.

3. The operator shall report all instances of noncompliance not reported under Part III I 1 or 2 in writing as part of the SWPPP. The reports shall contain the information listed in Part III I 2.

NOTE: The reports required in Part III G, H and I shall be made to the department and the VSMP authority. Reports may be made by telephone, email, or by fax. For reports outside normal working hours, leaving a recorded message shall fulfill the immediate reporting requirement. For emergencies, the Virginia Department of Emergency Management maintains a 24-hour telephone service at 1-800-468-8892.

- 4. Where the operator becomes aware of a failure to submit any relevant facts, or submittal of incorrect information in any report, including a registration statement, to the department or the VSMP authority, the operator shall promptly submit such facts or correct information.
- J. Notice of planned changes.
- 1. The operator shall give notice to the department and the VSMP authority as soon as possible of any planned physical alterations or additions to the permitted facility or activity. Notice is required only when:
 - The operator plans an alteration or addition to any building, structure, facility, or installation that may meet one of the criteria for determining whether a facility is a new source in 9VAC25-870-420;
 - b. The operator plans an alteration or addition that would significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants that are not subject to effluent limitations in this general permit; or
- 2. The operator shall give advance notice to the department and VSMP authority of any planned changes in the permitted facility or activity, which may result in noncompliance with state permit requirements.
- K. Signatory requirements.
- 1. Registration statement. All registration statements shall be signed as follows:
 - a. For a corporation: by a responsible corporate officer. For the purpose of this chapter, a responsible corporate officer means: (i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy-making or decision-making functions for the corporation; or (ii) the manager of one or more manufacturing, production, or operating facilities, provided the manager is authorized to make management decisions that govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long-term compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for state permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures;
 - b. For a partnership or sole proprietorship: by a general partner or the proprietor, respectively; or
 - c. For a municipality, state, federal, or other public agency: by either a principal executive officer or ranking elected official. For purposes of this chapter, a principal executive officer of a public agency includes: (i) the chief executive officer of the agency or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency.
- 2. Reports, etc. All reports required by this general permit, including SWPPPs, and other information requested by the board or the department shall be signed by a person described in Part III K 1 or by a duly authorized representative of that person. A person is a duly authorized representative only if:
 - a. The authorization is made in writing by a person described in Part III K 1;
 - b. The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity such as the position of plant manager, operator of a well or a well field, superintendent, position of equivalent responsibility, or an individual or position having overall responsibility for environmental matters for the operator. (A duly authorized

representative may thus be either a named individual or any individual occupying a named position); and

- c. The signed and dated written authorization is included in the SWPPP. A copy must be provided to the department and VSMP authority, if requested.
- 3. Changes to authorization. If an authorization under Part III K 2 is no longer accurate because a different individual or position has responsibility for the overall operation of the construction activity, a new authorization satisfying the requirements of Part III K 2 shall be submitted to the VSMP authority as the administering entity for the board prior to or together with any reports or information to be signed by an authorized representative.
- 4. Certification. Any person signing a document under Part III K 1 or 2 shall make the following certification:

"I certify under penalty of law that I have read and understand this document and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

L. Duty to comply. The operator shall comply with all conditions of this general permit. Any state permit noncompliance constitutes a violation of the Virginia Stormwater Management Act and the Clean Water Act, except that noncompliance with certain provisions of this general permit may constitute a violation of the Virginia Stormwater Management Act but not the Clean Water Act. Permit noncompliance is grounds for enforcement action; for state permit termination, revocation and reissuance, or modification; or denial of a state permit renewal application.

The operator shall comply with effluent standards or prohibitions established under § 307(a) of the Clean Water Act for toxic pollutants within the time provided in the regulations that establish these standards or prohibitions or standards for sewage sludge use or disposal, even if this general permit has not yet been modified to incorporate the requirement.

M. Duty to reapply. If the operator wishes to continue an activity regulated by this general permit after the expiration date of this general permit, the operator shall submit a new registration statement at least 90 days before the expiration date of the existing general permit, unless permission for a later date has been granted by the board. The board shall not grant permission for registration statements to be submitted later than the expiration date of the existing general permit.

N. Effect of a state permit. This general permit does not convey any property rights in either real or personal property or any exclusive privileges, nor does it authorize any injury to private property or invasion of personal rights, or any infringement of federal, state or local law or regulations.

O. State law. Nothing in this general permit shall be construed to preclude the institution of any legal action under, or relieve the operator from any responsibilities, liabilities, or penalties established pursuant to any other state law or regulation or under authority preserved by § 510 of the Clean Water Act. Except as provided in general permit conditions on "bypassing" (Part III U) and "upset" (Part III V), nothing in this general permit shall be construed to relieve the operator from civil and criminal penalties for noncompliance.

P. Oil and hazardous substance liability. Nothing in this general permit shall be construed to preclude the institution of any legal action or relieve the operator from any responsibilities, liabilities, or penalties to which the operator is or may be subject under §§ 62.1-44.34:14 through 62.1-44.34:23 of the State Water Control Law or § 311 of the Clean Water Act.

Q. Proper operation and maintenance. The operator shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances), which are installed or used by the operator to achieve compliance with the conditions of this general permit. Proper operation and maintenance also includes effective plant performance, adequate funding, adequate staffing, and adequate laboratory and process controls, including appropriate quality assurance procedures. This provision requires the operation of back-up or auxiliary facilities or similar systems, which are installed by the operator only when the operation is necessary to achieve compliance with the conditions of this general permit.

R. Disposal of solids or sludges. Solids, sludges or other pollutants removed in the course of treatment or management of pollutants shall be disposed of in a manner so as to prevent any pollutant from such materials from entering surface waters and in compliance with all applicable state and federal laws and regulations.

S. Duty to mitigate. The operator shall take all steps to minimize or prevent any discharge in violation of this general permit that has a reasonable likelihood of adversely affecting human health or the environment.

T. Need to halt or reduce activity not a defense. It shall not be a defense for an operator in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this general permit.

U. Bypass.

- 1. "Bypass," as defined in 9VAC25-870-10, means the intentional diversion of waste streams from any portion of a treatment facility. The operator may allow any bypass to occur that does not cause effluent limitations to be exceeded, but only if it also is for essential maintenance to ensure efficient operation. These bypasses are not subject to the provisions of Part III U 2 and 3.
- 2. Notice.
 - a. Anticipated bypass. If the operator knows in advance of the need for a bypass, the operator shall submit prior notice to the department, if possible at least 10 days before the date of the bypass.
 - b. Unanticipated bypass. The operator shall submit notice of an unanticipated bypass as required in Part III I.
- 3. Prohibition of bypass.
 - a. Except as provided in Part III U 1, bypass is prohibited, and the board or department may take enforcement action against an operator for bypass unless:
 - (1) Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage. Severe property damage means substantial physical damage to property, damage to the treatment facilities that causes them to become inoperable, or substantial and permanent loss of natural resources that can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production;
 - (2) There were no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. This condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass that occurred during normal periods of equipment downtime or preventive maintenance; and
 - (3) The operator submitted notices as required under Part III U 2.

b. The department may approve an anticipated bypass, after considering its adverse effects, if the department determines that it will meet the three conditions listed in Part III U 3 a.

V. Upset.

- 1. An "upset," as defined in 9VAC25-870-10, means an exceptional incident in which there is unintentional and temporary noncompliance with technology-based state permit effluent limitations because of factors beyond the reasonable control of the operator. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.
- 2. An upset constitutes an affirmative defense to an action brought for noncompliance with technologybased state permit effluent limitations if the requirements of Part III V 4 are met. A determination made during administrative review of claims that noncompliance was caused by upset, and before an action for noncompliance, is not a final administrative action subject to judicial review.
- 3. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventative maintenance, or careless or improper operation.
- 4. An operator who wishes to establish the affirmative defense of upset shall demonstrate, through properly signed, contemporaneous operating logs or other relevant evidence that:
 - a. An upset occurred and that the operator can identify the cause(s) of the upset;
 - b. The permitted facility was at the time being properly operated;
 - c. The operator submitted notice of the upset as required in Part III I; and
 - d. The operator complied with any remedial measures required under Part III S.
- 5. In any enforcement proceeding, the operator seeking to establish the occurrence of an upset has the burden of proof.

W. Inspection and entry. The operator shall allow the department as the board's designee, the VSMP authority, EPA, or an authorized representative of either entity (including an authorized contractor), upon presentation of credentials and other documents as may be required by law to:

- 1. Enter upon the operator's premises where a regulated facility or activity is located or conducted, or where records must be kept under the conditions of this general permit;
- 2. Have access to and copy, at reasonable times, any records that must be kept under the conditions of this general permit;
- 3. Inspect and photograph at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this general permit; and
- 4. Sample or monitor at reasonable times, for the purposes of ensuring state permit compliance or as otherwise authorized by the Clean Water Act or the Virginia Stormwater Management Act, any substances or parameters at any location.

For purposes of this section, the time for inspection shall be deemed reasonable during regular business hours, and whenever the facility is discharging. Nothing contained herein shall make an inspection unreasonable during an emergency.

X. State permit actions. State permits may be modified, revoked and reissued, or terminated for cause. The filing of a request by the operator for a state permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not stay any state permit condition.

- Y. Transfer of state permits.
- 1. State permits are not transferable to any person except after notice to the department. Except as provided in Part III Y 2, a state permit may be transferred by the operator to a new operator only if the state permit has been modified or revoked and reissued, or a minor modification made, to identify the new operator and incorporate such other requirements as may be necessary under the Virginia Stormwater Management Act and the Clean Water Act.
- 2. As an alternative to transfers under Part III Y 1, this state permit may be automatically transferred to a new operator if:
 - a. The current operator notifies the department at least 30 days in advance of the proposed transfer of the title to the facility or property;
 - b. The notice includes a written agreement between the existing and new operators containing a specific date for transfer of state permit responsibility, coverage, and liability between them; and
 - c. The department does not notify the existing operator and the proposed new operator of its intent to modify or revoke and reissue the state permit. If this notice is not received, the transfer is effective on the date specified in the agreement mentioned in Part III Y 2 b.
- 3. For ongoing construction activity involving a change of operator, the new operator shall accept and maintain the existing SWPPP, or prepare and implement a new SWPPP prior to taking over operations at the site.

Z. Severability. The provisions of this general permit are severable, and if any provision of this general permit or the application of any provision of this state permit to any circumstance, is held invalid, the application of such provision to other circumstances and the remainder of this general permit shall not be affected thereby.

DEFINITIONS

"Business day" means Monday through Friday excluding state holidays.

"Commencement of land disturbance" means the initial disturbance of soils associated with clearing, grading, or excavating activities or other construction activities (e.g., stockpiling of fill material).

"Construction site" means the land where any land-disturbing activity is physically located or conducted, including any adjacent land used or preserved in connection with the land-disturbing activity.

"Final stabilization" means that one of the following situations has occurred:

- 1. All soil disturbing activities at the site have been completed and a permanent vegetative cover has been established on denuded areas not otherwise permanently stabilized. Permanent vegetation shall not be considered established until a ground cover is achieved that is uniform (e.g., evenly distributed), mature enough to survive, and will inhibit erosion.
- 2. For individual lots in residential construction, final stabilization can occur by either:
 - a. The homebuilder completing final stabilization as specified in subdivision 1 of this definition; or
 - b. The homebuilder establishing temporary soil stabilization, including perimeter controls for an individual lot prior to occupation of the home by the homeowner, and informing the homeowner of the need for, and benefits of, final stabilization.
- 3. For construction projects on land used for agricultural purposes, final stabilization may be accomplished by returning the disturbed land to its preconstruction agricultural use. Areas disturbed that were not previously used for agricultural activities, such as buffer strips immediately adjacent to surface waters, and areas that are not being returned to their preconstruction agricultural use must meet the final stabilization criteria specified in subdivision 1 or 2 of this definition.

"Immediately" means as soon as practicable, but no later than the end of the next business day, following the day when the land-disturbing activities have temporarily or permanently ceased. In the context of this general permit, "immediately" is used to define the deadline for initiating stabilization measures.

"Impaired waters" means surface waters identified as impaired on the 2012 § 305(b)/303(d) Water Quality Assessment Integrated Report.

"Infeasible" means not technologically possible or not economically practicable and achievable in light of best industry practices.

"Initiation of stabilization activities" means:

- 1. Prepping the soil for vegetative or nonvegetative stabilization;
- 2. Applying mulch or other nonvegetative product to the exposed area;
- 3. Seeding or planting the exposed area;
- 4. Starting any of the above activities on a portion of the area to be stabilized, but not on the entire area; or
- 5. Finalizing arrangements to have the stabilization product fully installed in compliance with the applicable deadline for completing stabilization.

This list is not exhaustive.

"Measurable storm event" means a rainfall event producing 0.25 inches of rain or greater over 24 hours.

"Stabilized" means land that has been treated to withstand normal exposure to natural forces without incurring erosion damage.



Appendix C Forms: Notice of Registration and Notice of Termination

Registration Statement

	-		• • •		
General VPDES	Permit for Discharges o	f Stormwater trom	Construction	Activities	VARIO
CONTRACTOR AL MAN	I other for alloaner Boo a				

	(Ple	ease Type or Pri	nt All Information)
1.	Construction Activity Operator: (General pe signed by the appropriate person associated was Name: SB Bailard Construction Company	rmit coverage wi ith this operator.)	Il be issued to this	operator. The Certification in Item #12 must be
	CONTACT			
	Mailing Address:	Chatas VA	7: 23453	Dhono, 757-440-8555
	City, manual potent	State: ···	z ıp	Fione.
	Email address (ir available).			a 🗅
_	Indicate if DEQ may transmit general permit co	rrespondence ele	ectronically: Yes 🕒	
2.	Existing General Permit Registration Number	or (for renewais	oniy): <u>nan</u>	
3.	Name and Location of the Construction Action Name: Noriolk State University New Residential Facility	vity:		
	Address (if available): 700 Park Avenue			
	City: Nortolk		State: VA	Zip: 23504
	County (if not located within a City):			
	Latitude (decimal degrees): 36.84	Long	jitude (decimal deg	rees): - ^{76.26}
	Name and Location of all Off-site Support A	ctivities to be co	overed under the	general permit:
	Address (if available):			
	City:		State:	Zip:
	County (if not located within a City):			
	Latitude (decimal decrees);	Lond	uitude (decimal dec	rees):
	Status of the Construction Arthuity (check o	niv one): Fodor		
4. F	Status of the Construction Activity (check o	mporeist indus	rial racidantial	
φ.	Commercial Construction of New Residential Fac	ility	anal, restmention, e	grooming on the gas, etc.).
6	Name of the Receiving Water(s) and Hydrold	valc Unit Code (HUC):	
•	Name- Eastern Branch Elizabeth River	· 3 ,	Name [.]	
	HIIC: JL54		HUC:	
7.	If the discharge is through a Municipal Sepa Norfolk State University	rate Storm Sew	er System (MS4),	the name of the MS4 operator:
R	Estimated Project Start and Completion Date	B .		
	Start Date /mm/dd/una/)- 06/05/2018	••	Completion Da	te (mm/dd/www)- 07/15/2020
n.	Total Land Area of Development (to the near	rest one-hundre	dth acre): 6.10	
	Estimated Area to be Disturbed (to the near	est one-hundred	th acre); ^{5.63}	
10	le the area to be disturbed part of a larger of	ommon nian of	levelopment or s	ale? Yes No 🗸
10. 44	A stormuster pollution prevention plan (SV	VPPP) must be	prepared in acco	rdance with the requirements of the General
	VPDES Permit for Discharges of Stormwate By signing this Registration Statement the c	r from Constructor	tion Activities <u>pr</u> ying that the SWI	ior to submitting this Registration Statement. PPP has been prepared.
12.	Certification: "I certify under penalty of law the and all attachments were prepared in accordance evaluated the information submitted. Based of directly responsible for gathering the information accurate, and complete. I am aware that there fine and imprisonment for knowing violations." Printed Name:	at I have read a ice with a system in my inquiry of f tion, the informa- are significant p	nd understand this designed to assu- he person or pers ation submitted is renalties for submi	Registration Statement and that this document re that qualified personnel properly gathered and sons who manage the system or those persons to the best of my knowledge and belief true, tting false information including the possibility of Title:
	Signature:	-		Date: 6/6/2010

(Please sign in INK. This Certification must be signed by the appropriate person associated with the operator identified in item #1.)

GENERAL

A. Coverage Under this General Permit.

Any operator applying for coverage under this general permit who is required to submit a Registration Statement (see Section B below) must submit a complete Registration Statement to the Department. The Registration Statement serves as a Notice of Intent for coverage under the General VPDES Permit for Discharges of Stormwater from Construction Activities (VAR10).

B. Single-family Detached Residential Structures.

Operators with an existing stormwater discharge or proposing a new stormwater discharge associated with the construction of a single-family detached residential structure are not required to submit a Registration Statement or the Department of Environmental Quality (DEQ) portion of the general permit fee.

Operators of these types of discharges are authorized to discharge under this general permit immediately upon the general permit's effective date of July 1, 2014.

C. To Apply for Permit Coverage.

1. New Construction Activities. Any operator proposing a new stormwater discharge from construction activities shall submit a complete Registration Statement to the Department prior to the commencement of land disturbance, unless exempted by Section B above. Any operator proposing a new stormwater discharge from construction activities in response to a public emergency where the related work requires immediate authorization to avoid imminent endangerment to human health or the environment is immediately authorized to discharge under this general permit and must submit a complete Registration Statement to the Department no later than 30 days after commencing land disturbance; documentation to substantiate the occurrence of the public emergency must accompany the Registration Statement.

2. Existing Construction Activities. Any operator that was authorized to discharge under the general permit issued in 2009, and who intends to continue coverage under this general permit, shall submit a complete Registration Statement to the Department on or before June 1, 2014, unless exempted by Section B above.

D. Where to Submit Registration Statements.

All Registration Statements should be submitted to:

Department of Environmental Quality Office of Stormwater Management, 10th Floor P.O. Box 1105 Richmond, VA 23218

LINE-BY-LINE INSTRUCTIONS

Item 1: Construction Activity Operator Information.

"Operator" means the owner or operator of any facility or activity subject to the Stormwater Management Act and regulations. In the context of stormwater associated with a large or small construction activity, operator means any person associated with a construction project that meets either of the following two criteria: (i) the person has direct operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications or (ii) the person has day-to-day operational control of those activities at a project that are necessary to ensure compliance with a stormwater pollution prevention plan for the site or other state permit or VSMP authority permit conditions (i.e., they are authorized to direct workers at a site to carry out activities required by the stormwater pollution prevention plan or comply with other permit conditions). The entities that are considered operators will commonly consist of the owner or developer of a project (the party with control of project plans and specifications) or the general contractor (the party with day to day operational control of the activities at the project site which are necessary to ensure compliance with the general permit).

Provide the legal name (do not use a colloquial name), contact, mailing address, telephone number, and email address (if available) of the construction activity operator; general permit coverage will be issued to this operator. Indicate if the Department may transmit general permit correspondence electronically.

Item 2: Existing General Permit Registration Number.

For reapplications only, provide the existing general permit registration number for the construction activity. This item does not need to be completed for new construction activities applying for general permit coverage.

Item 3: Name and Location of the Construction Activity Information.

Provide the official name, street address (if available), city or county (if not located within a City) of the construction activity. Also, provide the latitude and longitude in decimal degrees of the approximate center of the construction activity (e.g., N 37.5000, W 77.5000).

Name and Location of Off-site Support Activity Information.

This general permit also authorizes stormwater discharges from support activities (e.g., concrete or asphalt batch plants, equipment staging yards, material storage areas, excavated material disposal areas, borrow areas) located on-site or off-site provided that (i) the support activity is directly related to a construction activity that is required to have general permit coverage; (ii) the support activity is not a commercial operation, nor does it serve multiple unrelated construction activities by different operators; (iii) the support activity does not operate beyond the completion of the construction activity is support; (iv) the support activity is identified in the registration statement at the time of general permit coverage; (v) appropriate control measures are identified in a SWPPP and implemented to address the discharges from the support activity areas; and (vi) all applicable state, federal, and local approvals are obtained for the support activity.

Provide the official name, street address (if available), City and County (if not located within a City) of all off-site support activities to be covered under this general permit. Also, provide the latitude and longitude in decimal degrees of the approximate center of the off-site support activities (e.g., N 37.5000, W 77.5000). Also, if an off-site support activity is going to be covered under this general permit the total land area of the off-site support activity and the estimated area to be disturbed by the off-site support activity need to be included in Item #9.

Item 4: Status of the Construction Activity.

indicate the appropriate status (Federal, State, Public, or Private) of the construction activity.

Item 5: Nature of the Construction Activity.

Provide a brief description of the construction activity, such as commercial, residential, agricultural, oil and gas, etc. This list is not all inclusive.

Item 6: Receiving Waters(s) and HUC information.

Provide the name of the receiving water(s) and corresponding HUC for all stomwater discharges including any stomwater discharges from off-site support activities to be covered under this general permit. Hydrologic Unit Code or HUC is a watershed unit established in the most recent version of Virginia's 6th order national watershed boundary dataset.

Item 7: MS4 Information.

If stormwater is discharged through a municipal separate storm sewer system (MS4), provide the name of the MS4 operator. The name of the MS4 operator is generally the Town, City, County, Institute or Federal facility where the construction activity is located.

Item 8: Construction Activity Start and Completion Date Information.

Provide the estimated start date (month/day/year) of the construction activity. Provide the estimated completion date (month/day/year) of the construction activity.

Item 9: Construction Activity Area Information.

Provide the total area (to the nearest one-hundredth acre) of the development (i.e.., the total acreage of the larger common plan of development or sale). Include the total acreage of any off-site support activity to be covered under this general permit.

Provide the estimated area (to the nearest one-hundredth acre) to be disturbed by the construction activity. Include the estimated area of land disturbance that will occur at any off-site support activity to be covered under this general permit.

Item 10: Common Plan of Development or Sale Information.

Indicate if the area to be disturbed by the construction activity is part of a larger common plan of development or sale. Larger common plan of development or sale is defined as a contiguous area where separate and distinct construction may be taking place at different times on different schedules. Plan is broadly defined as any announcement or documentation, including a sign, public notice or hearing, sales pitch, advertisement, drawing, permit application, zoning request, etc., or physical demarcation such as boundary signs, lot stakes, or surveyor markings indicating that construction activities may occur.

Item 11: Stormwater Pollution Prevention Plan (SWPPP).

A Stormwater Pollution Prevention Plan (SWPPP) must be prepared in accordance with the requirements of the General VPDES Permit for Discharges of Stormwater from Construction Activities (VAR10) prior to submitting this Registration Statement. By signing this Registration Statement the operator is certifying that the SWPPP has been prepared.

Item 12: Certification.

A properly authorized individual associated with the operator identified in item 1 of the Registration Statement is responsible for certifying and signing the Registration Statement. Please sign the Registration Statement in INK.

State statutes provide for severe penalties for submitting false information on the Registration Statement. State regulations require that the Registration Statement be signed as follows:

a. For a corporation; by a responsible corporate officer. For the purpose of this part, a responsible corporate officer means;

(i) A president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy-making or decision-making functions for the corporation, or

(ii) the manager of one or more manufacturing, production, or operating facilities, provided the manager is authorized to make management decisions that govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long-term compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

 For a partnership or sole proprietorship: by a general partner or the proprietor, respectively.

c. For a municipality, state, federal, or other public agency: by either a principal executive officer or ranking elected official. For purposes of this part, a principal executive officer of a public agency includes:

(i) The chief executive officer of the agency, or

(ii) A senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency.

Notice of Termination General VPDES Permit for Discharges of Stormwater from Construction Activities (VAR10)

(Please Type or Print All Information)

1.	Construction Activity Operator:				
	Name:				
	Contact:				
	Mailing Address:				
	City:	State:	Zip:	Phone:	
	Email address (if available):				
2.	Name and Location of the Construction A	ctivity: (As listed	on the Registratio	n Statement.)	
	Name:				
	Address (if available):				
	City:		State:	Zip:	
	County (if not located within a City):				
	Latitude (decimal degrees):		Longitude (decimal degrees):	
3.	General Permit Registration Number:		0 (0 <i>/</i>	
4.	Reason for Terminating Coverage Under more of the following conditions have been m	the General Pernet.)	rmit: (The operato	r shall submit a Notice of Term	ination after one or
	A. Necessary permanent control measur stabilization has been achieved on all p responsibility and maintenance requirem to the submission of a notice of terminati	res included in the portions of the sit <u>pents for permane</u> on;	e SWPPP for the size for which the open to on the open to one of the o	ite are in place and functioning perator is responsible. <u>When ap</u> res shall be recorded in the loca	effectively and final oplicable, long-term al land records prior
	 B. Another operator has assumed contro for the ongoing discharge; 	ol over all areas o	of the site that hav	e not been finally stabilized and	obtained coverage
	C. Coverage under an alternative VPDES	S or state permit	has been obtained	; or	
	D. For residential construction only, temp the homeowner.	oorary soil stabiliz	zation has been co	mpleted and the residence has	been transferred to
	The notice of termination should be submitted discharge terminates at midnight on the date through D above, unless otherwise notified b for the conditions set forth in subsection A a subsection A have been met or 60 days after	ed no later than 3 that the notice o by the VSMP aut above shall be e submittal of the l	30 days after one of f termination is su thority or the Depa ffective upon notil notice of terminatio	of the above conditions being m omitted for the conditions set for artment. Termination of authoriz ication from the Department the ons, whichever occurs first.	net. Authorization to rth in subsections B rations to discharge at the provisions of
5.	Permanent Control Measures Installed: (\ structural and nonstructural) that were installe if additional space is needed.)	When applicable ed to comply with	, a list of the on-s the stormwater m	ite and off-site permanent cont anagement technical criteria. A	rol measures (both ttach a separate list
	Permanent Control Measure #1				
	Type of Permanent Control Measure:				
	Date Functional:				
	Address (if available):				
	City:		State:	Zip:	
	County (if not located within a City):				
	Latitude (decimal degrees):		Longitude (decimal degrees):	

Receiving Water:_____

Total Acres Treated:______ Impervious Acres Treated:_____

Permanent Control Measure #2

	Type of Permanent Control Measure:		
	Date Functional:		
	Address (if available):		
	City:	State:	Zip:
	County (if not located within a City):		
	Latitude (decimal degrees):	Longitude (decimal de	egrees):
	Receiving Water:		
	Total Acres Treated:	Impervious Acres Tre	ated:
	Permanent Control Measure #3		
	Type of Permanent Control Measure:		
	Date Functional:		
	Address (if available):		
	City:	State:	Zip:
	County (if not located within a City):		
	Latitude (decimal degrees):	Longitude (decimal de	egrees):
	Receiving Water:		
	Total Acres Treated:	Impervious Acres Tre	ated:
6.	Participation in a Regional Stormwater Manage regional stormwater management plan. Attach a sepa	ement Plan: (When applicable, info	rmation related to the participation in a .)
	Regional Stormwater Management Facility		
	Type of Regional Stormwater Management Facility:		
	Address (if available):		
	City:	State:	Zip:
	County (if not located within a City):		
	Latitude (decimal degrees):	Longitude (decimal de	egrees):
	Total Site Acres Treated:	Impervious Site Acres	Treated:
7.	Perpetual Nutrient Credits: (When applicable, info with § 62.1-44.15:35 of the Code of Virginia. Attach a	rmation related to perpetual nutrient of separate list if additional space is ne	credits that were acquired in accordance eded.)
	Nonpoint Nutrient Credit Generating Entity		
	Name:		
	Perpetual Nutrient Credits Acquired (lbs/acre/year):_		
8.	Certification: "I certify under penalty of law that I ha all attachments were prepared in accordance with evaluated the information submitted. Based on my directly responsible for gathering the information, accurate, and complete. I am aware that there are s fine and imprisonment for knowing violations."	ve read and understand this Notice of a system designed to assure that quinquiry of the person or persons wh the information submitted is to the significant penalties for submitting false	Termination and that this document and valified personnel properly gathered and o manage the system or those persons best of my knowledge and belief true, se information including the possibility of
	Printed Name:	Title	2:
	Signature:	Dat	e:

(Please sign in INK. This Certification must be signed by the appropriate person associated with the operator identified in Item #1.)

GENERAL

A Notice of Termination must be submitted when an operator no longer wishes to be covered under the General VPDES Permit for Discharges of Stormwater from Construction Activities (VAR10).

All Notice of Terminations should be submitted to:

Department of Environmental Quality Office of Stormwater Management, 10th Floor P.O. Box 1105 Richmond, VA 23218

LINE-BY-LINE INSTRUCTIONS

Item 1: Construction Activity Operator Information.

Provide the legal name (do not use a colloquial name), contact, mailing address, telephone number, and email address (if available) of the construction activity operator that was issued general permit coverage.

Item 2: Name and Location of the Construction Activity Information.

Provide the official name, street address (if available), city or county (if not located within a City) of the construction activity. Also, provide the latitude and longitude in decimal degrees of the approximate center of the construction activity (e.g., N 37.5000, W 77.5000). NOTE: This information can be obtained from the previously submitted Registration Statement.

Item 3: General Permit Registration Number.

Provide the existing general permit registration number for the construction activity identified in Item 2.

Item 4: Reason for Termination.

Indicate the appropriate reason for submitting this Notice of Termination. The Notice of Termination may only be submitted after one or more of the following conditions have been met:

a. Necessary permanent control measures included in the SWPPP for the site are in place and functioning effectively and final stabilization has been achieved on all portions of the site for which the operator is responsible. <u>When applicable, long-term responsibility</u> and maintenance requirements for permanent control measures shall be recorded in the local land records prior to the submission of a notice of termination;

b. Another operator has assumed control over all areas of the site that have not been finally stabilized and obtained coverage for the ongoing discharge;

c. Coverage under an alternative VPDES or state permit has been obtained; or

d. For residential construction only, temporary soil stabilization has been completed and the residence has been transferred to the homeowner.

The Notice of Termination should be submitted no later than 30 days after one of the above conditions being met.

Item 5: Permanent Control Measures (when applicable).

For each on-site and off-site permanent control measure (both structural and non-structural) that was installed to comply with the stormwater management technical criteria provide the following information:

a. The type of permanent control measure;

b. The date that the permanent control measure became functional as a post-development stormwater management control;

c. The street address (if available), City or County (if not located within a City) of the permanent control measure;

d. The latitude and longitude in decimal degrees of the approximate center of the permanent control measure;

e. The receiving water of the permanent control measure; and

f. The number of total and impervious acres treated by the permanent control measure (to the nearest one-tenth of an acre).

Attach a separate list if additional space is needed.

Item 6: Participation in a Regional Stormwater Management Plan (when applicable).

For each Regional Stormwater Management Facility provide the following information:

a. The type of regional facility to which the site contributes;

b. The street address (if available), City or County (if not located within a City) of the regional facility;

c. The latitude and longitude in decimal degrees of the approximate center of the regional facility; and

d. The number of total and impervious site acres treated by the regional facility (to the nearest one-tenth of an acre).

Attach a separate list if additional space is needed.

Item 7: Perpetual Nutrient Credits (when applicable).

Provide the following information related to perpetual nutrient credits that were acquired in accordance with § 62.1-44.15:35 of the Code of Virginia:

a. The name of the nonpoint nutrient credit generating entity from which perpetual nutrient credits were acquired; and

b. The number of perpetual nutrient credits acquired (lbs. per acre per year).

Attach a separate list if additional space is needed.

Item 8: Certification.

A properly authorized individual associated with the operator identified in Item 1 of the Registration Statement is responsible for certifying and signing the Registration Statement. **Please sign the Registration Statement in INK.**

State statutes provide for severe penalties for submitting false information on the Registration Statement. State regulations require that the Registration Statement be signed as follows:

a. For a corporation: by a responsible corporate officer. For the purpose of this part, a responsible corporate officer means:

(i) A president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy-making or decision-making functions for the corporation, or

(ii) the manager of one or more manufacturing, production, or operating facilities, provided the manager is authorized to make management decisions that govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long-term compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

b. For a partnership or sole proprietorship: by a general partner or the proprietor, respectively.

c. For a municipality, state, federal, or other public agency: by either a principal executive officer or ranking elected official. For purposes of this part, a principal executive officer of a public agency includes:

(i) The chief executive officer of the agency, or

(ii) A senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency.



Appendix D Notice of Project Completion



Notice of Project Completion

Construction Activity Operator

ſ	Name:
	Title:
	Firm:
	Name:
	Address:
	Telephone:
	Date:
	Signature:

Location of Construction Activity

Name:
Title:
Firm:
Name:
Address:
Telephone:
Date:
Signature:



Project Completed Certification Under the site specific SWPPP

Certification:

"I certify under penalty of law that in signing this notice of project completion all necessary post-construction control measures included in the SWPPP for the site are in place and functioning effectively and final stabilization has been achieved on all portions of the site for which the operator is responsible."

Name:
Title:
Date:
RLD Signature:



Appendix E Record of Land Disturbance



Record of Land Disturbance

		Dates	
	Land	Land	Stabilization
Location (Attach a map showing the location of the activity)	Disturbance	Disturbance	Measures
	Began	Ended	Implemented



Appendix F Record of Inspections



Record of Site Inspection

(Attach as many sheets as necessary, including maps)

			Control Measu	ire	Incident of			
Inspection Item	Location	Туре	Maintenance Req'd (Y/N)	Additional BMP Req'd (Y/N)	Non- Compliance (Y/N) ¹	Comments	Corrective Measure	Re-Inspection
Concrete Washout Area								
Construction Entrance								
Exit								
Silt Fencing								
Stockpile								
Chemical Storage								
Equipment Storage								
Receiving Waterway								
Dry Weather Flow Pumpback								
Runoff Appearance								
Tree Protection								



			Control Measu	ire	Incident of			
Inspection Item	Location	Туре	Maintenance Req'd (Y/N)	Additional BMP Req'd (Y/N)	Non- Compliance (Y/N) ¹	Comments	Corrective Measure	Re-Inspection
Dust Control								
Dewatering Methods								
Safety Fencing								
Straw Bales								
Storm Drain Inlet Protection								
Topsoiling								
Temporary & Permanent Seeding								
Soil Stabilization Blanket Matting								
Receiving Channel								
Name:			Ti	tle:		Date:		
Signature:								

¹If no incidents of Non-Compliance have been noted above, I certify that the site complies with the provisions of this SWPPP and Permit.

²Blank lines should be used for additional inspection items including potential pollutants and items defined by owner.



Record of Potential Construction Site Pollutants

Material/Chemical	Physical Description	Stormwater Pollutant	Location



Appendix G Record of Contractor Certification



Record of Contractor Certification

"I certify under penalty of law that I understand the terms and conditions of this Virginia Stormwater Management Program (VSMP) general permit that authorizes the storm water discharges from the construction activity identified as part of this certification."

Site:_____

Contractor No
Name:
Title:
Firm:
Address:
Telephone:
Date:
Signature:
Contractor No.
Contractor No Name:
Contractor No Name: Title:
Contractor No
Contractor No
Contractor No
Contractor No



Appendix H Water Quality Protection
Water Quality Protection

Permanent BMP Description	Geographic Location	Water body Discharge	Acres Treated



Appendix I Details of Best Management Practices

Vhb

Designate Washout Areas

Instructions

Describe location(s) and controls to eliminate the potential for discharges from washout areas for concrete mixers, paint, stucco, and so on.

BMP Description

A designated temporary, above-grade concrete washout area will be constructed as detailed on the site plans. The temporary concrete washout area could be constructed as shown in the figure below, with a recommended minimum length and minimum width of 10 feet and with sufficient quantity and volume to contain all liquid and concrete waste generated by washout operations. The washout area will be lined with plastic sheeting at least 10 mils thick and free of any holes or tears. Signs will be posted marking the location of the washout area to ensure that concrete equipment operators use the proper facility.

Concrete pours will not be conducted during or before an anticipated storm event. Concrete mixer trucks and chutes will be washed in the designated area or concrete wastes will be properly disposed of off-site. When the temporary washout area is no longer needed for the construction project, the hardened concrete and materials used to construct the area will be removed and disposed of according to the maintenance section below, and the area will be stabilized.

Installation Schedule

The washout area will be constructed before concrete pours occur at the site.

Maintenance and Inspection

The washout areas will be inspected daily to ensure that all concrete washing is being discharged into the washout area, no leaks or tears are present, and to identify when concrete wastes need to be removed. The washout areas will be cleaned out once the area is filled to 75 percent of the holding capacity. Once the area's holding capacity has been reached, the concrete wastes will be allowed to harden; the concrete will be broken up, removed, and taken to a nearby Landfill for disposal. The plastic sheeting will be replaced if tears occur during removal of concrete wastes from the washout area.

vhb



Design Specifications:

- 1. Temporary concrete washout type Above Grade will be constructed as shown above, with a recommended minimum length and minimum width of 10 feet.
- 2. The washout will be a minimum of 50 feet from storm drain inlets.
- 3. Plastic lining will be free of holes, tears, or other defects that compromise the impermeability of the material.

Responsible Staff: Contractor

STD & SPEC 3.02

TEMPORARY STONE CONSTRUCTION ENTRANCE





Definition

A stabilized stone pad with a filter fabric underliner located at points of vehicular ingress and egress on a construction site.

Purpose

To reduce the amount of mud transported onto paved public roads by motor vehicles or runoff.

Conditions Where Practice Applies

Wherever traffic will be leaving a construction site and move directly onto a public road or other paved area.



Planning Considerations

Minimum Standard #17 (MS #17) requires that provisions be made to minimize the transport of sediment by vehicular traffic onto a paved surface. Construction entrances provide an area where a significant amount of mud can be removed from construction vehicle tires before they enter a public road and, just as important, the soil adjacent to the paved surface can be kept intact. A filter fabric liner is used as a "separator" to minimize the dissipation of aggregate into the underlying soil due to construction traffic loads. If the action of the vehicles traveling over the gravel pad is not sufficient to remove the majority of the mud or there exists an especially sensitive traffic situation on the adjacent paved road, the tires must be washed before the vehicle enters the public road. If washing is necessary, provisions must be made to intercept the wash water and trap the sediment so it can be collected and stabilized. Construction entrances should be used in conjunction with the stabilization of construction roads (see Std. & Spec. 3.03, CONSTRUCTION ROAD STABILIZATION) to reduce the amount of mud picked up by construction vehicles and to do a better job of mud removal. Other innovative techniques for accomplishing the same purpose (such as a bituminous entrance) can be utilized, but only after specific plans and details are submitted to and approved by the appropriate Plan-Approving Authority.

Design Criteria

Aggregate Size

VDOT #1 Coarse Aggregate (2- to 3-inch stone) should be used.

Entrance Dimensions

The aggregate layer must be at least 6 inches thick; a minimum three inches of aggregate should be placed in a cut section to give the entrance added stability and to help secure filter cloth separator. It must extend the <u>full width</u> of the vehicular ingress and egress area and have a <u>minimum 12-foot width</u>. The length of the entrance must be <u>at least 70 feet</u> (see Plate 3.02-1).

Washing

If conditions on the site are such that the majority of the mud is not removed by the vehicles traveling over the stone, then the tires of the vehicles must be washed before entering the public road. Wash water must be carried away from the entrance to a approved settling area to remove sediment. All sediment shall be prevented from entering storm drains, ditches, or watercourses. A wash rack may also be used to make washing more convenient and effective (see Plate 3.02-1).

Location

The entrance should be located to provide for maximum utilization by all construction vehicles.

3.02

Construction Specifications

The area of the entrance must be excavated a minimum of 3 inches and must be cleared of all vegetation, roots, and other objectionable material. The filter fabric underliner will then be placed the full width and length of the entrance.

Following the installation of the filter cloth, the stone shall be placed to the specified dimensions. If wash racks are used, they should be installed according to manufacturer's specifications. Any drainage facilities required because of washing should be constructed according to specifications. Conveyance of surface water under entrance, through culverts, shall be provided as required. If such conveyance is impossible, the construction of a "mountable" berm with 5:1 slopes will be permitted.

The filter cloth utilized shall be a woven or nonwoven fabric consisting only of continuous chain polymeric filaments or yarns of polyester. The fabric shall be inert to commonly encountered chemicals and hydrocarbons, be mildew and rot resistant, and conform to the physical properties noted in Table 3.02-A.

Maintenance

The entrance shall be maintained in a condition which will prevent tracking or flow of mud onto public rights-of-way. This may require periodic top dressing with additional stone or the washing and reworking of existing stone as conditions demand and repair and/or cleanout of any structures used to trap sediment. All materials spilled, dropped, washed, or tracked from vehicles onto roadways or into storm drains must be removed immediately. The use of water trucks to remove materials dropped, washed, or tracked onto roadways will not be permitted under any circumstances.







TABLE 3.02-A

CONSTRUCTION SPECIFICATIONS FOR FILTER CLOTH UNDERLINER

Fabric Properties ¹	Light-Duty Entrance ² (Graded Subgrade)	Heavy-Duty Entrance ³ (Rough Graded)	Test Method
Grab Tensile Strength (lbs.)	200	220	ASTM D1682
Elongation at Failure (%)	50	220	ASTM D1682
Mullen Burst Strength (lbs.)	190	430	ASTM D3786
Puncture Strength (lbs.)	40	125	ASTM D751 (modified)
Equivalent Openin Size (mm)	g 40-80	40-80	U.S. Standard Sieve CW-02215

 1 Fabrics not meeting these specifications may be used only when design procedure and supporting documentation are supplied to determine aggregate depth and fabric strength.

² <u>Light Duty Entrance</u>: Sites that have been graded to subgrade and where most travel would be single axle vehicles and an occasional multi-axle truck. Examples of fabrics which can be used are: Trevira Spunbond 1115, Mirafi 100X, Typar 3401, or equivalent.

³ <u>Heavy Duty Entrance</u>: Sites with only rough grading and where most travel would be multi-axle vehicles. Examples of fabrics which can be used are: Trevira Spunbond 1135, Mirafi 600X, or equivalent.

Source: Virginia Highway and Transportation Research Council (VHTRC)

STD & SPEC 3.05



SILT FENCE



Definition

A temporary sediment barrier consisting of a synthetic filter fabric stretched across and attached to supporting posts and entrenched.

Purposes

- 1. To intercept and detain small amounts of sediment from disturbed areas during construction operations in order to prevent sediment from leaving the site.
- 2. To decrease the velocity of sheet flows and low-to-moderate level channel flows.



Conditions Where Practice Applies

- 1. Below disturbed areas where erosion would occur in the form of sheet and rill erosion.
- 2. Where the size of the drainage area is no more than one quarter acre per 100 feet of silt fence length; the maximum slope length behind the barrier is 100 feet; and the maximum gradient behind the barrier is 50 percent (2:1).
- 3. In minor swales or ditch lines where the maximum contributing drainage area is no greater than 1 acre and flow is no greater than 1 cfs.
- 4. Silt fence will not be used in areas where rock or some other hard surface prevents the full and uniform depth anchoring of the barrier.

Planning Considerations

Laboratory work at the Virginia Highway and Transportation Research Council (VHTRC) has shown that silt fences can trap a much higher percentage of suspended sediments than straw bales, though silt fence passes the sediment-laden water slower. Silt fences are preferable to straw barriers in many cases because of their durability and potential cost savings. While the failure rate of silt fences is lower than that of straw barriers, many instances have been observed where silt fences are improperly installed, inviting failure and sediment loss. The installation methods outlined here can improve performance and reduce failures.

As noted, flow rate through silt fence is significantly lower than the flow rate for straw bale barriers. This creates more ponding and hence more time for sediment to fall out. Table 3.05-A demonstrates these relationships.

Both woven and non-woven synthetic fabrics are commercially available. The woven fabrics generally display higher strength than the non-woven fabrics and, in most cases, do not require any additional reinforcement. When tested under acid and alkaline water conditions, most of the woven fabrics increase in strength, while the reactions of non-woven fabrics to these conditions are variable. The same is true of testing under extensive ultraviolet radiation. Permeability rates vary regardless of fabric type. While all of the fabrics demonstrate very high filtering efficiencies for sandy sediments, there is considerable variation among both woven and non-woven fabrics when filtering the finer silt and clay particles.

Design Criteria

1. No formal design is required. As with straw bale barriers, an effort should be made to locate silt fence at least 5 feet to 7 feet beyond the base of disturbed slopes with grades greater than 7%.

TABLE 3.05-A TYPICAL FLOW RATES AND FILTERING EFFICIENCIES OF PERIMETER CONTROL				
Straw	5.6	67		

Source: VHTRC

- 2. The use of silt fences, because they have such a low permeability, is limited to situations in which only sheet or overland flows are expected and where concentrated flows originate from drainage areas of 1 acre or less.
- 3. Field experience has demonstrated that, in many instances, silt fence is installed too short (less than 16 inches above ground elevation). The short fence is subject to breaching during even small storm events and will require maintenance "clean outs" more often. Properly supported silt fence which stands 24 to 34 inches above the existing grade tends to promote more effective sediment control.

Construction Specifications

Materials

- 1. Synthetic filter fabric shall be a pervious sheet of propylene, nylon, polyester or ethylene yarn and shall be certified by the manufacturer or supplier as conforming to the requirements noted in Table 3.05-B.
- 2. Synthetic filter fabric shall contain ultraviolet ray inhibitors and stabilizers to provide a minimum of six months of expected usable construction life at a temperature range of 0° F to 120° F.
- 3. If <u>wooden stakes</u> are utilized for silt fence construction, they must have a diameter of 2 inches when oak is used and 4 inches when pine is used. Wooden stakes must have a minimum length of 5 feet.

TABLE 3.05-B PHYSICAL PROPERTIES OF FILTER FABRIC IN SILT FENCE					
Physical Property	Test	Requirements			
Filtering Efficiency	ASTM 5141	75% (minimum)			
Tensile Strength at 20% (max.) Elongation*	VTM-52	Extra Strength - 50 lbs./linear inch (minimum)			
		Standard Strength - 30 lbs./linear inch (minimum)			
Flow Rate	ASTM 5141	0.2 gal./sq.ft./ minute (minimum)			
Ultraviolet Radiation Stability %	ASTM-G-26	90% (minimum)			
* Requirements reduced by 50% after six months of installation.					

Source: VHTRC

- 4. If <u>steel posts</u> (standard "U" or "T" section) are utilized for silt fence construction, they must have a minimum weight of 1.33 pounds per linear foot and shall have a minimum length of 5 feet.
- 5. Wire fence reinforcement for silt fences using standard-strength filter cloth shall be a minimum of 14 gauge and shall have a maximum mesh spacing of 6 inches.

Installation

1. The height of a silt fence shall be a minimum of 16 inches above the original ground surface and shall not exceed 34 inches above ground elevation.

- 2. The filter fabric shall be purchased in a continuous roll cut to the length of the barrier to avoid the use of joints. When joints are unavoidable, filter cloth shall be spliced together only at a support post, with a minimum 6-inch overlap, and securely sealed.
- 3. A trench shall be excavated approximately 4-inches wide and 4-inches deep on the upslope side of the proposed location of the measure.
- 4. When <u>wire support is used</u>, standard-strength filter cloth may be used. Posts for this type of installation shall be placed a <u>maximum of 10-feet apart</u> (see Plate 3.05-1). The wire mesh fence must be fastened securely to the <u>upslope</u> side of the posts using heavy duty wire staples at least one inch long, tie wires or hog rings. The wire shall extend into the trench a minimum of two inches and shall not extend more than 34 inches above the original ground surface. The standard-strength fabric shall be stapled or wired to the wire fence, and 8 inches of the fabric shall be extended into the trench. The fabric shall not be stapled to existing trees.
- 5. When <u>wire support is not used</u>, extra-strength filter cloth shall be used. Posts for this type of fabric shall be placed a <u>maximum of 6-feet apart</u> (see Plate 3.05-2). The filter fabric shall be fastened securely to the upslope side of the posts using one inch long (minimum) heavy-duty wire staples or tie wires and eight inches of the fabric shall be extended into the trench. The fabric shall not be stapled to existing trees. This method of installation has been found to be more commonplace than #4.
- 6. If a silt fence is to be constructed across a ditch line or swale, the measure must be of sufficient length to eliminate endflow, and the plan configuration shall resemble an arc or horseshoe with the ends oriented upslope (see Plate 3.05-2). Extra-strength filter fabric shall be used for this application with a maximum 3-foot spacing of posts.

All other installation requirements noted in #5 apply.

- 7. The 4-inch by 4-inch trench shall be backfilled and the soil compacted over the filter fabric.
- 8. Silt fences shall be removed when they have served their useful purpose, but not before the upslope area has been permanently stabilized.











Maintenance

- 1. Silt fences shall be inspected immediately after each rainfall and at least daily during prolonged rainfall. Any required repairs shall be made immediately.
- 2. Close attention shall be paid to the repair of damaged silt fence resulting from end runs and undercutting.
- 3. Should the fabric on a silt fence decompose or become ineffective prior to the end of the expected usable life and the barrier still be necessary, the fabric shall be replaced promptly.
- 4. Sediment deposits should be removed after each storm event. They must be removed when deposits reach approximately one-half the height of the barrier.
- 5. Any sediment deposits remaining in place after the silt fence is no longer required shall be dressed to conform with the existing grade, prepared and seeded.

STD & SPEC 3.07

STORM DRAIN



Definition

A sediment filter or an excavated impounding area around a storm drain drop inlet or curb inlet.

Purpose

To prevent sediment from entering storm drainage systems prior to permanent stabilization of the disturbed area.

Conditions Where Practice Applies

Where storm drain inlets are to be made operational before permanent stabilization of the corresponding disturbed drainage area. Different types of structures are applicable to different conditions (see Plates 3.07-1 through 3.07-8).



Planning Considerations

Storm sewers which are made operational prior to stabilization of the associated drainage areas can convey large amounts of sediment to natural drainageways. In case of extreme sediment loading, the storm sewer itself may clog and lose a major portion of its capacity. To avoid these problems, it is necessary to prevent sediment from entering the system at the inlets.

This practice contains several types of inlet filters and traps which have different applications dependent upon site conditions and type of inlet. Other innovative techniques for accomplishing the same purpose are encouraged, but only after specific plans and details are submitted to and approved by the appropriate Plan-Approving Authority.

Care should be taken when choosing a specific type of inlet protection. Field experience has shown that inlet protection which causes excessive ponding in an area of high construction activity may become so inconvenient that it is removed or bypassed, thus transmitting sediment-laden flows unchecked. In such situations, a structure with an adequate overflow mechanism should be utilized.

The following inlet protection devices are for drainage areas of <u>one acre or less</u>. Runoff from larger disturbed areas should be routed to a TEMPORARY SEDIMENT TRAP (Std. & Spec. 3.13) or a TEMPORARY SEDIMENT BASIN (Std. & Spec. 3.14).

The best way to prevent sediment from entering the storm sewer system is to stabilize the site as quickly as possible, preventing erosion and stopping sediment at its source.

Stone is utilized as the chief ponding/filtering agent in most of the inlet protection types described in this specification. The various types of "coarse aggregates" which are depicted are able to filter out sediment mainly through slowing down flows directed to the inlet by creating an increased flow path for the stormwater (through void space in the respective stone). The stone filtering medium by no means slows stormwater flowrate as does filter cloth and therefore cannot provide the same degree of filter efficiency when smaller silt and clay particles are introduced into stormwater flows. However, as mentioned earlier, excessive ponding in busy areas adjacent to stormwater inlets is in many cases unacceptable - that is why stone must be utilized with many installations.

Fortunately, in most instances, inlet protection utilizing stone should not be the sole control measure. At the time that storm sewer inlet and associated appurtances become operational, areas adjacent to the structures are most likely at final grade or will not be altered for extended periods; this is the time when TEMPORARY SEEDING (Std. & Spec. 3.31) and other appropriate controls should be implemented to enhance sediment-loss mitigation. In addition, by varying stone sizes used in the construction of inlet protection, a greater degree of sediment removal can be obtained. As an option, filter cloth can be used with the stone in these devices to further enhance sediment removal. Notably, the potential inconvenience of excessive ponding must be examined with these choices, especially the latter.

- 1. The drainage area shall be no greater than 1 acre.
- 2. The inlet protection device shall be constructed in a manner that will facilitate cleanout and disposal of trapped sediment and minimize interference with construction activities.
- 3. The inlet protection devices shall be constructed in such a manner that any resultant ponding of stormwater will not cause excessive inconvenience or damage to adjacent areas or structures.
- 4. Design criteria more specific to each particular inlet protection device will be found on Plates 3.07-1 through 3.07-8.
- 5. For the inlet protection devices which utilize stone as the chief ponding/filtering medium, a range of stone sizes is offered; VDOT #3, #357, or #5 Coarse Aggregate should be used. The designer/plan reviewer should attempt to get the greatest amount of filtering action possible (by using smaller-sized stone), while not creating significant ponding problems.
- 6. In all designs which utilize stone with a wire-mesh support as a filtering mechanism, the stone can be <u>completely wrapped</u> with the wire mesh to improve stability and provide easier cleaning.
- 7. <u>Filter Fabric</u> may be added to any of the devices which utilize "coarse aggregate" stone to significantly enhance sediment removal. The fabric, which must meet the physical requirements noted for "extra strength" found in Table 3.05-B, should be secured between the stone and the inlet (on wire-mesh if it is present). As a result of the significant increase in filter efficiency provided by the fabric, a larger range of stone sizes (VDOT #1, #2 or #3 Coarse Aggregate) may be utilized with such a configuration. The larger stone will help keep larger sediment masses from clogging the cloth. Notably, significant ponding may occur at the inlet if filter cloth is utilized in this manner.

Construction Specifications

- 1. <u>Silt Fence Drop Inlet Protection</u>
 - a. Silt Fence shall conform to the construction specifications for "extra strength" found in Table 3.05-B and shall be cut from a continuous roll to avoid joints.
 - b. For stakes, use 2 x 4-inch wood (preferred) or equivalent metal with a minimum length of 3 feet.

- c. Space stakes evenly around the perimeter of the inlet a <u>maximum of 3-feet</u> <u>apart</u>, and securely drive them into the ground, approximately 18-inches deep (see Plate 3.07-1).
- d. To provide needed stability to the installation, frame with 2 x 4-inch wood strips around the crest of the overflow area at a maximum of $1\frac{1}{2}$ feet above the drop inlet crest.
- e. Place the bottom 12 inches of the fabric in a trench (see Plate 3.07-1) and backfill the trench with 12 inches of compacted soil.
- f. Fasten fabric securely by staples or wire to the stakes and frame. Joints must be overlapped to the next stake.
- g. It may be necessary to build a temporary dike on the downslope side of the structure to prevent bypass flow.

2. Gravel and Wire Mesh Drop Inlet Sediment Filter

- a. Wire mesh shall be laid over the drop inlet so that the wire extends a minimum of 1 foot beyond each side of the inlet structure. Wire mesh with 1/2-inch openings shall be used. If more than one strip of mesh is necessary, the strips shall be overlapped.
- b. Coarse aggregate shall be placed over the wire mesh as indicated on Plate 3.07-2. The depth of stone shall be at least 12 inches over the entire inlet opening. The stone shall extend beyond the inlet opening at least 18 inches on all sides.
- c. If the stone filter becomes clogged with sediment so that it no longer adequately performs its function, the stones must be pulled away from the inlet, cleaned and/or replaced.

Note: This filtering device has no overflow mechanism; therefore, ponding is likely especially if sediment is not removed regularly. This type of device must <u>never</u> be used where overflow may endanger an exposed fill slope. Consideration should also be given to the possible effects of ponding on traffic movement, nearby structures, working areas, adjacent property, etc.

3. Block and Gravel Drop Inlet Sediment Filter

a. Place concrete blocks lengthwise on their sides in a single row around the perimeter of the inlet, with the ends of adjacent blocks abutting. The height of the barrier can be varied, depending on design needs, by stacking combinations of 4-inch, 8-inch and 12-inch wide blocks. The barrier of blocks shall be at least 12-inches high and no greater than 24-inches high.



Planning and Design Manual, 1988



Source: Va. DSWC

- b. Wire mesh shall be placed over the outside vertical face (webbing) of the concrete blocks to prevent stone from being washed through the holes in the blocks. Wire mesh with 1/2-inch openings shall be used.
- c. Stone shall be piled against the wire to the top of the block barrier, as shown in Plate 3.07-3.
- d. If the stone filter becomes clogged with sediment so that it no longer adequately performs its function, the stone must be pulled away from the blocks, cleaned and replaced.
- 4. Excavated Drop Inlet Sediment Trap
 - a. The excavated trap shall be sized to provide a minimum storage capacity calculated at the rate of 134 cubic yards per acre of drainage area. A trap shall be no less than 1-foot nor more than 2-feet deep measured from the top of the inlet structure. Side slopes shall not be steeper than 2:1 (see Plate 3.07-4).
 - b. The slope of the basin may vary to fit the drainage area and terrain. Observations must be made to check trap efficiency and modifications shall be made as necessary to ensure satisfactory trapping of sediment. Where an inlet is located so as to receive concentrated flows, such as in a highway median, it is recommended that the basin have a rectangular shape in a 2:1 (length/width) ratio, with the length oriented in the direction of the flow.
 - c. Sediment shall be removed and the trap restored to its original dimensions when the sediment has accumulated to one-half the design depth of the trap. Removed sediment shall be deposited in a suitable area and in a manner such that it will not erode.
- 5. Sod Drop Inlet Sediment Filter
 - a. Soil shall be prepared and sod installed according to the specifications in Std. & Spec. 3.33, SODDING.
 - b. Sod shall be placed to form a turf mat covering the soil for a distance of 4 feet from each side of the inlet structure, as depicted in Plate 3.07-5.
- 6. Gravel Curb Inlet Sediment Filter
 - a. Wire mesh with 1/2-inch openings shall be placed over the curb inlet opening so that at least 12 inches of wire extends across the inlet cover and at least 12 inches of wire extends across the concrete gutter from the inlet opening, as depicted in Plate 3.07-6.



Source: Va. DSWC



Source: Michigan Soil Erosion and Sediment Control Guidebook, 1975, and USDA-SCS



Source: Va. DSWC



Source: Va. DSWC

- b. Stone shall be piled against the wire so as to anchor it against the gutter and inlet cover and to cover the inlet opening completely.
- c. If the stone filter becomes clogged with sediment so that it no longer adequately performs its function, the stone must be pulled away from the block, cleaned and replaced.

7. Curb Inlet Protection with 2-inch x 4-inch Wooden Weir

- a. Attach a continuous piece of wire mesh (30-inch minimum width x inlet throat length plus 4 feet) to the 2-inch x 4-inch wooden weir (with a total length of throat length plus 2 feet) as shown in Plate 3.07-7. Wood should be "construction grade" lumber.
- b. Place a piece of approved "extra-strength" filter cloth of the same dimensions as the wire mesh over the wire mesh and securely attach to the 2-inch x 4-inch weir.
- c. Securely nail the 2-inch x 4-inch weir to the 9-inch long vertical spacers which are to be located between the weir and inlet face at a maximum 6-foot spacing.
- d. Place the assembly against the inlet throat and nail 2-foot (minimum) lengths of 2-inch x 4-inch board to the top of the weir at spacer locations. These 2inch x 4-inch anchors shall extend across the inlet tops and be held in place by sandbags or alternate weight.
- e. The assembly shall be placed so that the end spacers are a minimum 1 foot beyond both ends of the throat opening.
- f. Form the wire mesh and filter cloth to the concrete gutter and against the face of curb on both sides of the inlet. Place coarse aggregate over the wire mesh and filter fabric in such a manner as to prevent water from entering the inlet under or around the filter cloth.
- g. This type of protection must be inspected frequently and the filter cloth and stone replaced when clogged with sediment.
- h. Assure that storm flow does not bypass inlet by installing temporary earth or asphalt dikes directing flow into inlet.

8. Block and Gravel Curb Inlet Sediment Filter

a. Two concrete blocks shall be placed on their sides abutting the curb at either side of the inlet opening.



Source: <u>1983 Maryland Standards and Specifications for</u> <u>Soil Erosion and Sediment Control</u>, and USDA-SCS

- b. A 2-inch x 4-inch stud shall be cut and placed through the outer holes of each spacer block to help keep the front blocks in place.
- c. Concrete blocks shall be placed on their sides across the front of the inlet and abutting the spacer blocks as depicted in Plate 3.07-8.
- d. Wire mesh shall be placed over the outside vertical face (webbing) of the concrete blocks to prevent stone from being washed through the holes in the blocks. Wire mesh with 1/2-inch openings shall be used.
- e. Coarse aggregate shall be piled against the wire to the top of the barrier as shown in Plate 3.07-8.
- f. If the stone filter becomes clogged with sediment so that it no longer adequately performs its function, the stone must be pulled away from the blocks, cleaned and/or replaced.

Maintenance

- 1. The structure shall be inspected after each rain and repairs made as needed.
- 2. Sediment shall be removed and the trap restored to its original dimensions when the sediment has accumulated to one half the design depth of the trap. Removed sediment shall be deposited in a suitable area and in such a manner that it will not erode.
- 3. Structures shall be removed and the area stabilized when the remaining drainage area has been properly stabilized.



Source: Va. DSWC

STD & SPEC 3.08



CULVERT INLET PROTECTION



Definition

A sediment filter located at the inlet to storm sewer culverts.

Purposes

- 1. To prevent sediment from entering, accumulating in and being transferred by a culvert and associated drainage system prior to permanent stabilization of a disturbed project area.
- 2. To provide erosion control at culvert inlets during the phase of a project where elevation and drainage patterns change, causing original control measures to be ineffective or in need of removal.



Conditions Where Practice Applies

Where culvert and associated drainage system is to be made operational prior to permanent stabilization of the disturbed drainage area. Different types of structures are applicable to different conditions (see Plates 3.08-1 and 3.08-2).

Planning Considerations

When construction on a project reaches a stage where culverts and other storm sewer appurtenances are installed and many areas are brought to a desired grade, the erosion control measures used in the early stages normally need to be modified or may need to be removed altogether. At that time, there is a need to provide protection at the points where runoff will leave the area via culverts and drop or curb inlets.

Similar to drop and curb inlets, culverts which are made operational prior to stabilization of the associated drainage areas can convey large amounts of sediment to natural drainageways. In case of extreme sediment loading, the pipe or pipe system itself may clog and lose a major portion of its capacity. To avoid these problems, it is necessary to prevent sediment from entering the culvert by using one of the methods noted in this section.

General Guidelines (All Types)

- 1. The inlet protection device shall be constructed in a manner that will facilitate cleanout and disposal of trapped sediment and minimize interference with construction activities.
- 2. The inlet protection devices shall be constructed in such a manner that any resultant ponding of stormwater will not cause excessive inconvenience or damage to adjacent areas or structures.
- 3. Design criteria more specific to each particular inlet protection device will be found in Plates 3.08-1 through 3.08-2.

Design Criteria

- 1. <u>Silt Fence Culvert Inlet Protection</u>
 - a. No formal design is required.
 - b. Silt fence culvert inlet protection has an expected maximum usable life of three months.
 - c. The maximum area draining to this practice shall not exceed one acre.

- a. Runoff storage requirements shall be in accordance with information outlined under Std. & Spec. 3.13, TEMPORARY SEDIMENT TRAP.
- b. Culvert inlet sediment traps have a maximum expected useful life of 18 months.
- c. The maximum area draining to this practice shall not exceed 3 acres.

Construction Specifications

1. <u>Silt Fence Culvert Inlet Protection</u>

- a. The height of the silt fence (in front of the culvert opening) shall be a minimum of 16 inches and shall not exceed 34 inches.
- b. Extra strength filter fabric with a maximum spacing of stakes of 3 feet shall be used to construct the measure.
- c. The placement of silt fence should be approximately 6 feet from the culvert in the direction of incoming flow, creating a "horseshoe" shape as shown in Plate 3.08-1.
- d. <u>If silt fence cannot be installed properly</u> or the flow and/or velocity of flow to the culvert protection is excessive and may breach the structure, the <u>stone</u> <u>combination</u> noted in Plate 3.08-1 should be utilized.

2. Culvert Inlet Sediment Trap

- a. Geometry of the design will be a "horseshoe" shape around the culvert inlet (see Plate 3.08-2).
- b. The toe of riprap (composing the sediment filter dam) shall be no closer than 24" from the culvert opening in order to provide an acceptable emergency outlet for flows from larger storm events.
- c. All other "Construction Specifications" found within Std. & Spec. 3.13, TEMPORARY SEDIMENT TRAP, also apply to this practice.
- e. The proper installation of the culvert inlet sediment trap is <u>a viable substitute</u> for the installation of the TEMPORARY SEDIMENT TRAP.






Source: North Carolina Sediment Control Commission

Plate 3.08-2

Maintenance

- 1. The structure shall be inspected after each rain and repairs made as needed.
- 2. Aggregate shall be replaced or cleaned when inspection reveals that clogged voids are causing ponding problems which interfere with on-site construction.
- 3. Sediment shall be removed and the impoundment restored to its original dimensions when sediment has accumulated to one-half the design depth. Removed sediment shall be deposited in a suitable area and in such a manner that it will not erode and cause sedimentation problems.
- 4. Temporary structures shall be removed when they have served their useful purpose, but not before the upslope area has been permanently stabilized.

STD & SPEC 3.31



TEMPORARY SEEDING

Definition

The establishment of a temporary vegetative cover on disturbed areas by seeding with appropriate rapidly growing annual plants.

Purposes

- To reduce erosion and sedimentation by stabilizing disturbed areas that will not be brought to final grade for a period of more than 30 days. RWE; DEQ-OTS 14 - RWE; DEQ-OTS 3-12-14
- To reduce damage from sediment and runoff to downstream or off-site areas, and to provide protection to bare soils exposed during construction until permanent vegetation or other erosion control measures can be established.



3.31

Conditions Where Practice Applies

Where exposed soil surfaces are not to be fine graded for periods longer than 14 days. Such areas include denuded areas, soil stockpiles, dikes, dams, sides of sediment basins, temporary roadbanks, etc. (see MS #1 and MS #2). A permanent vegetative cover shall be applied to areas that will be left dormant for a period of more than 1 year.

Planning Considerations

Sheet erosion, caused by the impact of rain on bare soil, is the source of most fine particles in sediment. To reduce this sediment load in runoff, the soil surface itself should be protected. The most efficient and economical means of controlling sheet and rill erosion is to establish vegetative cover. Annual plants which sprout rapidly and survive for only one growing season are suitable for establishing temporary vegetative cover. Temporary seeding is encouraged whenever possible to aid in "controlling" construction sites.

Temporary seeding also prevents costly maintenance operations on other erosion control systems. For example, sediment basin clean-outs will be reduced if the drainage area of the basin is seeded where grading and construction are not taking place. Perimeter dikes will be more effective if not choked with sediment.

Temporary seeding is essential to preserve the integrity of earthen structures used to control sediment, such as dikes, diversions, and the banks and dams of sediment basins.

Proper seedbed preparation and the use of quality seed are important in this practice just as in permanent seeding. Failure to carefully follow sound agronomic recommendations will often result in an inadequate stand of vegetation that provides little or no erosion control.

Specifications

Prior to seeding, install necessary erosion control practices such as dikes, waterways, and basins.

Plant Selection

Select plants appropriate to the season and site conditions from Tables 3.31-B and 3.31-C. Note that Table 3.31-B presents plants which can be used without extensive evaluation of site conditions; Table 3.31-C presents more in-depth information on the plant materials.

Seedbed Preparation

To control erosion on bare soil surfaces, plants must be able to germinate and grow. Seedbed preparation is essential.

1. <u>Liming</u>: An evaluation should be conducted to determine if lime is necessary for temporary seeding. In most soils, it takes up to 6 months for a pH adjustment to occur following the application of lime. Therefore, it may be difficult to justify the cost of liming a temporary site, especially when the soil will later be moved and regraded. The following table may be used to determine the actual need along with suggested application rates.

TABLE 3.31-A				
LIMIN FOR '	IG REQUIREMENTS IEMPORARY SITES			
pH Test	Recommended Application of Agricultural Limestone			
below 4.2	3 tons per acre			
4.2 to 5.2	2 tons per acre			
5.2 to 6	1 ton per acre			

Source: Va. DSWC

- 2. <u>Fertilizer</u>: Shall be applied as 600 lbs./acre of 10-20-10 (14 lbs./1,000 sq. ft.) or equivalent nutrients. Lime and fertilizer shall be incorporated into the top 2 to 4 inches of the soil if possible.
- 3. <u>Surface Roughening</u>: If the area has been recently loosened or disturbed, no further roughening is required. When the area is compacted, crusted, or hardened, the soil surface shall be loosened by discing, raking, harrowing, or other acceptable means (see SURFACE ROUGHENING, Std. & Spec. 3.29).
- 4. <u>Tracking</u>: Tracking with bulldozer cleats is most effective on sandy soils. This practice often causes undue compaction of the soil surface, especially in clayey soils, and does not aid plant growth as effectively as other methods of surface roughening.

Seeding

Seed shall be evenly applied with a broadcast seeder, drill, cultipacker seeder or hydroseeder. Small grains shall be planted no more than $1\frac{1}{2}$ inches deep. Small seeds, such as Kentucky Bluegrass, should be planted no more than 1/4 inch deep. Other Grasses and Legumes should be planted from 1/4 inch to 1/2 inch deep.

3.31

÷ •...

1992

Mulching

- 1. Seedings <u>made in fall for winter cover and during hot and dry summer months</u> shall be mulched according to MULCHING, Std. & Spec. 3.35, except that hydromulches (fiber mulch) will not be considered adequate. Straw mulch should be used during these periods.
- 2. Temporary seedings made under favorable soil and site conditions during optimum spring and fall seeding dates may not require mulch.

Re-seeding

Areas which fail to establish vegetative cover adequate to prevent rill erosion will be reseeded as soon as such areas are identified.

	TABLE 3.31-B		
ACCEPTABLE TEMPORARY SEEDING PLANT MATERIALS			
"QUIC	K REFERENCE FOR ALL REGIO	NS"	
Planting Dates	Species	Rate <u>(lbs./acre)</u>	
Sept. 1 - Feb. 15	50/50 Mix of Annual Ryegrass (Lolium multi-florum) & Cereal (Winter) Rye (Secale cereale)	50 - 100	
eb. 16 - Apr. 30	Annual Ryegrass (Lolium multi-florum)	60 - 100	
May 1 - Aug 31	German Millet (Setaria italica)	50	

Source: Va. DSWC

TABLE 3.31-C

TEMPORARY SEEDING PLANT MATERIALS, SEEDING RATES, AND DATES

992			Ī	1	Ī		T	3.31
	PLANT CHARACTERISTICS	Use spring varieties (e.g., Noble).	Use for late fall seedings, winter cover. Tolerates cold and low moisture.	Warm-season annual. Dies at first frost. May be added to summer mixes.	May be added in mixes. Will mow out of most stands.	Warm-scason perenuial. May bunch. Tolerates hot, dry slopes and acid, infertile soils. May be added to mixes.	Warm season annual legume. Tolerates acid soils. May be added to mixes.	
4I	9/1 to 11/15	1	X	ŧ	х	I	t	
SOUTH	5/1 to 9/1	1	I	X	ŀ	×	x	
	2/15 to 4/30	×	×	ı	х	•	×	
	8/15 to 11/1	ı	×	Þ	x	a	I	Ċ.
ORTH ⁴	5/1 to 8/15	,		×	ı	×	×	ad 3.22.
Z	3/1 to 4/30	×	×		×	ı	×	.22-1 ar
ATE	1000 ft ²	2 Ibs.	2.5 lbs.	approx, 1 lb.	1½ lbs.	51⁄2 ozs.	approx. 1½ ibs.	. See Plates 3 seeding. eding.
SEEDING R	Acre	3 bu. (up to 100 lbs., not less than 50 lbs.)	2 bu. (up to 110 lbs., not less than 50 lbs.)	50 lbs.	60 lbs.	15 lbs.	25 lbs.	and Mountain region. and Coastal Plain. over crop with spring over crop with fall se ween these dates. between these dates.
	SPECIES	OATS (Avena sativa)	RYE ^d (Secale cereale)	GERMAN MILLET (Setaria italica)	ANNUAL RYEGRASS [©] (Lolium multi-florum)	WEEPING LOVEGRASS (Eragrostis curvula)	KOREAN LESPEDEZA ^c (Lespedeza <u>stipulacea</u>)	 ^a Northern Piedmont ^b Southern Piedmont ^c May be used as a co ^d May be used as a co X May be planted bet May not be planted

III - 288

STD & SPEC 3.32



PERMANENT SEEDING

Definition

The establishment of perennial vegetative cover on disturbed areas by planting seed.

Purposes

- 1. To reduce erosion and decrease sediment yield from disturbed areas.
- 2. To permanently stabilize disturbed areas in a manner that is economical, adaptable to site conditions, and allows selection of the most appropriate plant materials.
- 3. To improve wildlife habitat.
- 4. To enhance natural beauty.



Conditions Where Practice Applies

- 1. Disturbed areas where permanent, long-lived vegetative cover is needed to stabilize the soil.
- 2. Rough-graded areas which will not be brought to final grade for a year or more.

Planning Considerations

Vegetation controls erosion by reducing the velocity and the volume of overland flow and protecting the bare soil surface from raindrop impact.

Areas which must be stabilized after the land has been disturbed require vegetative cover. The most common and economical means of establishing this cover is by seeding grasses and legumes. Permanent vegetative covers must meet the requirements of Minimum Standard #3.

Advantages of seeding over other means of establishing plants include the small initial establishment cost, the wide variety of grasses and legumes available, low labor requirement, and ease of establishment in difficult areas.

Disadvantages which must be dealt with are the potential for erosion during the establishment stage, a need to reseed areas that fail to establish, limited periods during the year suitable for seeding, the potential need for weed control during the establishment phase, and a need for water and appropriate climatic conditions during germination.

There are so many variables in plant growth that an end product cannot be guaranteed. Much can be done in the planning stages to increase the chances for successful seeding. Selection of the right plant materials for the site, good seedbed preparation, and conscientious maintenance are important.

<u>SELECTING PLANT MATERIALS</u>: The factors affecting plant growth are climate, soils, and topography. In Virginia, there are three major physiographic regions that reflect changes in soil and topography. In selecting appropriate plant materials, one should take into account the characteristics of the physiographic region in which the project is located (see Plate 3.32-1).

PHYSIOGRAPHIC REGIONS:

<u>Coastal Plain</u> - Soils on the Coastal Plain are deeply weathered, stratified deposits of sand and clay. They are generally acidic and low in plant nutrients. The sandy soils are hot and droughty in summer. This region receives more rain and is warmer than the other regions of the state. The land is fairly level, and many areas are poorly drained. Warm season grasses traditionally perform well in these areas.





<u>Piedmont</u> - Soils on the Piedmont plateau are highly variable. They tend to be shallow, with clavey subsoils. Piedmont soils are low in phosphorus. Soils derived

shallow, with clayey subsoils. Piedmont soils are low in phosphorus. Soils derived from mica schist are highly erodible. Topography is rolling and hilly. The southern Piedmont has much the same climate as the Coastal Plain. Often referred to as the "transition zone" in planting. Contains areas that will support both warm or cool season grasses.

Appalachian and Blue Ridge Region - This region is divided into plateaus, mountains, and narrow valleys. Soils tend to be shallow and acid, and may erode rapidly on steep slopes. Shaley slopes are often unstable and droughty. This area is colder and drier than the rest of the State. The rugged topography makes plant establishment difficult. Cool season grasses are normally specified in this region.

<u>SOILS</u>: On the whole, soils in Virginia always require some nitrogen (N) fertilization to establish plants. Phosphorus (P) and potassium (K) are usually needed. Except for some small pockets of shallow limestone soils, lime is universally needed.

Soils can be modified with lime and fertilizer, but climate cannot be controlled. For this reason, the State has been divided into two major climatic regions, referred to as the Northern Piedmont and Mountain Region and the Southern Piedmont and Coastal Plain Region, for grass and legume selection (see map, Plate 3.32-2).

Microclimate, or localized climate conditions, can affect plant growth. A south-facing slope is drier and hotter than a north-facing slope, and may require drought-tolerant plants. Shaded areas require shade-tolerant plants; the windward side of a ridge will be drier than the leeward, etc.

LAND USE: A prime consideration in selecting which plants to establish is the intended use of the land. All of these uses - residential, industrial, commercial, recreational - can be separated into two major categories: high-maintenance and low-maintenance.

<u>High-maintenance areas</u> will be mowed frequently, limed and fertilized regularly, and will either receive intense use (e.g., athletics) or require maintaining to an aesthetic standard (home lawns). Grasses used for these situations must be fine-leaved and attractive in appearance, able to form tight sod, and be long-lived perennials. They must be well-adapted to the geographic area where they are planted, because constant mowing puts turf under great stress. Sites where high-maintenance vegetative cover is desirable include homes, industrial parks, schools, churches, athletic playing surfaces as well as some recreational areas.

Low-maintenance areas will be mowed infrequently or not at all; lime and fertilizer may not be applied on a regular basis; the areas will not be subjected to intense use, nor required to have a uniform appearance. These plants must be able to persist with little maintenance over long periods of time. Grass and legume mixtures are favored for these sites because legumes are capable of fixing nitrogen from the air for their own use, and the use of the plants around them. Such mixed stands are better able to withstand adverse conditions.

Sites that would be suitable for low-maintenance vegetation include steep slopes, stream or channel banks, some commercial properties, and "utility turf" areas such as roadbanks.

<u>Seedbed Preparation</u> - The soil on a disturbed site must be modified to provide an optimum environment for seed germination and seedling growth. The surface soil must be loose enough for water infiltration and root penetration. The pH (acidity and alkalinity) of the soil must be such that it is not toxic and nutrients are available, usually between pH 6.0-7.0. Sufficient nutrients (added as fertilizer) must be present. After seed is in place, it must be protected with a mulch to hold moisture and modify temperature extremes, and to prevent erosion while seedlings are growing.

The addition of lime is equally as important as applying fertilizer. Lime is best known as a pH, or acidity, modifier, but it also supplies calcium and magnesium which are plant nutrients. Its effect on pH makes other nutrients more available to the plant. It can also prevent aluminum toxicity by making aluminum less soluble in the soil. Many soils in Virginia are high in aluminum, which stunts the growth of plant roots.

MAINTENANCE: Even with careful, well-planned seeding operations, failures can occur. When it is clear that plants have not germinated on an area or have died, these areas must be reseeded immediately to prevent erosion damage. However, it is extremely important to determine for what reason germination did not take place and make any corrective action necessary prior to reseeding the area. <u>Healthy vegetation is the most effective erosion</u> control available.

Specifications

Selection of Plant Materials

- 1. Selection of plant materials is based on climate, topography, soils, land use, and planting season. To determine which plant materials are best adapted to a specific site, use Tables 3.32-A and 3.22-B which describe plant characteristics and list recommended varieties.
- 2. Appropriate seeding mixtures for various site conditions in Virginia are given in Tables 3.32-C, 3.32-D and 3.32-E. These mixtures are designed for general use, and are known to perform well on the sites described. Check Tables 3.32-A and 3.32-B for recommended varieties.
- 3. A more extensive description of plant materials (grasses and legumes), their usage and pictorial representation can be found in Appendix 3.32-c.
- 4. When using some varieties of turfgrasses, the Virginia Crop Improvement Association (VCIA) recommended turfgrass mixtures may also be used. Consumer protection programs have been devised to identify quality seed of the varieties recommended by the Virginia Cooperative Extension Service. These will bear a label indicating



that they are approved by the Association. Mixtures may be designed for a specific physiographic region or based on intended use. Special consideration is given to plant characteristics, performance, etc.

· · · · · · · · · · · · · · · · · · ·	suggested Varieties for Virginia	Ky 31	See current VCIA list.	See current VCIA list.	See current VCIA list.
	REMARKS	Better suited for erosion control and rough turf application.	Excellent for lawn and fine turf.	Excellent for fine turfs-takes traffic, mowing. Poor drought/heat tolerance.	May be added to mixes. * Improved varieties will perform well all year.
5E.5	MAINTENANCE REQUIREMENTS	Low when used for erosion control; high when used in lawn	Responds well to high maintenance.	Needs fertile soil, favorable moisture. Requires several years to become well established.	Will tolerate traffic.
U GKAD	Seeds Per Pound	225K	220K	2.2m	227K
BLEUEUE	Soil Drainage Tolerance	SPD	SPD	Qas	CIAS
IUNEX	Ferülity	×	×	×	H-M
OMIN	Drought Tolerance	ĨĽ.	IJ	₽-	لت
UF C	Winter Hardiness	μ.	ц	σ	Ľ4
KINICI	noitanimaGermination Temperature (°F)	60-85	60-85	60-75	60-75
ARACTE	Germination Тіте In Days	10-14	10-34	4	7-10
E	рН Капус	5.5- 6.2	5.5- 6.2	6.0- 6.5	5.8- 6.2
	логьэг	υ	U	U	U
	Life Cycle	p.	<u>ρ</u> .	<u>A</u>	<u>م</u>
	COMMON NAME (Botanical Name)	TALL FESCUE (Festuca arundinacea)	TALL FESCUES (Improved)	KENTUCKY BLUEGRASS (Poa pratense)	PERENNIAL RYEGRASS (Lolium perenne)

TABLE 3.32-A

VP = Very Poor H = High VPD = Very Poorly Drained P = Fair P = PoorPD = Poorly Drained A = Annual M = Medium

KEY

	Suggested Varieties for Virginia	Reliant, Spartan, Aurora	Flyer	Long- fellow, Victory	No named varieties
RASSES	REMARKS	Exceeds all fine fescues in most tests. Excellent for low-maintenance situations.	Poor traffic tolerance, less thatch than other fine fescues.	Spreads by rhizomes, tillers and stolons. Will not take traffic - very shade tolerant.	Conservation cover in wet areas.
	MAINTENANCE REQUIREMENTS	Grows well in sun or shade and will tolerate infertile soils; improved disease resistance.	Tolerates shade, dry infertile soils.	Low to medium fertility requirements. Requires well-drained soil.	Do not mow closely or often.
ECTED G	Seeds Per Pound	400K	400K	400K	530K
Continued) NLY SEL	Soil Drainage Toleгансе	ДММ	СММ	ФММ	QdA
3.32-A ((COMMO	Fertility	jana)	Ļ	L	H-M
BLE OF (Drought Tolerance	Ð	Ð	IJ	U
TA	Winter Hardiness	6V VG	ŊŊ	Ŋ	Ŀ
ACTERI	Optimum Germination Temperature (°F)	60- 80 -	60- 80	80 - 80 -	70- 85
HAR/	Сегтіпасіюп Тіте, Іл Days	-0 <u>-</u> 4	-01 41	- 10	21
)	рН Капес	5.0- 6.2	5.0- 6.2	5.0- 6.2	5.8- 6.2
	Season	U	U	U	υ
	Life Cycle	d	Ч	<u>а</u> .	а.
	DN NAME cal Name)	HARD FESCUE (Festuca Longifolia)	CHEWINGS FESCUE	RED FESCUE (Festuca Rubra)	ARYGRASS ndinacea)
	COMMC (Botanic		FINE		REED CAN/ (Phalaris arur

Ī.

VP = Very Poor H = High VPD = Very Poorly Drained F = Fair P = PoorPD = Poorly Drained $P = Perennial \quad C = Cool Season Plant \quad W = Warm Season Plant \quad G = Good \\ L = Low \quad SPD = Somewhat Poorly Drained \quad MPD = Moderately Poorly Drained \\ \label{eq:constraint}$ P = Perennial A = Annual M = Medium

KEY

-

	Suggested Varieties for Virginia	No named varieties.	No named varieties.	See current VCIA list.	Virginia origin or Potomac
	REMARKS	Does well in erosion control mixes - not for lawns.	Fast-growing, warm-season bunch grass. Excellent cover for erosion control.	Common varieties used for erosion control. Hybrids used for fine turf.	Good pasture selection - may be grazed.
CLIC	MAINTENANCE REQUIREMENTS	Will tolerate poor, infertile soils; deep rooted.	Low-fertility requirements; excellent drought tolerance.	High nitrogen utilization, excellent drought tolerance. Some varieties adapted to western VA.	Does best on well- drained, loamy soil.
U UKAD	Seeds Per Pound	Śт	1.5m	1.8m hulled	625K
a l'hara	Soil Drainage Tolerance	Cd	SPD	SPD	CIdS
IUNLY 3	Fertility	<u></u> ц	L-N	H-M	¥
WIND:	Drought Tolerance	щ	U	U	íц.
5	Winter Hardiness	IJ	-д-я	4	ш
KINICO	Optimum Germination Temperature (°F)	65-85	65-85	70-95	60-75
AKAUTE	Germination Time, In Days	10	14	21	18
CH	рН Капде	5.8- 6.2	4.5 6.2	6.5 6.7	5.8- 6.2
	noseo2	υ	≥	8	с
	Life Cycle	<u>م</u>	۵.	۵.	<u>م</u>
	COMMON NAME (Botanical Name)	REDTOP (Agrostis alba)	WEEPING LOVEGRASS (Evagrostis curvula)	BERMUDAGRASS (Cynodon dactylon)	ORCHARDGRASS (Dactylis glomerata)

TABLE 3.32-A (Continued) FERISTICS OF COMMONLY SELECTED GRASSES

KEY

÷21

VP = Very Poor H = High VPD = Very Poorly Drained A = Annual P = Perennial C = Cool Season Plant W = Warm Season Plant G = Good F = Fair P = Poor M = Medium L = Low SPD = Somewhat Poorly Drained MPD = Moderately Poorly Drained PD = Poorly Drained C = Poorly Drained PD = Po

III - 298

	Suggested Varieties for Virginia	No named varieties.	Abruzzi, Bałboa	Common, German
ES	REMARKS	May be added into mixes or established alone as temporary cover in spring and fall.	May be added into mixes or established alone for late fall/winter cover.	May be added to erosion-control mixes or established alone.
	MAINTENANCE REQUIREMENTS	Will grow on most Virginia Soils. Do not use in fine-turf areas.	Will establish in most all Virginia soils. Do not use in fine-turf areas.	Establishes well during summer. Very low moisture requirements.
D GRAS	Seeds Per Pound	227K	18K	220K
ued) SELECTE	Soil Drainage Tolerance	SPD	QdS	ДWМ
(Contim IONLY S	Fertility	H-M	L-M	Σ
.32-A	Drought Tolerance	Р	U	9
ABLE 3 S OF C	Winter Hardiness	U	VG	q
T/ CRISTIC	Optimum Germination Temperature (°F)	60-70	55-70	65-85
ARACTE	Germination Time In Days	٢	L	10
CH	рН Капge	5.8- 6.2	5.8- 6.2	5.8- 6.2
	Season	C	υ	3
	Life Cycle	×	¥	V
	COMMON NAME (Botanical Name)	ANNUAL RYEGRASS (Lolium multiflorum)	RYE (Secale cercale)	FOXTAIL MILLET (Setaria italica)

KEY

VP = Very Poor H = High VPD = Very Poorly Drained F = Fair P = PoorPD = Poorly Drained $P = Perennial \quad C = Cool Season Plant \quad W = Warm Season Plant \quad G = Good \\ L = Low \quad SPD = Somewhat Poorly Drained \quad MPD = Moderately Poorly Drained \\ Drained \quad MPD = Moderately Poorly Drained \\ MPD = Moderat$ A = Annual M = Medium

COMMON NAME CARACTERISTICS OF LEGUNES AFTROPRIATE FOR EROSION CONTROL COMMON NAME COMMON NAME MAINTENANCE MAINTENANCE REMARKS (Looanical Nauo) Comunal Nauo) P Comunal Nauo) Naune (Looanical Nauo) P Comunal Nauo) P Comunal Nauo) Naune (Looanical Nauo) P Comunal Nauo) P Comunal Nauo) Naune Consulta varia) P C 6.0 14-21 70 C VG M NVD 110K Docuptati Tolerance Pangifit Consontil a varia) P C VG M NVD 110K Docuptati Tolerance Pangifit Consontil a varia) P C VG M NVD 10K Docuptati Tolerance Consontil a varia) P C VG M NVD 10K Docuptati Tolerance Consontil a varia) P VG L NVD 10K Docuptati Tolerance Docupt	6		·····		1		
COMMON NAME COMMON NAME COMMON NAME MAINTENANCE READING COMMON NAME Cycle Many MAINTENANCE REQUIREMENTS COMMON NAME Cycle Many Many Mainten MAINTENANCE Consulta varia) Cycle P C Cycle REQUIREMENTS REMARKS Consulta varia) Consulta varia) Consulta varia) Consulta varia) Consulta varia) Consulta varia) Construct E E Construct E Construct E Construct E <td< td=""><td></td><td>Suggested Varieties for Virginia</td><td>Penngift Chemung Emerald</td><td>Serecia Interstate</td><td>Lathco</td><td>No named varieties.</td><td></td></td<>		Suggested Varieties for Virginia	Penngift Chemung Emerald	Serecia Interstate	Lathco	No named varieties.	
CHARACTERISTICS OF LEGUMES APPROPRIATE FOR EROSION CONTROL COMMON NAME COMMON NAME MAINTENANCE (Botanical Name) Cycle MAINTENANCE (Social Name) Cycle MAINTENANCE (Social Name) Cycle MAINTENANCE (Botanical Name) MAINTENANCE REQUIREMENTS (Coronilla vaia) Cycle MAINT Named (Laspedeza curreata) P V/G L MAINT	OR EROSION CONTROL	REMARKS	Excellent for steep, rocky slopes. Produces colorful blooms in May/June. Slow to establish. Does best when seeded in spring.	Use hulled seed in spring; unhulled in fall. Very deep-rooted legume. Excellent choice for eastern Va.	Tolerates acidic and wetter soils better than other legumes.	Grows better on poorfy drained soils than most legumes. Poor drought/ heat tolerance.	
CHARACTERISTICS OF LEGUMES APPROPRIATE Common NAME Common NAME Characteristrics of LeGUMES APPROPRIATE (Botanical Name) Life Cycle Name Season (Botanical Name) Drought Tolerance Numb Season (Botanical Name) P C 6.0 14-21 70 G VG M MWD 110K CrownVETCH P C 6.0 14-21 70 G VG M MWD 110K CrownVETCH P W 5.8 20- F VG Lespeletance Crownila varia) P K 5.8 20- F VG L MVD 335K LESPEDEZA P W 5.8 21-28 55- G 70- F VG L MVD 335K LESPEDEZA P K 5.8 70- F VG L P 9 5 10- 5 5 12- 8		MAINTENANCE REQUIREMENTS	Does best on well-drained soils. Minimum maintenance when established. May need phosphorus. Inoculation is essential.	Grows in most well-drained soils. Low fertility requirements. Inoculation is essential.	Needs lime and high phosphorus. Good shade tolerance.	tnoculation is essential. Grows in medium-fertile, slightly acid soils.	
CHARACTERISTICS OF LEGUMES APPRO COMMON NAME COMMON NAME CHARACTERISTICS OF LEGUMES APPRO (Botanical Name) (Botanical Name) (Botanical Name) (Botanical Name) Common NAME (Cormination (Botanical Name) Common NAME Name (Botanical Name) Common NAME Name (Botanical Name) Common Name Name (Botanical Name) P C 6.0 (Botanical Name) P C 6.0 (Coronilla varia) P C 6.0 (Coronilla varia) P C 6.1 (Coronilla varia) P C 6.1 N SERICEA P W 5.8 70 Fertility ILESPEDEZA P VG L P P Silvestrus) P C 5.0 14-28 65 G L	PRIATE	Seeds Per Pound	110K	335K	15K	375K	
CHARACTERISTICS OF LEGUME COMMON NAME COMMON NAME COMMON NAME COMMON NAME (Botanical Name) (Botanical Name) Title Cycle Season (Botanical Name) P C 5.50 Life Cycle (Botanical Name) P C 5.6.0 H Range (Botanical Name) P C 5.6.0 H Range (Botanical Name) P C 5.6.0 14-21 20 Creatination (Coronilla varia) P C 5.0 14-21 20 C C (Lespedeza cuncata) P K 5.1-28 70 T C C ILESPEDEZA RiRDSFOOT P C 5.0 14-28 65 G L IREFOLL (Louis P C 5.0 14-28 65 G L L IREFOLL (Louis) P C 6.0 7.0 G L L L IREFOLL (Louis) P C 5.0 14-28 65 G L L L </td <td>S APPRO</td> <td>Soil Drainage Tolerance</td> <td>dwM</td> <td>dwm</td> <td>Dd</td> <td>SPD</td> <td>KEY</td>	S APPRO	Soil Drainage Tolerance	dwM	dwm	Dd	SPD	KEY
COMMON NAME COMMON NAME COMMON NAME Botanical Name) Botanical Name) Botanical Name) Common NAME Botanical Name) Common Name Common Name Bitabilita varia) Consulta varia) SERICEA P C 6.5 14-21 70 Germination Coronilia varia) Constituation Filametication Constituation Constituation Bitabsfoort P C 6.0 7.0 7.0 7.0 7.0 7.0 7.0 7.0 7.0 7.0 7.0 7.0 7.0 <td>GUME</td> <td>Fertility</td> <td>×</td> <td>ц.</td> <td></td> <td>×</td> <td></td>	GUME	Fertility	×	ц.		×	
CHARACTERISTICS COMMON NAME COMMON NAME (Botanical Name) (Botanical Name) (Coronilla varia) (Botanical Name) (BitBDSFOOT P (BitBDSFOOT P (BitBIt Corus) P (Coronilla varia) (Botanical Name) (BitBIt Corus) P (BitBit Corus)	OF LE	Drought Tolerance	ÐV	Ŋ	U	щ	
CHARACTERIS COMMON NAME (Botanical Name) (Coronilla varia)	LICS	Winter Hardiness	Ċ	ĒĽ.	U	υ	
COMMON NAME CHARAC COMMON NAME (Botanical Name) (Botanical Name) Cycle (Coronilla varia) P CROWNVETCH P CROWNVETCH P (Coronilla varia) P (Coronilla varia) P (Coronilla varia) N (Lespedeza cuncata) N SERICEA W SERICEA W (Lespedeza cuncata) P silvestrus) P BIRDSFOOT P RIRDSFOOT P C 6.5 0 7.0 14-28 conticulatus) P C 6.5 0 7.0 14-28 0 <t< td=""><td>TERIS</td><td>Optimum Germination Temperature (°F)</td><td>70</td><td>70- 85</td><td>65- 75</td><td>65- 70</td><td></td></t<>	TERIS	Optimum Germination Temperature (°F)	70	70- 85	65- 75	65- 70	
COMMON NAME (Botanical Name) (Botanical Name) (Botanical Name) (Botanical Name) CROWNVETCH (Coronila varia) (Coronila varia) (Coronila varia) (Coronila varia) (Coronila varia) P C 6.0- 6.5 6.5 6.5 6.5 7.0 silvestrus) P C 5.0- 6.5 6.5 7.0 silvestrus) BIRDSFOOT P C 6.0- 6.5 7.0 silvestrus) BIRDSFOOT P C 6.0- 6.5 7.0	HARAC	Germination Time In Days	14-21	21-28	14-28	L	
COMMON NAME COMMON NAME (Botanical Name) (Botanical Name) (Coronilla varia) P (Lespedeza cuncata) P (Lespedeza cuncata) P Silvestrus) P BiRDSFOOT P TREFOIL (Lotus comiculatus) P	U U	эвляя На	6.0- 6.5	5.8- 6.2	5.0-7.0	6.0- 6.5	
COMMON NAME (Botanical Name) (Botanical Name) (Botanical Name) (Botanical Name) CROWNVETCH (Coronilla varia) (Coronilla varia) (Coronilla varia) (Coronilla varia) (Coronilla varia) (Coronilla varia) P Estereza (Lespedeza cuneata) (Lespedeza cuneata) FLATPEA (Lathyrus P silvestrus) BIRDSFOOT P BIRDSFOOT TREFOIL (Lotus comiculatus)		nozas	ى v	≥	U U	υ	
COMMON NAME (Botanical Name) (Botanical Name) (Coronilla varia) (Coronilla varia) (Coronilla varia) (Lespedeza cumeata) ESRICEA (Lespedeza cumeata) (Lespedeza cumeata) FLATPEA (Lathyrus silvestrus) BIRDSFOOT TREFOIL (Lotus corniculatus)		Life Cycle	۵.	۵.	۵.	<u>م</u>	
		COMMON NAME (Botanical Name)	CROWNVETCH (Coronilla varia)	SERICEA LESPEDEZA (Lespedeza cuncata)	FLATPEA (Lathyrus silvestrus)	BIRDSFOOT TREFOIL (Lotus corniculatus)	

VP = Very Poor H = High VPD = Very Poorly Drained

 $P = Perennial \quad C = Cool Season Plant \quad W = Warm Season Plant \quad G = Good \quad F = Fair \quad P = Poor \\ L = Low \quad SPD = Somewhat Poorly Drained \quad MPD = Moderately Poorly Drained \quad PD = Poorly Drained \\ \end{array}$

A = Annual 1 M = Medium

TABLE 3.32-B

Suggested Varietics for Virginia	Kobe, Korean	Kenstar, Kenland	Common, White Dutch
REMARKS	Choose Kobe for southeastern Va.; needs almost no nitrogen to survive.	Acts as a biennial. Can be added to low- maintenance mixes.	Spreads by soil surface stolons, white flowers.
MAINTENANCE REQUIREMENTS	Will grow on almost any well-drained soil.	Needs high levels of phosphorus and potassium.	Requires favorable moisture, fertile soils, high pH.
Seeds Per Pound	200K	275K	700K
Soil Drainage Tolerance	CMM	SPD	PD
Fertility	Ц	W	Ψ,
Drought Tolerance	VG	Ľ.	а.
Winter Hardiness	Įي.	U	Ċ
Optimum Germination Temperature (°F)	70- 85	70	70
Сегтіпаtіоп Тіте Іп Дауз	4	7-14	0
ogne F Hq	5.8- 6.2	6.0- 6.5	6.0- 6.5
nozesč	≥	U	U
Life Cycle	<	4	<u>A</u> ,
COMMON NAME (Botanical Name)	ANNUAL LESPEDEZAS (Lespedeza striata, L. stipulacea)	RED CLOVER (Trifolium pratense)	WHITE CLOVER (Trifolium repeas)
	Back Control Contrece Conto Control Control Control Control Control Con	COMMON NAMECOMMON NAMECOMMON NAMECOMMON NAMECOMMON NAMEBotanical NameNuLALNVCondomnationSold Drought ToleranceSold Drought Tolerance <t< td=""><td>COMMON NAME COMMON NAME COMMON NAME COMMON NAME COMMON NAME COMMON NAME Bolanical Name) MAINTENTIC Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name Bolanical Name) Bolanical Name Bolanical Name) Bolanical Name Bolanical Name) Bolanical Name Bolanical Name Bolanical Name AnNUAL A W Scie Develop H Multiprov on almost any Choose Kobe for Choose Kobe for Southesten Va.: (LisepetibeZAS P M Southesten Va.: (LisepetibeZAS P N Southesten Va.: (LisepetibeZAS P N Southesten Va.:</td></t<>	COMMON NAME COMMON NAME COMMON NAME COMMON NAME COMMON NAME COMMON NAME Bolanical Name) MAINTENTIC Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name) Bolanical Name Bolanical Name) Bolanical Name Bolanical Name) Bolanical Name Bolanical Name) Bolanical Name Bolanical Name Bolanical Name AnNUAL A W Scie Develop H Multiprov on almost any Choose Kobe for Choose Kobe for Southesten Va.: (LisepetibeZAS P M Southesten Va.: (LisepetibeZAS P N Southesten Va.: (LisepetibeZAS P N Southesten Va.:

KEY

	8.97. J.
	C + C + L + L + L
var vra i	e 20 8 12 1
	X
	Xaa
	글 옷 문제
	53
്റി	R CH
ः ्षः ।	
ંત્રમાં ન	
Section 2010	
	Q
00 2 0.	ୋ
ାର ଅଧ୍ୟ ମ	. (1)
9	1996 - C
· 94	C
1.00	58 8
_ C •	
5	
	. · · · · · · · · · · · · · · · · · · ·
	11
ःामः ।	
ं	
	9 - 2 C A D A
rese a s	
60. A 4 4 4	
:::: : :::::::::::::::::::::::::::::::	X
́х.	X 1
- -	M 1
- H	5
3 - 1 - 1	L (1971)
Sec. H - 1	
994 <u>1</u>	1.11
· PA	
923 5 8 2	
49 ((())	ହା
8 - 1 - 1	्रा
· · · · 별 · ·	page 1911 de
200 0	4. CAN
: 	18-21-6
: / a .	1
88 B A	<u> </u>
	a: / I
- 1	
99 - 99 - 19 - 19 - 19 - 19 - 19 - 19 -	and the late
44100	
<u> - 14</u>	
ः च प्र	0
Q.,	HE COLOR
∴ 	2 1
ാറ	C 1
99 T	∧ 1
ं स	
- -	.
S. PH	
. V.	:북소 요네
434 A.A.	X
12.000	
. .	
은 세 .	
	9
- 	
N N 22	G
- - E	9 1
- 	TQ 1
1	22 1 24
8	¥
Seas	ž
Seas	ž
m Seas	¥ П
rm Seas	Ŭ I
arm Seas	¥ ₽
Varm Seas	₩ ₩ Ω
Warm Seas	MPD = Mc
- Warm Seas	MPD = Mc
= Warm Seas	MPD = Mc
– Warm Seas	MPD = Mc
N = Warm Seas	ed MPD = Mc
W = Warm Seas	ned MPD = Mc
W = Warm Seas	ined MPD = Mc
W = Warm Seas	rained MPD = Mc
t W = Warm Seas	Drained MPD = Mc
at W = Warm Seas	Drained MPD = Mc
ant W = Warm Seas	y Drained MPD = Mc
'lant W = Warm Seas	iy Drained MPD = Mc
Plant W = Warm Seas	orly Drained MPD = Mc
n Plant W = Warm Seas	oorly Drained MPD = Mc
on Plant W = Warm Seas	oorly Drained MPD = Mc
son Plant W = Warm Seas	Poorly Drained MPD = Mc
ason Plant W = Warm Seas	i Poorly Drained MPD = Mc
cason Plant W = Warm Seas	lat Poorly Drained MPD = Mc
Season Plant W = Warm Seas	hat Poorly Drained MPD = Mc
d Season Plant W = Warm Seas	what Poorly Drained MPD = Mc
ol Season Plant W = Warm Seas	ewhat Poorly Drained MPD = Mc
cool Season Plant W = Warm Seas	mewhat Poorly Drained MPD = Mc
Cool Season Plant W = Warm Seas	omewhat Poorly Drained MPD = Mc
Cool Season Plant W = Warm Seas	Somewhat Poorly Drained MPD = Mc
= Cool Season Plant W = Warm Seas	Somewhat Poorly Drained MPD = Mc
= Cool Season Plant W = Warm Seas	= Somewhat Poorly Drained MPD = Mc
C = Cool Season Plant W = Warm Seas	= Somewhat Poorly Drained MPD = Mc
C = Cool Season Plant W = Warm Seas) = Somewhat Poorly Drained MPD = Mc
C = Cool Season Plant W = Warm Seas	D = Somewhat Poorly Drained MPD = Mc
C = Cool Season Plant W = Warm Seas	PD = Somewhat Poorly Drained MPD = Mc
d. C = Cool Season Plant W = Warm Seas	SPD = Somewhat Poorly Drained MPD = Mc
ial C = Cool Season Plant W = Warm Seas	SPD = Somewhat Poorly Drained MPD = Mc
nial C = Cool Season Plant W = Warm Seas	SPD = Somewhat Poorly Drained MPD = Mc
mial C = Cool Season Plant W = Warm Seas	v SPD = Somewhat Poorly Drained MPD = Mc
emial C = Cool Season Plant W = Warm Seas	<pre>w SPD = Somewhat Poorly Drained MPD = Mc</pre>
rrennial C = Cool Season Plant W = Warm Seas	.cow SPD = Somewhat Poorly Drained MPD = Mc
Perennial C = Cool Season Plant W = Warm Seas	Low SPD = Somewhat Poorly Drained MPD = Mc
Perennial C = Cool Season Plant W = Warm Seas	= Low SPD = Somewhat Poorly Drained MPD = Mc
= Peremial C = Cool Season Plant W = Warm Seas	= Low SPD = Somewhat Poorly Drained MPD = Mc
= Perennial C = Cool Season Plant W = Warm Seas	c = Low SPD = Somewhat Poorly Drained MPD = Mc
> = Peremial C = Cool Season Plant W = Warm Seas	L = Low SPD = Somewhat Poorly Drained MPD = Mc
P = Perennial C = Cool Season Plant W = Warm Seas	L = Low SPD = Somewhat Poorly Drained MPD = Mc
P = Peremial C = Cool Season Plant W = Warm Seas	L = Low SPD = Somewhat Poorly Drained MPD = Mc
P = Perennial C = Cool Season Plant W = Warm Seas	1 L = Low SPD = Somewhat Poorly Drained MPD = Mc
P = Peremial C = Cool Season Plant W = Warm Seas	m L = Low SPD = Somewhat Poorly Drained MPD = Mc
al P = Perennial C = Cool Season Plant W = Warm Seas	um L = Low SPD = Somewhat Poorly Drained MPD = Mc
ual P = Perennial C = Cool Season Plant W = Warm Seas	jium L = Low SPD = Somewhat Poorly Drained MPD = Mc
nual P = Perennial C = Cool Season Plant W = Warm Seas	edium L = Low SPD = Somewhat Poorly Drained MPD = Mc
nnual P = Perennial C = Cool Season Plant W = Warm Seas	fedium L = Low SPD = Somewhat Poorly Drained MPD = Mc
Annual P = Perennial C = Cool Season Plant W = Warm Seas	Medium L = Low SPD = Somewhat Poorly Drained MPD = Mc
Annual P = Perennial C = Cool Season Plant W = Warm Seas	: Medium L = Low SPD = Somewhat Poorly Drained MPD = Mc
= Annual P = Perennial C = Cool Season Plant W = Warm Seas	= Medium L = Low SPD = Somewhat Poorly Drained MPD = Mc
= Annual P = Peremial C = Cool Season Plant W = Warm Seas	<pre>[= Medium L = Low SPD = Somewhat Poorly Drained MPD = Mc</pre>
A = Annual P = Perennial C = Cool Season Plant W = Warm Seas	M = Medium L = Low SPD = Somewhat Poorly Drained MPD = Mc
A = Annual P = Perennial C = Cool Season Plant W = Warm Seas	M = Medium L = Low SPD = Somewhat Poorly Drained MPD = Mc
A = Annual P = Perennial C = Cool Season Plant W = Warm Seas	M = Medium L = Low SPD = Somewhat Poorly Drained MPD = Mc

III - 301[.]

TABLE 3.32-C SITE SPECIFIC SEEDING MIXTURES FOR APPALACHIAN/MOUNTAIN AREA

Minimum Care Lawn	Per Acre
- Commercial or Residential	200-250 lbs.
- Kentucky 31 or Turf-Type Tall Fescue	90-100%
 Improved Perennial Ryegrass * 	0-10%
- Kentucky Bluegrass	0-10%
High-Maintenance Lawn	
Minimum of three (3) up to five (5) varieties of bluegrass from approved list for use in Virginia.	125 lbs.
General Slope (3:1 or less)	
- Kentucky 31 Fescue	128 lbs.
- Red Top Grass	2 lbs.
- Seasonal Nurse Crop **	20.1bs.
*	150 lbs.
Low-Maintenance Slope (Steeper than 3:1)	
- Kentucky 31 Fescue	108 lbs.
- Red Top Grass	2 lbs.
- Seasonal Nurse Crop **	20 lbs.
- Crownvetch ***	<u>20 lbs.</u>
	150 lbs.

* Perennial Ryegrass will germinate faster and at lower soil temperatures than fescue, thereby providing cover and erosion resistance for seedbed.

** Use seasonal nurse crop in accordance with seeding dates as stated below: March, April through May 15th Annual Rye May 16th through August 15th Foxtail Millet August 16th through September, October Annual Rye November through February Winter Rye

*** If Flatpea is used, increase to 30 lbs./acre. All legume seed must be properly inoculated. Weeping Lovegrass may also be included in any slope or low-maintenance mixture during warmer seeding periods; add 10-20 lbs/acre in mixes.

Total I be

TABLE 3.32-D

SITE SPECIFIC SEEDING MIXTURES FOR PIEDMONT AREA		
	Total Lbs. <u>Per Acre</u>	
Minimum Care Lawn		
 Commercial or Residential Kentucky 31 or Turf-Type Tall Fescue Improved Perennial Ryegrass Kentucky Bluegrass 	175-200 lbs. 95-100% 0-5% 0-5%	
High-Maintenance Lawn	200-250 lbs.	
- Kentucky 31 or Turf-Type Tall Fescue	100%	
General Slope (3:1 or less)		
 Kentucky 31 Fescue Red Top Grass Seasonal Nurse Crop * 	128 lbs. 2 lbs. <u>20 lbs.</u> 150 lbs.	
Low-Maintenance Slope (Steeper than 3:1)		
 Kentucky 31 Fescue Red Top Grass Seasonal Nurse Crop * Crownvetch ** 	108 lbs. 2 lbs. 20 lbs. <u>20 lbs.</u> 150 lbs.	
* Use seasonal nurse crop in accordance with seeding dates as February 16th through April	stated below: Annual Rye Foxtail Millet Annual Rye Winter Rye	
** Substitute Sericea lespedeza for Crownvetch east of Farm through September use hulled Sericea, all other periods, use us If Flatpea is used in lieu of Crownvetch, increase rate to 30 lbs.// seed must be properly inoculated. Weeping Lovegrass may be ac or low-maintenance mix during warmer seeding periods; add 1 mixes.	nville, Va. (May nhulled Sericea). acre. All legume dded to any slope .0-20 lbs./acre in	

TABLE 3.32-D

SITE SPECIFIC SEEDING MIXTURES FOR COASTAL PLAIN AREA

	Total Lbs. Per Acre
Minimum Care Lawn	
- Commercial or Residential	
- Kentucky 31 or Turf-Type Tall Fescue	175-200 lbs.
or	
- Common Bermudagrass **	75 lbs.
High-Maintenance Lawn	
- Kentucky 31 or Turf-Type Tall Fescue	200-250 lbs.
- Hybrid Bermudagrass (seed) **	40 lbs. (unhulled)
or	30 lbs. (hulled)
- Hybrid Bermudagrass (by other vegetative	· · · ·
establishment method, see Std. & Spec. 3.34)	
General Slope (3:1 or less)	
- Kentucky 31 Fescue	128 lbs.
- Red Top Grass	2 lbs.
- Seasonal Nurse Crop *	<u>20 lbs.</u>
	150 lbs.
Low Maintenance Slope (Steeper than 3:1)	
- Kentucky 31 Tall Fescue	93-108 lbs.
 Common Bermudagrass ** 	0-15 lbs,
- Red Top Grass	2 lbs.
- Seasonal Nurse Crop *	20 lbs.
- Sericea Lespedeza **	<u>20 lbs.</u>
	150 lbs.
* Use seasonal nurse crop in accordance with seeding dates	as stated below:
February, March through April	Annual Rye
May 1st through August	Foxtail Millet
Santamhan Oatahan through Norrowshan 15th	A

September, October through November 15th Annual Rye November 16th through January Winter Rye

** May through October, use hulled seed. All other seeding periods, use unhulled seed. Weeping Lovegrass may be added to any slope or low-maintenance mix during warmer seeding periods; add 10-20 lbs./acre in mixes.

Seedbed Requirements

Vegetation should not be established on slopes that are unsuitable due to inappropriate soil texture, poor internal structure or internal drainage, volume of overland flow, or excessive steepness, until measures have been taken to correct these problems.

To maintain a good stand of vegetation, the soil must meet certain minimum requirements as a growth medium. The existing soil must have these characteristics:

- 1. Enough fine-grained material to maintain adequate moisture and nutrient supply.
- 2. Sufficient pore space to permit root penetration. A bulk density of 1.2 to 1.5 indicates that sufficient pore space is present. A fine granular or crumb-like structure is also favorable.
- 3. Sufficient depth of soil to provide an adequate root zone. The depth to rock or impermeable layers such as hardpans shall be 12 inches or more, except on slopes steeper than 2:1 where the addition of soil is not feasible.
- 4. A favorable pH range for plant growth. If the soil is so acidic that a pH range of 6.0-7.0 cannot be attained by addition of pH-modifying materials, then the soil is considered an unsuitable environment for plant roots and further soil modification would be required.
- 5. Freedom from toxic amounts of materials harmful to plant growth.
- 6. Freedom from excessive quantities of roots, branches, large stones, large clods of earth, or trash of any kind. Clods and stones may be left on slopes steeper than 3:1 if they do not significantly impede good seed soil contact.

If any of the above criteria cannot be met, i.e., if the existing soil is too coarse, dense, shallow, acidic, or contaminated to foster vegetation, then topsoil shall be applied in accordance with TOPSOILING, Std. & Spec. 3.30.

<u>Necessary structural erosion and sediment control practices</u> will be installed prior to seeding. Grading will be carried out according to the approved plan.

<u>Surfaces</u> will be roughened in accordance with SURFACE ROUGHENING, Std. & Spec. 3.29.

Soil Conditioners

In order to modify the texture, structure, or drainage characteristics of a soil, the following materials may be added to the soil:

- 1. <u>Peat</u> is a very costly conditioner, but works well. If added, it shall be sphagnum moss peat, hypnum moss peat, reed-sedge peat or peat humus, from fresh-water sources. Peat shall be shredded and conditioned in storage piles for at least six months after excavation.
- 2. <u>Sand</u> shall be clean and free of toxic materials. Sand modification is ineffective unless you are adding 80 to 90% sand on a volume basis. This is extremely difficult to do on-site. If this practice is considered, consult a professional authority to ensure that it is done properly.
- 3. <u>Vermiculite</u> shall be horticultural grade and free of toxic substances. It is an impractical modifier for larger acreage due to expense.
- 4. <u>Raw manure</u> is more commonly used in agricultural applications. However, when stored properly and allowed to compost, it will stabilize nitrogen and other nutrients. Manure, in its composted form, is a viable soil conditioner; however, its use should be based on site-specific recommendations offered by a professional in this field.
- 5. <u>Thoroughly rotted sawdust shall have 6 pounds of nitrogen added to each cubic yard and shall be free of stones, sticks, and toxic substances.</u>
- 6. The use of <u>treated sewage sludge</u> has benefitted from continuing advancements in its applications in the agricultural community. When composted, it offers an alternative soil amendment. Limitations include a potentially undesirable pH (because of lime added during the treatment process) and the possible presence of heavy metals. This practice should be thoroughly evaluated by a professional and be used in accordance with any local, state, and federal regulations.

Lime and Fertilizer

Lime and fertilizer needs should be determined by soil tests. Soil tests may be performed by the Cooperative Extension Service Soil Testing Laboratory at VPI&SU, or by a reputable commercial laboratory. Information concerning the State Soil Testing Laboratory is available from county extension agents. Reference Appendix 3.32-d for liming applications (in lbs.) needed to correct undesirable pH for various soil types.

Under unusual conditions where it is not possible to obtain a soil test, the following soil amendments will be applied:

Lime

Coastal Plain:	2	tons/acre	pulverized	agricultural	grade	limestone	(90
	lbs	s./1000 ft. ²).	•				

Piedmont and Appalachian Region:

2 tons/acre pulverized agricultural grade limestone (90 lbs./1000 ft. 2).

Note: An agricultural grade of limestone should always be used.

Fertilizer

Mixed grasses and le	gumes: 1000 lbs./acre 10-20-10 or equivalent nutrients $(23 \text{ lbs.}/1000 \text{ ft.}^2).$
Legume stands only:	1000 lbs./acre 5-20-10 (23 lbs./ 1000 ft. ²) is preferred; however, 1000 lbs./acre of 10-20-10 or equivalent may be used.
Grass stands only:	1000 lbs./acre 10-20-10 or equivalent nutrients, (23 lbs./1000 $ft.^2$).

Other fertilizer formulations, including slow-release sources of nitrogen (preferred from a water quality standpoint), may be used provided they can supply the same amounts and proportions of plant nutrients.

<u>Incorporation</u> - Lime and fertilizer shall be incorporated into the top 4-6 inches of the soil by discing or other means whenever possible. For erosion control, when applying lime and fertilizer with a hydroseeder, apply to a rough, loose surface.

Seeding

1. <u>Certified seed</u> will be used for all permanent seeding whenever possible. Certified seed is inspected by the Virginia Crop Improvement Association or the certifying agency in other states. The seed must meet published state standards and bear an official "Certified Seed" label (see Appendix 3.32-a).



- Legume seed should be inoculated with the inoculant appropriate to the species. Seed of the Lespedezas, the Clovers and Crownvetch should be scarified to promote uniform germination.
- 3. <u>Apply seed</u> uniformly with a broadcast seeder, drill, culti-packer seeder, or hydroseeder on a firm, friable seedbed. Seeding depth should be 1/4 to 1/2 inch.
- 4. To avoid poor germination rates as a result of seed damage during <u>hydroseeding</u>, it is recommended that if a machinery breakdown of 30 minutes to 2 hours occurs, 50% more seed be added to the tank, based on the proportion of the slurry remaining in the tank. Beyond 2 hours, a full rate of new seed may be necessary.

Often hydroseeding contractors prefer not to apply lime in their rigs as it is abrasive. In inaccessible areas, lime may have to be applied separately in pelletized or liquid form. Surface roughening is particularly important when hydroseeding, as a roughened slope will provide some natural coverage of lime, fertilizer and seed.

Legume inoculants should be applied at five times the recommended rate when inoculant is included in the hydroseeder slurry.

Mulching

All permanent seeding must be mulched immediately upon completion of seed application. Refer to MULCHING, Std. & Spec. 3.35.

Maintenance of New Seedings

In general, a stand of vegetation cannot be determined to be fully established until it has been <u>maintained for one full year after planting</u>.

<u>Irrigation</u>: New seedings should be supplied with adequate moisture. Supply water as needed, especially late in the season, in abnormally hot or dry weather, or on adverse sites. Water application rates should be controlled to prevent excessive runoff. Inadequate amounts of water may be more harmful than no water.

<u>Re-seeding</u>: Inspect seeded areas for failure and make necessary repairs and reseedings within the same season, if possible.

- a. If vegetative cover is inadequate to prevent rill erosion, over-seed and fertilize in accordance with soil test results.
- b. If a stand has less than 40% cover, re-evaluate choice of plant materials and quantities of lime and fertilizer. The soil must be tested to determine if acidity or nutrient imbalances are responsible. Re-establish the stand following seedbed preparation and seeding recommendations.

Apply maintenance levels of fertilizer as determined by soil test. In the absence of a soil test, fertilization should be as follows:

Cool Season Grasses

4 lbs. nitrogen (N)		
1 lb. phosphorus (P)	\rangle	Per 1000 ft. ² per year
2 lbs. potash (K)	,	

Seventy-five percent of the total requirements should be applied between September 1 and December 31st. The balance should be applied during the remainder of the year. More than 1 lb. of soluble nitrogen per 1000 ft.² should not be applied at any one time.

Warm Season Grasses

Apply 4-5 lbs. nitrogen (N) between May 1 and August 15th per 1000 ft.² per year.

Phosphorus (P) and Potash (K) should only be applied according to soil test.

Note: The use of slow-release fertilizer formulations for maintenance of turf is encouraged to reduce the number of applications and the impact on groundwater.

Additional Information on the Successful Establishment of Grasses and Legumes

See Appendix 3.32-b for "helpful hints" in achieving high success rates in grass or legume plantings.

APPENDIX 3.32-a

SEED QUALITY CRITERIA

Where certified seed is not available, the minimum requirements for grass and legume seed used in vegetative establishment are as follows:

- a. All tags on containers of seed shall be labeled to meet the requirements of the State Seed Law.
- b. All seed shall be subject to re-testing by a recognized seed laboratory that employs a registered seed technologist or by a state seed lab.
- c. All seed used shall have been tested within twelve (12) months.
- d. Inoculant the inoculant added to legume seed in the seed mixtures shall be a pure culture of nitrogen-fixing bacteria prepared for the species. Inoculants shall not be used later than the date indicated on the container. Twice the supplier's recommended rate of inoculant will be used on dry seedings; five times the recommended rate if hydroseeded.
- e. The quality of the seed used shall be shown on the bag tags to conform to the guidelines in Table 3.32-E.

TABLE 3.32-E

QUALITY OF SEED*

Legumes	Minimum Seed Purity (%)	Minimum <u>Germination (%)</u>
Crownvetch	98	65**
Lespedeza, Korean	97	85**
Lespedeza, Sericea	98	85**
Grasses		
Bluegrass, Kentucky	97	85
Fescue, Tall (Improved,		
Turf-Type Cultivars)	98	85
Fescue, Tall (Ky-31)	97	85
Fescue, Red	98	85
Redtop	94	80
Reed Canarygrass	98	80
Perennial Ryegrass	98	90
Weeping Lovegrass	98	87
Annuals		
Annual Ryegrass	97	90
German Millet	98	85
Oats	98	80
Cereal Rye	98	85

* Seed containing <u>prohibited or restricted noxious weeds</u> should not be accepted. Seed should not contain in excess of 0.5% weed seed. To calculate percent pure, live seed, multiply germination times purity and divide by 100.

Example: Ky-31 Tall Fescue with a germination of 85 percent and a purity of 97 percent.

 $97 \times 85 = 8245$. $8245 \div 100 = 82.45$ percent pure live seed.

** Includes "hard seed"

APPENDIX 3.32-b

KEYS TO SUCCESSFUL ESTABLISHMENT OF GRASSES AND LEGUMES

Planning

Where feasible, grading operations should be planned around optimal seeding dates for the particular region. The most effective times for establishing perennial grass in Virginia generally extend from March through May and from August through October. Outside these dates, the probability of failure is much higher. If the time of year is not suitable for seeding a permanent cover (perennial species), a temporary cover crop should be planted. Temporary seeding of annual species (small grains, ryegrasses or millets) often succeeds during periods of the year that are unsuitable for seeding permanent (perennial) species.

Variations in weather and local site conditions can modify the effects of regional climate on seeding success. For this reason, mixtures including both cool and warm season species are preferred for low-maintenance cover, particularly in the Coastal Plain. Such mixtures promote cover which can adapt to a range of conditions. Many of these mixtures are not desirable, however, for high quality lawns, where variation in texture of the turf is inappropriate. It is important to note that in Virginia the establishment of 100% warm season grasses in a high quality lawn is limited to the extreme eastern portions of the Coastal Plain.

Selection

Species selection should be considered early in the process of preparing an erosion and sediment control plan. A variety of vegetation can be established in Virginia due to the diversity in both soils and climate. However, for practical, economical stabilization and long-term protection of disturbed sites, species selection should be made judiciously.

Seasonality must be considered when selecting species. Grasses and legumes are usually classified as warm or cool season in reference to their season of growth. Cool season plants realize most of their growth during the spring and fall and are relatively inactive or dormant during the hot summer months. Therefore, fall is the most favorable time to plant them. Warm season plants "green-up" late in the spring, grow most actively during the summer, and go dormant at the time of the first frost in fall. Spring and early summer are preferred planting times for warm season plants.

Seed Mixtures

As previously noted, the establishment of high quality turf frequently involves planting one single species. However, in seedings for <u>erosion control purposes</u>, the inclusion of more than one species should always be considered. Mixtures need not be excessive in poundage or seed count. The addition of a quick-growing annual provides early protection and facilitates establishment of one or two perennials in a mix. More complex mixtures might include a quick-growing annual, one or two legumes and more than one perennial grass.

The addition of a "nurse" crop (quick-growing annuals added to permanent mixtures) is a sound practice for soil stabilization, particularly on difficult sites - those with steep slopes; poor, rocky, erosive soils; those seeded out the optimum seeding periods; or in any situation where the development of permanent cover is likely to be slow. The nurse crop germinates and grows rapidly, holding the soil until the slower-growing perennial seedlings become established.

APPENDIX 3.32-c

PLANT INFORMATION SHEETS

Contents:

Annual Grasses and Grains

Oats Rye Foxtail Millet Annual Ryegrass

Annual Legumes

Annual Lespedeza

Perennials

Tall Fescue Kentucky Bluegrass Perennial Ryegrass Fine Fescues Bermudagrass Reed Canarygrass

Miscellaneous Erosion Control Grasses

Weeping Lovegrass Redtop

Legumes

Crownvetch Flatpea Sericea Lespedeza White Clover











ANNUAL GRASSES AND GRAINS

Small grains are cool season annual grasses primarily grown for animal feed and human consumption. In Virginia, the grains used for soil stabilization are primarily Rye and Oats. Foxtail Millet, which is sometimes considered a small grain, is becoming a very popular and successful planting for soil stabilization.

- 1. <u>Oats</u> (Avenasativa): A cool season annual grass primarily grown for animal feed and human consumption, but also used for soil stabilization. Oats are seeded in early spring in the western part of the state (winter oats may be sown in the Coastal Plain). Seeding rates are 3 bushels (100 lbs.) per acre bare ground or 2-1/2 lbs. per 1000 square feet.
- 2. <u>**Rye</u>** (Secale cereale):</u> Often referred to as Winter Rye because of its winter hardiness, Rye is the most common small grain used for soil stabilization. It is also the most productive grain on dry, infertile, acid or sandy soils. It may be seeded in the fall for winter ground cover. By maturing early, it offers less competition during the late spring period, a critical time in the establishment of perennial species. Rye grain germinates quickly and is tolerant of poor soils. Including Rye grain in fall-seeded mixtures is almost always advantageous, but it is particularly helpful on difficult and erodible soils, erodible slopes or when seeding is late. Rates up to 100 lbs. for bare ground. Overly thick stands of Rye grain will suppress the growth of perennial seedlings. Approximately 50 lbs. per acre is the maximum for this purpose and, where lush growth is



expected, that rate should either be cut in half, or Rye grain should be totally eliminated from the mixture.

- 3. <u>Foxtail Millet</u> (Setaria italica): A warm season annual grass which may be used for temporary cover. German Millet (variety commonly used in Virginia) germinates quickly and goes to seed quickly. These features make it an excellent companion grass for summer seedlings. It dies at first frost. Seeding rates are up to 50 lbs. per acre for temporary cover. Use 10 to 20 lbs. per acre in mixes.
- <u>Annual Rye</u> (Lolium multiflorum): A cool season annual grass used for temporary cover or as a nurse grass to allow for germination of permanent stands. Most commonly used in mixes for erosion control. Performs well throughout the state in neutral to slightly acid soils. Rates up to 100 lbs. per acre for temporary cover. Use 10 to 20 lbs. per acre in mixes.



Foxtail Millet (Setaria italica)



Annual Rye (Lolium multiflorum)

ANNUAL LEGUMES

1. <u>Annual Lespedezas</u> (Lespedeza striata)

Uses: Pasture, hay, erosion control, soil improvement, wildlife food.

<u>Description</u>: Annual warm season legumes. Korean Lespedeza is larger and coarser than Common Lespedeza and grows to about 12 inches. Seed of Korean is shiny and black, while seed of Common is stippled. Kobe is the most desirable variety of Common Lespedeza.

Adaptation: Throughout Virginia. Optimum pH range is 6.0 to 6.5; will grow from 5.5 to 7.0. Will grow in soil textures ranging from sands to clays and through a wide range of fertility conditions.

Establishment: Seed should always May be seeded be inoculated. alone or mixed with grasses or small grains. Requires a firm seedbed; may be broadcast or drilled. Should be seeded in early spring at 25 to 40 lbs. per acre or one-half to 1 lb. per 1000 square feet, depending on use. (Use lower figure as half the seeding rate of any spring seeding with grass or grain.) Should not be mowed at less than three inches. Lespedeza will not make a large contribution in sod grasses like Bluegrass; they do best in open sod grasses like tall fescue.

<u>Sources</u>: Seed of common variety (Kobe) and Korean varieties (Climax, Harbin and Rowan) are commercially available.



Annual Lespedezas (Lespedeza striata)
PERENNIALS

1. <u>Tall Fescue</u> (Festuca arundinacea)

<u>Uses</u>: Pasture, hay, recreation areas, lawns and stabilization of waterways, banks, slopes, cuts, fills, and spoils. It is the most widely used grass at this time for stabilizing large disturbed areas.

<u>Description</u>: A robust, cool season, long-lived, deep-rooted bunchy grass which may have short rhizomes (underground stems). Kentucky 31 is the best-known variety. A number of new varieties of Tall Fescue are becoming available for lawn and other fine-turf uses, and several offer definite improvements. However, their higher cost over the old standby, KY 31, is seldom justified when used for purposes of stabilization and erosion control. Tall Fescue tolerates a wide range of seeding dates; however, with the possible exception of high mountain elevation, it is most dependable when planted in fall.

Adaptation: Adapts well to both high and low maintenance uses throughout Virginia. Adapted to a wide range of climatic conditions. Optimum pH range is 6.0 to 7.0; will

tolerate from 3.0 to 8.0. Will grow on shallow and claypan soils if they are moist. Growth is limited more by moisture than by temperature extremes, but it will tolerate drought, infertile soils and moderate shade.

Establishment: Requires a firm seedbed. Hydroseeding is successful. Seeding rates vary from 100 lbs. per acre for erosion control to 250 lbs. per acre for lawns. Plant in early spring or from the middle of August through September. Legumes may not thrive in fescue stands due to the aggressive growth habits of this Mowing is desirable on grass. critical areas at least once every two years; lack of periodic mowing will encourage clumpiness.

Sources: Readily available as seed and sod.



Tall Fescue (Festuca arundinacea)

2. Kentucky Bluegrass (Poa pratense)

<u>Uses</u>: Pasture, turf for lawns, athletic fields, golf courses, and playgrounds. Also used to stabilize waterways, slopes, cuts and fills. Choice food for grouse, turkeys, deer and rabbits.

<u>Description</u>: Long-lived, cool season perennial grass which forms a dense sod. Becomes dormant in the heat of summer since its growing season is spring and fall.

Adaptation: Best adapted to welldrained, fertile soils of limestone origin and the climate of northern and western Virginia. Optimum pH range is 6.0 to 7.0. Bluegrasses are better suited to high the maintenance situations in transition zone. Essentially dormant during dry or hot weather; however, it will normally survive severe drought.

Establishment: Requires a firm, weed-free seedbed and adequate fertilization (liberal phosphorus) and lime are important. Can be used with Tall Fescues at low rates. Minimum mowing height is 1-1/2inches. Critical erosion areas may be mowed only once per year, if This grass is usually desired. seeded with a mixture of other ог legumes; several grasses varieties of Bluegrass should be used together to ensure good stand survival. Bare ground rates are 120 lbs. per acre. Overseed 1 to 1-1/2per 1000 square feet.

Sources: Readily available as seed and sod.



Kentucky Bluegrass (Poa pratense)

3. <u>Perennial Ryegrass</u> (Lolium perrenne)

<u>Uses</u>: Erosion control, soil improvement, lawns, pasture, and hay; newer varieties are excellent for high-traffic areas.

Description: Perennial Ryegrasses are an excellent selection where rapid establishment is desired. Cool season. Ryegrasses crosspollinate freely so "Common Ryegrass" may be a mixture of annual and perennial species. Certified seed of Perennial Ryegrass varieties is produced: Blaser, Palmer, Goalie, Fiesta II, Ranger, Regal and Pennfine may be used in Virginia.

Adaptation: Throughout Virginia. Grows best on dark, rich soils in mild climates. Newer varieties have good drought tolerance but may require irrigation if under drought stress or heavy traffic. Will tolerate wet soils with good surface drainage.

Establishment: A firm, mellow surface over compact subsoils gives good results. Seed in fall or spring. Perennial Ryegrass may also be seeded in mid-August to early September. For turf, use a rate of 5 to 8 lbs. per 1000 square feet, if seeded alone; lesser amounts are suitable in mixtures, depending on characteristics the of the companion species. Generally not seeded alone except on athletic fields with intensive use. Perennial Ryegrass does best when used with bluegrass as 20 percent or less of the mixture. Ryegrasses germinate which rapidly makes them particularly suited to disturbed-area stabilization and temporary



Perennial Ryegrass (Lolium perrenne)

seeding. They will, however, tend to dominate stands in mixtures if percentage is too high.

Sources: Readily available commercially. Care should be taken to buy seed appropriate to the needs of the project.

4. Fine Fescues

- * Red Fescue
- Hard Fescue
- * Chewings Fescue

<u>Uses</u>: Excellent for shady, low maintenance areas and north-facing slopes. May be used to stabilize waterways, slopes, banks, cuts, fills, and as a cover crop in orchards.

<u>Description</u>: Red Fescue is a cool season perennial that occurs in two forms: bunchtype and creeping. Creeping Red Fescue forms a tight sod. The leaves of Red Fescue are narrow and wiry. Hard Fescues are slow-growing with excellent shade tolerance.

Adaptation: Shade tolerant and somewhat drought-resistant once established. Grows well in sandy and acidic soils. Optimum pH range is 4.5 to 6.0. Prefers welldrained soils but requires adequate moisture for establishment. In areas of high temperature and humidity (such as southeastern Virginia), some Fine Fescues may turn brown or deteriorate during the summer. Newer varieties of Hard Fescue are more drought tolerant.

Establishment: Rarely seeded in pure stands. Seedbed preparation and fertility adjustments are usually dictated by the other grasses in the mixture. Red Fescues may comprise 25 to 60% by weight of a seeding mixture. In <u>shaded</u> areas red fescue may be the key grass in the mixture. Mowing consistently below 1-1/2 is not recommended.

<u>Sources</u>: Readily available commercially. New Hard Fescues may be in short supply.



Red Fescue (Festuca rubra)

1992

5. Bermudagrass (Cynodon dactylion)

<u>Uses</u>: Soil and water conservation, pasture, hay, silage, lawns, both high maintenance and general purpose turf, and stabilization of grassed waterways.

Description: A long-lived, warm season perennial that spreads by stolons and rhizomes (runners and underground stems). Height of stems of Common Bermudagrass may be 12 inches. The stems are short-jointed and the leaves flat and spreading. Common Bermudagrass may be established vegetatively with sprigs (sections of stems) or from seeds; however, it has the potential to develop into a weed problem because it spreads vigorously. Cold-tolerant hybrids are usually specified. These are traditionally established from sprigs or sod, but seed is now available.

Adaptation: Southern Piedmont and Coastal Plain in Virginia and some southern appalachian ridges and valleys. Check Std. & Spec. 3.34 for regional adaptations of varieties. Makes its best growth when average daily temperatures are above 75 degrees. Grows on a wide range of soils from heavy clays to deep sands. Optimum pH is 6.0 to 6.5. It is drought-resistant and salt-tolerant. Tolerates floods of short duration but will not thrive on waterlogged soils; does not persist under heavy shade. For rough areas, the varieties Midland (a forage hybrid) and Coastal are recommended. For fine-turf areas. Tufcote (a fine-leaved turf hybrid), Midiron, Tifway, and Vamont are used in Virginia.



Bermudagrass (Cynodon dactylion)

Establishment: By sodding or planting sprigs. Sprigs should be planted (by hand or machine) when soil is warm in a well-prepared, moist seedbed. One end of the sprig should extend above ground, and the other should be covered by firmly packed soil.

Sources: Readily available as seed, sprigs, and sod.

6. Reed Canarygrass (Phalaris arundinacea)

Pasture, hay silage, and Uses: erosion control. An excellent grass for stabilizing waterways, healing and controlling gullies, and protecting shorelines of ponds and reservoirs from wave action. Also provides good cover for shooting preserves. Can be used in deep gullies and drainage ditches where streamflow is rapid. Vigorous growth may impede flow in small, low velocity channels.

<u>Description</u>: A long-lived, cool season, clumpy perennial with coarse rhizomes (underground stems). Grows 4 to 7 feet tall. Most widely used variety is loreed.

Adaptation: Throughout Virginia. Does best in a cool, moist climate. Makes best growth on fertile, moist, medium to fine soils; but will grow in a wide range of soil moisture conditions. Will also grow well on swampy or floodplain soils consisting of peat, muck or sand. Will withstand flooding, yet is quite drought-tolerant when mature. Optimum pH range 5.0 to 7.5.



Reed Canarygrass (Phalaris arundinacea)

Establishment: Requires a well-prepared seedbed that is firm and weed free. Seed in spring or late summer; drill seed alone or with a legume. <u>Seed must be fresh - it</u> should be labeled as having at least 70% germination tested within the last 6 months. Normally, pure stands should be established because this grass is not very compatible with other plants. Mowing should not occur more than twice a year on stabilized critical erosion areas or waterway as this will result in reduced stands.

Sources: Available commercially.

MISCELLANEOUS EROSION CONTROL GRASSES

1. <u>Weeping Lovegrass</u> (Eragrostis curvula)

<u>Uses</u>: Fast-growing cover for erosion control. In the northeast, weeping lovegrass acts as a summer annual. The normal life of 3 to 5 years may be foreshortened by low winter temperatures. May provide permanent cover on southern exposure.

<u>Description</u>: A rapid-growing, warm season bunch grass introduced from East Africa. The long, narrow leaves are numerous, very fine, and droop over to the ground, hence the name. Leaf height is rarely above 12 inches.

Adaptation: Prefers light-textured, well-drained soil; will thrive on soil of low fertility. Low winter temperatures may deplete stand.

Establishment: Easy to establish by seed; germinates rapidly and grows quickly. Lime and fertilizer needs are similar to those of Tall Fescue and Ryegrass. Requires pH of 5.5 or higher. May be planted any time after danger of frost and throughout the summer. Very fine seed, commonly added to erosion control seed mixtures. Use of hydroseeders is successful if the seeding rate is increased to compensate for the lack of a firm seedbed. Normal seeding rates are 5 to 20 lbs. per acre in mixes.

<u>Sources</u>: Readily available from large seed companies.



Weeping Lovegrass (Eragrostis curvula)

2. <u>Redtop</u> (Agrostis alba)

<u>Uses</u>: Erosion control, pasture, companion grass in turf seedings and stabilizing ditch and channel banks, grassed waterways, and other disturbed areas.

Description: A coarse, cool season perennial grass with rhizomes (underground stems). Grows to 30 to 40 inches.

Adaptation: Throughout Virginia; does better in the cool, humid areas. Will grow under a wide variety of soil and moisture conditions. Grows on very acid soils (pH 4.0 to 7.5) and poor, clay soils of low fertility. While drought-resistant, it is also a useful wetland grass.

Establishment: Has very small seed and requires a compact seedbed. May be sown in early spring or late summer. Seldom seeded alone except as temporary Adequate fertilization is turf. essential on critical areas to obtain good cover rapidly. Most commonly added to mixes, usually 2 to 3 lbs. per acre. Redtop will disappear from a stand under frequent low mowing.

Sources: Available from commercial sources.



Redtop (Agrostis alba)

LEGUMES

1. <u>Crownvetch</u> (Coronilla varia)

<u>Uses</u>: For erosion control of critical areas such as steep roadbanks, surface mine spoil and industrial waste areas. It is also useful as a residential ground cover. It provides high-quality forage for ruminant animals and serves as a wildlife food and cover plant.

<u>Description</u>: A deep-rooted, cool season, perennial, herbaceous legume with a semi-reclining growth habit. It reaches 2 to 3 feet in height, and does not climb or twine. It fixes nitrogen in the soil and makes a dense mat of vegetative cover.

Adaptation: Best adapted to the northern Piedmont and Mountain regions of Virginia. It grows best on well-drained soils with a pH range of 5.5 to 8.3. It will persist on more acid soils for a prolonged period once established. It is not adapted to soils with poor drainage. Crownvetch is winterhardy and drought-tolerant. Varieties commonly used are Chemung, Penngift and Emerald.



Establishment: Only inoculated seed should be used. Requires at least 500 lbs. per acre of 5-10-10 fertilizer (or the area should be fertilized according to soil test results). Soil acidity must be raised above a pH of 5.5. Crownvetch requires mulch and can be hydroseeded successfully. Seeding in the spring is most successful. Frost-seeding may be used on steep or stony sites (seed in late winter, and allow frost action to work the seed into soil). Crownvetch often takes 2 to 3 years to establish a dense stand. A companion grass such as Perennial Ryegrass or Redtop needs to be mixed into the initial planting, but the Crownvetch will eventually crowd out the companion plants. It will not persist under frequent mowing.

Sources: Available commercially.

2. Flatpea (Lathyrus sylvestris)

<u>Uses</u>: Flatpea is an erosion control plant that provides a thick mat of vegetative cover, fixes nitrogen in the soil, and can be maintained with a minimum of management. It is useful on roadbanks, dams, borrow area, gravel pits, surface mine spoil, and industrial waste areas. It is an ideal plant for stabilizing logging roads and utility right-of-ways since it will restrict the invasion of many woody species. It also provides good wildlife cover and food.

<u>Description</u>: A cool season perennial legume. It will climb to a height of 6 to 7 feet if support is available, but the normal height is 2 to 3 feet.

Adaptation: Flatpea is adaptable to a wide variety of soil conditions. It is drought-tolerant, cold-hardy, and does well on low-fertility sites such as sands, gravels, and soils from acid sandstones. It is not adapted to wet sites, but it will grow on somewhat poorly drained soils. It will tolerate minor shade and a minor degree of flooding. The optimum pH range is from 6.0 to 6.5. The only available variety is Lathco, developed by the USDA-Soil Conservation Service.

Establishment: Use only inoculated seed. The seedbed should be scarified, if possible. The seed is normally drilled or band seeded, but on rough sites or steep slopes, it can be broadcast and then worked into the soil by light dragging. Where possible, a light application of mulch, properly anchored, will assure a good stand. Lime is essential if the soil is below a pH of 5.0. Fertilize according to a soil test or apply 400 lbs, per acre of 10-20-10. Work lime and fertilizer into soil when preparing



Flatpea (Lathyrus sylvestris)

the seedbed. For a primary stand, use a seeding rate of 30 to 40 lbs. in a mixture with 8 to 10 lbs. of Perennial Ryegrass or 10 to 15 lbs. of Tall Fescue. Flatpea is slow to germinate, so grasses are needed to provide quick cover. Early spring seedings in April or May are best; June seedings are less desirable. Grass seedings may be overseeded with Flatpea from November through March. Flatpea is usually not winter-hardy if seeded in mid or late summer; therefore, dormant seedings are recommended. Mulch with straw at a minimum rate of 1-1/2 tons per acre on all critical and anchor. sites, Little management is required. Remove woody vegetation if the site is invaded. Mowing is acceptable once the stand is established. Mow after full bloom at a 6-inch minimum height.

Sources: Lathco is commercially available.

3. <u>Sericea Lespedeza</u> (Lespedeza cuneata)

Uses: Hay, pasture, erosion control, cover crop, wildlife food.

<u>Description</u>: Warm season perennial legume with upright woody stems 12 to 18 inches tall. Roots widely branched penetrating soil 3 feet or more.

Adaptation: Well adapted to all parts of Virginia. Best on welldrained, deep soils of medium texture. Will also grow on sandy, rather acidic, infertile soils. Most often the legume of choice for eastern Virginia. Optimum pH range is 6.0 to 6.5, but will tolerate a range of 5.0 to 7.0. It is droughttolerant. Common varieties in Virginia are Serala and Interstate.

Establishment: Seed from April to June. Requires a firm seedbed. Use only inoculated seed. Rates vary from 20 to 30 lbs. of unhulled seed per acre. Requires phosphate and potash. Will not persist under frequent mowing (once a year recommended).

<u>Sources</u>: Seed of common varieties is commercially available.



Sericea Lespedeza (Lespedeza cuneata)

1992

4. <u>White Clover</u> (Trifolium repens)

<u>Uses</u>: Common White Clover is used mostly for pastures. Ladino clover, a giant white clover, is also used for hay and silage in mixtures with a grass. The thick-growing, spreading characteristics of the common type make it ideal for erosion control.

Description: cool Α season perennial legume. The common type has a prostrate type of growth, while the Ladino is more upright. Both spread by stolons (horizontal branches along ground) and by roots at the nodes. Representative common varieties used in Virginia are Tillman, Common and White Dutch. Ladino is the only cultivar for the large type.

Adaptation: Thrives in cool climates and on moist, rich soils with full sun. Will not tolerate extremes of cold or drought. Where soil moisture is not adequate, Ladino is short-lived. Optimum soil pH is 6.5, but it will grow in a range of 5.0 to 7.5. Common White Clover volunteers readily in Bluegrass mixtures where moderate to high fertility is maintained. Stands are persistent.

Establishment: Ladino Clover requires inoculation, fertilizing, and liming for successful growth. Phosphorus and potash are the key fertilizer elements required. Ladino makes a good companion crop with grasses such Orchardgrass, as Bromegrass, Tall Fescue and Timothy. These grasses will normally crowd out the Ladino after 2 to 3 years. Seed should be planted (drilled or broadcast) at shallow depths, and a firm seedbed is desirable.

Sources: Available commercially.



White Clover (Trifolium repens)

APPENDIX 3.32-d

TABLE 3.32-F

LBS. OF GROUND AGRICULTURAL LIMESTONE* PER THOUSAND SQUARE FEET NEEDED TO CORRECT pH LEVEL OF ACID SOILS TO 6.5

		Soil Texture		
Existing pH	Sandy Loam	Loam	Clay Loam	
6.2	20	35	40	
6.0	40	55	70	
5.8	55	65	85	
5.6	70	80	105	
5.4	90	100	125	
5.2	105	120	140	
5.0	120	140	160	
4.8	125	180	205	
4.6	155	210	230	
4.0	200	250	300	

* Lime should always be applied in accordance with the results of a soil test, such as may be obtained through the soil testing laboratory at VPI&SU or through a reputable commercial laboratory.

Source: DSWC's Basic Urban E&S in Virginia



Appendix J ESC & SWM Approval Letters



13880 Dulles Corner Lane, Suite 100 Herndon, VA 20171 T: 703-449-6700 F: 703-449-6713

www.pennoni.com

June 4, 2018

Ms. Myrina Gaglione, PE Associate/Project Manager Two Columbus Center 4500 Main Street Virginia Beach, VA 23462

RE: E&S and SWM Plan Approval New Residential Facility Norfolk State University Project Code: #213-171818-000 VHB Project #32771.42

Dear Ms. Myrina Gaglione,

Based upon my review of the 4th submission of the site plans and stormwater, drainage and erosion control report dated June 1, 2018. I have found the plans to be consistent with the Virginia State requirements as set forth in 9VAC25-870 and I am recommending for approval of the stormwater and erosion control plans titled "New Residential Facility Norfolk State University" dated June 1, 2018.

If you have any questions or concerns, please contact Marco Restivo at 703-840-4843 or at mrestivo@pennoni.com.

Sincerely, PENNONI ASSOCIATES INC.

Marco B. Restivo, PE DEQ Certification No. SWCA0400

https://pennoni1-my.sharepoint.com/personal/mrestivo_pennoni_com/Documents/Documents/DEQ Review/2018-06-04 NSUVA18006 Res Dacility SWM Erosion 4th Sub/Sent/L-Comment-Letter-2018-06-04.docx

Enclosures / Attachments:

1 – E&S Checklist 2 – SWM Checklist timely manner if the RLD changes during the course of the project.

N/A

Local Consideration – Plans have been provided to the applicable jurisdictions.
Dulles Airport (MWAA)
Fairfax County
Loudoun County
Town of Herndon
Dulles Greenway (Trip II)
VDOT

CHECKLIST PREPARER

I certify that I am a professional in adherence to all minimum standards and requirements pertaining to the practice of that profession in accordance with Chapter 4 (§ 54.1-400 et seq.) of Title 54.1 of the Code of Virginia and attendant regulations. By signing this checklist I am certifying that this document and all attachments are, to the best of my knowledge and belief, true, accurate, and complete.

SIGNATURE	Mus lite
PRINTED NAME	MARCO B. RESTIVO, PE
QUALIFICATIONS	DEQ COMBINED ADMINISTRATOR SWCA0400
DATE	JUNE 4, 2018

NARRATIVE

Please reference plan sheet numbers where the information may be found.

<u>C1.02</u> <u>Project description</u> - Briefly describe the nature and purpose of the land-disturbing activity. CALC BOOKProvide the area (acres) to be disturbed.

- <u>C1.02</u> <u>Existing site conditions</u> A description of the existing topography (% slopes), ground cover, and drainage (on-site and receiving channels).
- <u>C1.02</u> <u>Adjacent areas</u> A description of all neighboring areas such as residential developments, agricultural areas, streams, lakes, roads, etc., that might be affected by the land disturbance.
- N/A <u>Off-site areas</u> Describe any off-site land-disturbing activities that may occur (borrow sites, disposal areas, easements, etc.). Identify the Owner of the off-site area and the entity responsible for plan review. Include a statement that any off-site land-disturbing activity associated with the project must have an approved ESC Plan. Submit documentation of the approved ESC Plan for each of these sites.
- <u>C1.02</u> <u>Soils</u> Provide a description of the soils on the site, giving such information as soil name, mapping unit, erodibility, permeability, surface runoff, and a *brief* description of depth, texture and soil structure. Show the site location on the Soil Survey, if it is available. Include a plan showing the boundaries of each soil type on the development site.
- C1.02 C7.00
 Critical areas - A description of areas on the site that have potentially serious erosion problems or that are sensitive to sediment impacts (e.g., steep slopes, watercourses, wet weather / underground springs, etc.).
- C1.02 Erosion and sediment control measures A description of the structural and vegetative methods that will be used to control erosion and sedimentation on the site. Controls should satisfy applicable minimum standards and specifications in Chapter 3 of the 1992 *Virginia Erosion and Sediment Control Handbook* (VESCH) or more stringent local requirements.
- C3.00Management strategies / Sequence of construction- Address management strategies, the sequenceC3.01of construction, and any phasing of installation of ESC measures.
- <u>C1.02</u> <u>Permanent stabilization</u> A brief description, including specifications, of how the site will be stabilized after construction is completed.
- C1.02 <u>Maintenance of ESC measures</u> A schedule of regular inspections, maintenance, and repair of erosion and sediment control structures should be set forth.
- <u>N/A</u> <u>Calculations for temporary erosion and sediment control measures</u> For each temporary ESC measure, provide the calculations required by the standards and specifications.

C1.02 Stormwater management considerations - Will the development of the site cause an increase in CALC BOOK peak runoff rates? Will the increase in runoff cause flooding or channel degradation downstream? Describe the strategy to control stormwater runoff, including during construction.

NEW RESIDENCE FACILITY, NORFOLK STATE PROJECT NAME: UNIVERSITY

__ SUBMITTAL#: ____4____

- <u>C7.00</u> <u>Specifications / Detail Drawings for erosion and sediment control measures</u> For each erosion and sediment control measure employed in the plan, include, at a minimum, the detail from the standard and specification in the VESCH or more stringent local requirements. Include any approved variances or revisions to the standards and specifications.
- SPECS Specifications for stormwater and stormwater management structures Provide specifications for stormwater and stormwater management structures, i.e., pipe materials, pipe bedding, stormwater structures.

PLANS DATED: 2018-06-01

SITE PLAN

Please reference plan sheet numbers where the information may be found.

<u>C0.00</u> <u>Vicinity map</u> - A small map locating the site in relation to the surrounding area. Include any landmarks that might assist in locating the site.

RELEVANT SHTS Indicate north - The direction of north in relation to the site.

- N/A <u>Off-site areas</u> Include any off-site land-disturbing activities (e.g., borrow sites, disposal areas, etc.) not covered by a separate approved ESC Plan.
- <u>C3.00</u> <u>Legend</u> Provide a complete listing of all ESC measures used, including the VESCH uniform code symbol and the standard and specification number. Include any other items necessary to identify pertinent features in the plan.
- SV-1 <u>Property lines and easements</u> Show all property and easement lines. For each adjacent property, list the deed book and page number and the property owner's name and address.
- SV-1 <u>Existing vegetation</u> Show the existing tree lines, grassed areas, or unique vegetation.
- <u>C5.00</u> <u>Limits of clearing and grading</u> Delineate all areas that are to be cleared and graded.
- C3.00 Protection of areas not being cleared Fencing or other measures to protect areas that are not to be disturbed on the site.
- N/A <u>Critical areas</u> Note all critical areas on the plan.
- C5.00 <u>Existing contours</u> Show the existing contours of the site.
- <u>C5.00</u> <u>Final contours and elevations</u> Show changes to the existing contours, including final drainage patterns.
- C5.00 Site development Show all improvements such as buildings, parking lots, access roads, utility construction, etc. Show all physical items that could affect or be affected by erosion, sediment, and drainage.
- C3.00Location of practices The locations of erosion and sediment control and stormwater managementC3.01practices used on the site. Use the standard symbols and abbreviations in Chapter 3 of the
VESCH.
- C5.00 <u>Adequate Conveyances</u> Ensure that stormwater conveyances with adequate capacity and adequate erosion resistance have been for provided all on-site concentrated stormwater runoff. Off-site channels that receive runoff from the site, including those receiving runoff from stormwater management facilities, must be adequate. Increased volumes of sheet flows must be diverted to a stable outlet, adequate channel, pipe or pipe system, or a stormwater management facility.

NEW RESIDENCE FACILITY, NORFOLK STATE

PROJECT NAME: UNIVERSITY

SUBMITTAL#: ____4

- Provide exhibits showing the drainage divides, the direction of flow, and the size (acreage) of each of the site drainage areas that discharge runoff off-site, both existing and proposed.
- X Provide calculations for pre- and post-development runoff from these drainage areas.
- Ensure that Minimum Standard 19 is satisfied for each off-site receiving channel, including those that receive runoff from stormwater management facilities.
- Provide calculations for the design of each permanent stormwater management facility.
- Ensure that increased volumes of sheet flows are diverted to a stable outlet, to an adequate channel, pipe or pipe system, or to a stormwater management facility.
- X Provide adequacy calculations for all on-site stormwater conveyances.
- CALC BOOK Calculations for permanent stormwater conveyances For each permanent stormwater conveyance or structure, provide the following design calculations, as applicable:
 - \boxtimes Drainage area map with time of concentration (T_C) path shown
 - \mathbf{X} T_C calculation/nomograph
 - N/A Locality IDF curve
 - Composite runoff coefficient or RCN calculation
 - Peak runoff calculations USED RATIONAL METHOD

NTA Stormwater conveyance channel design calculations

- X Storm drain and storm sewer system design calculations
- X Hydraulic Grade Line if any pipe in the system is more than 90% full for a 10-year storm
- MACulvert design calculations
- MADrop inlet backwater calculations
- N/A Curb inlet length calculations
- <u>C5.00</u> <u>Direction of Flow for Conveyances</u> Indicate the direction of flow for all stormwater conveyances (storm drains, stormwater conveyance channels).
- CALC BOOK Storm Drain Profiles Provide profiles of all storm drains except roof drains. If the type of pipe (RCP, CMP, HDPE, etc.) is not called out on the profiles, then the most conservative pipe material that may be specified for the project must be used in the adequacy calculations. PROFILES PROVIDED IN CALC BOOK FOR HGL ILLUSTRATION

NEW RESIDENCE FACILITY, NORFOLK STATE PROJECT NAME: UNIVERSITY

SUBMITTAL#: ____4

MINIMUM STANDARDS

Plan Sheet #

Minimum Standards - All Minimum Standards must be addressed. C1.02

Yes No NA

		[] MS-1 [] [] [] [] [] [] []	Have temporary and permanent stabilization been addressed in the narrative? Are practices shown on the plan? Temporary and permanent seed specifications? Lime and fertilizer? Mulching? Blankets/Matting? Pavement/Construction Road Stabilization?
×	[]	[] MS-2	Has stabilization of soil stockpiles, borrow areas, and disposal areas been addressed in the narrative and on the plan?
M	[]	[]	Have sediment trapping measures been provided?
X	[]	[] MS-3	Has the establishment and maintenance of permanent vegetative stabilization been addressed?
X	[]	[] MS-4	Does the plan specifically state that sediment-trapping facilities shall be constructed as a first step in land-disturbing activities?
[]	[]	MS-5	Does the plan specifically state that stabilization of earthen structures is required immediately after installation? Is this noted for each measure on the plan?
[]	[]	MS-6	Are sediment traps and sediment basins specified where needed and designed to the standard and specification?
×	[]	[] MS-7	Have the design and temporary/permanent stabilization of cut and fill slopes been adequately addressed? Is Surface Roughening provided for slopes steeper than 3:1?
[]	[]	MS-8	Have adequate temporary or permanent conveyances (paved flumes, channels, slope drains) been provided for concentrated stormwater runoff on cut and fill slopes?
[]	[]	🕅 MS-9	Has water seeping from a slope face been addressed (e.g., subsurface drains)?
X	[]	[] MS-1) Is adequate inlet protection provided for all operational storm drain and culvert inlets?

NEW RESIDENCE FACILITY, NORFOLK STATE

PROJECT NAME: UNIVERSITY

_____ SUBMITTAL#: ____4

Yes No NA

[] MS-11 Are adequate outlet protection and/or channel linings provided for all stormwater X [] conveyance channels and receiving channels? Is there a schedule indicating: Dimensions of the outlet protection? Lining? Size of riprap? [] [] X Cross section and slope of the channels? Type of lining? Size of riprap, if used? [] X [] MS-12 Are in-stream protection measures required so that channel impacts are minimized? [] [] [] [] MS-13 Are temporary stream crossings of non-erodible material required where applicable? MS-14 Are all applicable federal, state and local regulations pertaining to working in or crossing [] [] live watercourses being followed? [] MS-15 Has immediate restabilization of areas subject to in-stream construction (bed and banks) [] been adequately addressed? [] MS-16 Have disturbances from underground utility line installations been addressed? Χ [] No more than 500 linear feet of trench open at one time? X [] [] Effluent from dewatering filtered or passed through a sediment-trapping device? X [] [] Proper backfill, compaction, and restabilization? X [] [] [] MS-17 Is the transport of soil and mud onto public roadways properly controlled? (i.e., X [] Construction Entrances, wash racks, transport of sediment to a trapping facility, cleaning of roadways at the end of each day, no washing before sweeping and shoveling) [] MS-18 Has the removal of temporary practices been addressed? [] X Have the removal of accumulated sediment and the final stabilization of the resulting Χ [] [] disturbed areas been addressed? [] MS-19 Are properties and waterways downstream from development adequately protected from X [] sediment deposition, erosion, and damage due to increases in volume, velocity and peak

flow rate of stormwater runoff? Have adequate channels been provided on-site?

SUBMITTAL#: 4

PLANS DATED: 2018-06-01

PLAN SUBMITTER'S CHECKLIST

FOR STORMWATER MANAGEMENT PLANS

Please fill in all blanks and **please reference the plan sheets/pages where the information may be found**, where appropriate, or write N/A by items that are not applicable.

GENERAL

Plan Submission Date	
roject Name NEW RESIDENCE FACILITY, NORFOLK STATE UNIVERSITY	
VSMP Permit Number TBD	
Site Plan Number PROJECT CODE #213-171818-000 (VHB PR	OJECT #32771.42)
Site Address 2401 COPREW AVE, NORFOLK, VA 23504	
Applicant VHB	Phone Number 757-490-0132
Applicant Legal Address 4500 MAIN ST, SUITE 400, VIRGINIG	A BEACH, VA 23462
Owner NORFOLK STATE UNIVERSITY	Phone Number 757-536-1159
Owner E-mail Address RICHARD LAW, AIA - RALAW@NSU.ED	U
Principal Designer VHB, MYRINA GAGLIONE	Phone Number 757-490-0132
Principal Designer E-mail Address MGAGLIONE@VHB.COM	
Total Disturbed Area Figure 5.63AC	

X <u>Professional's seal</u> - The designer's original seal, signature, and date are required on the *cover* sheet of each Narrative and each set of Plan Sheets. A facsimile is acceptable for subsequent Plan Sheets. ALL SHEETS

SUBMITTED

ELECTORNICALLY <u>Number of plan sets</u> – Attach two sets of SWM Plans.

- N/A <u>Exceptions</u> Exceptions requested are governed by Section 9VAC25-870-57 of the *Virginia Stormwater Management Regulations*.
- N/A <u>Local Consideration</u> Provide contact information for the <u>locality's</u> plan review coordinator.

Name	Phone Number
Address	

N/A <u>Grandfathering</u> - Attach supporting documentation consistent with the requirements of Section 9VAC25-870-48 of the *Virginia Stormwater Management Regulations*.

N/A <u>Offsite Compliance</u> – Attach letter of availability from the off-site provider as governed by Section 9VAC25-870-55 of the *Virginia Stormwater Management Regulations*.

NEW RESIDENCE FACILITY, NORFOLK STATE

PROJECT NAME: UNIVERSITY

SUBMITTAL#: <u>4</u>

PLANS DATED: 2018-06-01

CHECKLIST PREPARER

I certify that I am a professional in adherence to all minimum standards and requirements pertaining to the practice of that profession in accordance with Chapter 4 (§ 54.1-400 et seq.) of Title 54.1 of the Code of Virginia and attendant regulations. By signing this checklist I am certifying that this document and all attachments are, to the best of my knowledge and belief, true, accurate, and complete.

SIGNATURE	Must lette
PRINTED NAME	MARCO B. RESTIVO, PE
QUALIFICATIONS	DEQ COMBINED ADMINISTRATOR SWCA0400
DATE	JUNE 1, 2018

NEW RESIDENCE FACILITY, NORFOLK STATE PROJECT NAME: UNIVERSITY

_SUBMITTAL#: ____4

PLANS DATED: _________

Please reference the plan sheet numbers where specific information may be found in the blanks below.

- Common address and legal description of the site, including the tax reference number(s) and C0.00 parcel number(s) of the property or properties affected.
- A narrative that includes a description of current site conditions and proposed development and C1.02 final site conditions, including proposed use of environmental site design techniques and practices, stormwater control measures, relevant information pertaining to long-term maintenance of these measures, and a construction schedule.
- C0.00 Existing and proposed mapping and plans (recommended scale of $1^{"} = 50^{"}$, or greater detail), C2.00 which illustrates the following at a minimum:
- C3.00 X North arrow
- C3.01 X Legend
- C4.00 X Vicinity map C5.00
- X Existing and proposed topography (minimum of 2-foot contours recommended) C6.00
- **X** Property lines SV-1

N/A Perennial and intermittent streams

X Mapping of predominant soils from USDA soils surveys as well as the location of any sitespecific test bore hole investigations that may have been conducted and information identifying the hydrologic characteristics and structural properties of soils used in the installation of stormwater management facilities **PROVIDED IN CALC BOOK**

X Boundaries of existing predominant vegetation and proposed limits of clearing and grading

Location and boundaries of natural feature protection and conservation areas (e.g., wetlands, lakes, ponds, aquifers, public drinking water supplies, etc.) and applicable setbacks (e.g., stream buffers, drinking water well setbacks, septic drainfield setbacks, building setbacks, etc.)

MAIdentification of any on-site or adjacent water bodies included on the Virginia 303(d) list of impaired waters

X Current land use and location of existing and proposed roads, buildings, parking lots and other impervious areas

X Location and description of any planned demolition of existing structures, roads, etc.

X Proposed land use(s) with a tabulation of the percentage of surface area to be adapted to various uses, including but not limited to planned locations of utilities, roads, parking lots, stormwater management facilities, and easements

X Location of existing and proposed utilities [e.g., water (including wells), sewer (including septic systems), gas, electric, telecommunications, cable TV, etc.] and easements

X Earthwork specifications

WA Show the BMP name, geographic coordinates and design of both structural and nonstructural stormwater control measures, including maintenance access and limits of disturbance X Storm drainage plans for site areas not draining to any BMP(s)

X Location of existing and proposed conveyance systems, such as storm drains, inlets, catch basins, channels, lateral groundwater movement interceptors (French drains, agric. tile drains, etc.), swales, and areas of overland flow, including grades, dimensions, and direction of flow **X** Final drainage patterns and flow paths

NA Location of floodplain/floodway limits and relationship of site to upstream and downstream properties and drainage systems

NEW RESIDENCE FACILITY, NORFOLK STATE

PROJECT NAME: UNIVERSITY

SUBMITTAL#: ____4

 \boxtimes Location of all contributing drainage areas and points of stormwater discharge, receiving surface waters or karst features into which stormwater discharges, the pre-development and post-development conditions for drainage areas, and the potential impacts of site stormwater on adjoining parcels

NTA Location and dimensions of proposed channel modifications, such as bridge or culvert crossings

X Final stabilization and landscaping plans LANDSCAPING N/A

Hydrologic and hydraulic analysis, including the following:

C0.00 C1.02

C4.00 Site map with locations of design points and drainage areas (size in acres) for runoff calculations

Ma Identification and calculation of stormwater site design credits, if any apply

Summary description of the water quantity and water quality compliance strategy.

X Time of concentration (and associated flow paths)

Imperviousness of the entire site and each drainage area SHOWN ON COVER AS # AND IN CALC BOOK

X NRCS runoff curve numbers or volumetric runoff coefficients RATIONAL C-FACTOR USED

 \mathbf{X} A hydrologic analysis for the existing (pre-development) conditions, including runoff rates, volumes, and velocities, showing the methodologies used and supporting calculations

A hydrologic analysis for the proposed (post-development) conditions, including runoff rates, volumes, and velocities, showing the methodologies used and supporting calculations

 \mathbf{X} Hydrologic and hydraulic analysis of the stormwater management system for all applicable design storms

Pollution load and load reduction requirements and calculations

 \overleftarrow{X} Final good engineering and sizing calculations for stormwater control measures, including contributing drainage areas, storage, and outlet configurations, verifying compliance with the water quality and water quantity requirements of the regulations

N/A Stage-discharge or outlet rating curves and inflow and outflow hydrographs for storage facilities

X Final analysis of the potential downstream impacts/effects of the project, where necessary

N/A Downstream analysis, where detention is proposed

MADam safety and breach analysis, where necessary

<u>C5.00</u> Representative cross-section and profile drawings and details of stormwater control measures and conveyances which include the following: NOT PROVIDED IN PLANS BUT SHOWN IN CALC BOOK

Existing and proposed structural elevations (e.g., inverts of pipes, manholes, etc.)

X Design water surface elevations

Structural details of BMP designs, outlet structures, embankments, spillways, grade control structures, conveyance channels, etc.

C0.00 C1.01 C1.02 Applicable construction and material specifications, including references to applicable material and construction standards (ASTM, etc.)

Landscaping plans for stormwater control measures and any site reforestation or revegetation

NEW RESIDENCE FACILITY, NORFOLK STATE

SUBMITTAL#: 4

NEW RESIDE PROJECT NAME: UNIVERSITY

C7.00

N/A

PLANS DATED: 2018-06-01

- N/A Long term operations and maintenance plan/agreement as governed by 9VAC25-870-112 of the Virginia Stormwater Management Program Regulations.
- N/A Evidence of acquisition of all applicable local and non-local permits
- N/A Waiver/exception requests
- N/A Evidence of acquisition of all necessary legal agreements (e.g., easements, covenants, land trusts, etc.)
- X Applicable supporting documents and studies (e.g., infiltration tests, geotechnical investigations, TMDLs, flood studies, etc.)
- N/A Other required permits:



Appendix K Site Plans (11" x 17" reductions)

Erosion & Sediment Control and Stormwater Plan

Issued for	Early E&S and Stormwater Approval
Date Issued	March 30, 2018
Latest Issue	June 1, 2018

Norfolk State University New Residential Facility ^{Corprew Avenue}

Norfolk, Virginia





> NEES BOITON ASSOCIATES Adomento de Boiton VIB Cinte doration SPECIFICA MARSHALL FRANCIS menormal doration THOMPSON CONSULTING ENGINEERS MORECISATE UNIVERSITY ONNE

S.B. BALLARD

2828 SHIPPS CORNER ROAD VIRGINIA BEACH, VIRGINIA 23453 TELEPHONE: 757.440.5555 FACSIMILE: 757.451.2873

ION WITH :

Owner:

Norfolk State University 700 Park Avenue Norfolk, Virginia 23504 Telephone: 757.823.8440

University Architect: Richard A. Law, AIA Email: ralaw@nsu.edu Telephone: 757.536.1159

Director, Capital Planning and Improvements: Terry G. Woodhouse Email: twoodhouse@nsu.edu Telephone: 757.823.8440

Development Summary

Site Address: GPIN Number: Instrument Number: Zoning: Overlay District: Character District: Existing Use: Proposed Use: Site Area:	2539 Corprew Ave Norfolk, VA 23504 1437863517 040033257 IN-C N/A Traditional Parking Lot Residence Hall 6.55 AC
Disturbed Area:	245,243 SF (5.63 AC)
Existing Impervious Area: Existing Pervious Area: Existing Open Space: Proposed Impervious Area: Proposed Pervious Area: Proposed Open Space: Watershed: Soil Type: Hydrologic Unit Code	217.800 SF (5.00 AC) 27,443 SF (0.63 AC) 0 SF (0 AC) 140,566 SF (3.23 AC) 104,677 SF (2.40 AC) 0 SF (0.00 AC) Elizabeth River Urban Land HUC 020802080204 JL54 Eastern Branch Elizabeth River

Sheet	Index	
No.	Drawing Title	Latest Issue
C1.00	Legend, Abbreviations, and General Notes	June 1, 2018
C1.01	City of Norfolk General Notes	June 1, 2018
C1.02	Erosion & Sediment Control Notes and Narrative	June 1, 2018
C2.00	Demolition Plan	June 1, 2018
C3.00	Erosion and Sediment Control Plan - Phase 1	June 1, 2018
C3.01	Erosion and Sediment Control Plan - Phase 2	June 1, 2018
C4.00	Layout and Materials Plan	June 1, 2018
C5.00	Grading and Drainage Plan	June 1, 2018
C6.00	Utility Plan	June 1, 2018
C6.01	Utility Plan	June 1, 2018
C7.00	Details	June 1, 2018
B1.00	Boring Location Plan	June 1, 2018
B1.01	Boring Logs	June 1, 2018
B1.02	Boring Logs	June 1, 2018

The following person MYRINA L. GAGLIONE, PE (p	rin
(sign), is identified as the	
Responsible Land Disturber who will be in charge of and responsit	ble
for carrying out the land disturbing activity. This person meets	th€
applicable requirements of Virginia Code Section 10.1-563 and	

10.1-566 by virtue of the following (check the category that ______ Responsible Land Disturber Certificate

> __ DCR Certification for Combined Administrator, Administrator, Plan Reviewer, Inspector, or Contractor

_____ VA Professional Engineer, Land Surveyor, Landscape Architect, or Architect

Upon Award of the contract and before any land disturbing activity con begin, the Contractor shall execute and submit a Responsible Land Disturber Notification form to the Department of Planning, Environmental Services, Rm. 508, City Hall Building, 810 Union Street, Noridu VA 23510 Tel: (757) 664-4368. Award of the contract will relieve the above signer of all responsibility.

THE RESPONSIBLE LAND DISTURGEN'S SCHATURE THAT APPEARS ABOVE HAS ONLY BEEN FROWIDED AS A CONDITION OF FLAN APPROVAL THIS INDIVIDUAL TAKES NO RESPONSIBILITY FOR ANY LAND DISTURBING ACTIVITIES RELATED TO THIS PROJECT. THE STEWORK CONTRACTOR SHALL PROVIDE TO VIRGINIA DEPARTMENT OF CONSERVATION AND RECREATION THE NAME OF A RESPONSIBLE LAND DISTURBER WHO SHALL BE RESPONSIBLE FOR LAND DISTURBING ACTIVITIES PRIOR TO APPLYING FOR A LAND DISTURBING PERMIT.

	NFW RFSIDENTIAL FACILITY	NORFOLK STATE UNIVERSITY	PROJECT CODE: #213-17818-000	
IRO	/ SEAL	NINA L.GAU INA L.GAU ic. No. 041- 04/0/2010 SONAL S		
NO.	DATE	RE	VISION	

XXX-XXXXX-XX EARLY E&S AND STORMWATER PLAN 3/30/18 COVER

C0.00

wight **O** 2018

TRUE PROJECT

Reference Drawings		
No.	Drawing Title	Latest Issue
Sv-1	Existing Conditions Topographic Survey	April 6, 2017



ROJECT TEAM S. B. BALLARD CONSTRUCTION COMPANY

COMMONWEALTH ARCHITECTS ARCHITECT OF RECORD

NILES BOLTON ASSOCIATES ARCHIECT OF DESIGN VHB CIVE ENGINEER

SPEIGHT.MARSHALL.FRANCIS THOMPSON CONSULTING ENGINEERS

NOROLK STATE UNIVERSITY





3/30/18 LEGEND, ABBREVIATIONS, AND GENERAL

NOTES

Copyright 🔘 2018 COMMONWEALTH ARCHITECTS

TRUE PROJECT

C1.00

JDF JAN

		Lege	nd				Abbreviations
Exist.	Prop.		Exist.	Prop.		General	
L=43.84'						ABAN	ABANDON
222		PROPERTY LINE			CONCRETE	ACR	ACCESSIBLE CURB RAMP
		PROJECT LIMIT LINE			HEAVY DUTY PAVEMENT	ADI	ADHIST
		RIGHT-OF-WAY/PROPERTY LINE			BUILDINGS	1423	ALICSI
		EASEMENT	2,292		RIPRAP	APPROX	APPROAIMATE
		BUILDING SETBACK		66/6/0	CONSTRUCTION ENTRANCE	BIT	BITUMINOUS
10+00		BASELINE				BS	BOTTOM OF SLOPE
		CONSTRUCTION LAYOUT	27.35 TC×	1027.35 x	TOP OF CURB ELEVATION	BWLL	BROKEN WHITE LANE LINE
		ZONING LINE	28.85 BCX	8026.85×	BOTTOM OF CURB ELEVATION	CONC	CONCRETE
IL.		TOWN LINE	20.80 FLX	FL2B.BDX	FLOW LINE ELEVATION	DYCL	DOUBLE YELLOW CENTER LINE
		IBAT OF DISTURBANCE	26.03 LP A	LF 20105 K	EDGE OF PAVEMENT ELEVATION	EL	ELEVATION
		WETLAND LINE WITH FLAC	132.75 × 45.0 TW	132.75 × 45.0 TW	SPOT ELEVATION	ELEV	ELEVATION
		ROODRAIN	38.5 BW	38.5 88	TOP & BOTTOM OF WALL ELEVATION	EXIST	EXISTING
8.95		BORDERING LAND SUBJECT	- <u>-</u>	×	BORING LOCATION	FDN	FOUNDATION
		TO FLOODING		MC	TEST PIT LOCATION		
01		WEILAND BUFFER ZONE			MONITORING WELL	PPL .	HISI FLOOR ELEVATION
		RMA - RESOURCE MANAGEMENT AREA	UD	u	UNDERDRAIN	GEN	GRANITE
BPA		RPA - RESOURCE PROTECTION AREA	12°D	12°D	DRAINAGE LINE	GTD	GRADE TO DRAIN
				6'RD-+	ROOF DRAIN	LA	LANDSCAPE AREA
EOP		GRAVEL ROAD	12"S	12"S	SEWER LINE	LOD	LIMIT OF DISTURBANCE
MS-3, 3A	WS-3. 3A	EDGE OF PAVEMENT	CHW		OVERHEAD WIRE	MAX	MAXIMUM
CG-2	CG-2	ASPHALT CONCRETE CURB AND MEDIAN		6°₩	WATER LINE	MIN	MINIMUM
00-3	00-3	STANDARD 6" CURB			FIRE PROTECTION LINE	NIC	NOT IN CONTRACT
CG-6	CG-6	STANDARD 4" CURB	2"DW	2"DW	DOMESTIC WATER LINE	NTS	NOT TO SCALE
CG-7	CG-7	COMBINATION 6" CURB & GUTTER		G	GAS LINE	PERF	PERFORATED
		SIDE I ANE STRENG			UNDERGROUND ELECTRIC	PROP	PROPOSED
	~	IMIT OF CURB TYPE	T	ī	TELEPHONE LINE	REM	REMOVE
		SAWCUT	FA	FA	FIRE ALARM	RET	RETAIN
E.			-CATV-		CABLE TV	R&D	REMOVE AND DISPOSE
111111		BUILDING		II II	DRAIN INLET (VDOT D -1 OR D -7)	R&R	REMOVE AND RESET
7	7den	BUILDING ENTRANCE			DRAIN INLET (VDOT D[-3B)	STATE	SOUD WHITE EDGE UNE
- ñ	Ī∢⊔	LOADING DOCK		1	DRAIN INLET (VDOT D -3C)	SWIL	SOLID WHITE LANE LINE
	٠.	BOLLARD	۲	•	DRAIN MANHOLE	SWIL	SOLD WHITE DAVE LIVE
D	D	DUMPSTER PAD	=TD=		TRENCH DRAIN	15	TOP OF SLOPE
-0-	+	SIGN	r	r	PLUG OR STUB	TYP	TYPICAL
-90-	*	DOUBLE SIGN	▶		FLARED END SECTION	Utility	
			\sim		HEADWAIL	CB	CATCH BASIN
		STEEL GUARDRAIL	s	•	SEWER MANHOLE	CMP	CORRUGATED METAL PIPE
		HOOD GUALDINAL	0	•	SEWER CLEANOUT	со	CLEANOUT
	====	PATH	CS	ß		DCB	DOUBLE CATCH BASIN
\sim		TREE LINE	N.		CURB STOP & BOX	DMH	DRAIN MANHOLE
× ×	- * *	WIRE FENCE	15V	15V	WALLER VALUE & BUX	DI	DRAIN INLET
	• •	FENCE		_÷	SIAMESE CONNECTION	(m	CAST IRON PIPE
00	⊷⊷	STOCKADE FENCE	e HYD	HTD A	SPECIESE CONVECTION	COMP	CONDUIT
·	• •	CHAIN LINK FENCE	WM	พัพ	WATER METER	COND n=	DIVERT BOX NOT
	·œœe·	STONE WALL	e PIV	PIV	POST INDICATOR VALVE	DIP	DUCTILE IRON PIPE
	<u> </u>	RETAINING WALL	(1)	@	WATER WELL	ES	END SECTION
		STREAM / POND / WATER COURSE	- 00	- 00		EW	END WALL
		DETENTION BASIN	O' Gi	o a	GAS GATE	FES	FLARED END SECTION
		HAY BALES		۵	GAS METER	F&G	FRAME AND GRATE
)X	×	SILT FENCE	©	٠	ELECTRIC MANHOLE	F&C	FRAME AND COVER
4		MINOR CONTOUR	EM	EM B	ELECTRIC METER	FM	FORCE MAIN
20	<u> </u>	MAJOR CONTOUR	\$	•	LIGHT POLE	GI	GUTTER INLET
(10)	@	BARKING COUNT	0	•	TELEPHONE MANHOLE	GT	GREASE TRAP
		COMPACT PARKING STATIS	TT .	EL I	TRANSEORMER PAP	HDPE	HIGH DENSITY POLYETHYLENE PIPI
DYL	DYL	COMPACT FARRENG STALLS	-		TRANSPORMER PAD	HH	HANDHOLE
SL.	3.	DOUBLE YELLOW LINE	-0-	•	UTILITY POLE	HW	HEADWALL
		STOP LINE	0-	•	GUY POLE	HVD	HYDRANT
		CROSSWALK	, ju	, H	GUY WIRE & ANCHOR	nib NV	INVERT DEVATION
1.1	4_6	ACCESSIBLE CURB RAMP	PB	20 PB	HAND HOLE	INV	INVERTIBLEVATION
6	ė 1	HANDICAP PARKING	2	5	PULL BOX	1-	ENVERT ELEVATION
WAN .	UAN .	VAN-ACCESSIBLE HANDICAP PARKING				LP	LIGHT POLE
						MES	METAL END SECTION
						PWW	PAVED WATER WAY
						PVC	POLYVINYLCHLORIDE PIPE

PIV RCP

R-

TSV

UG

UP

SMH

POST INDICATOR VALVE REINFORCED CONCRETE PIPE

RIM ELEVATION

UNDERGROUND

UTILITY POLE

SEWER MANHOLE

TAPPING SLEEVE, VALVE AND BOX

<text></text>	Ge	eneral	Layout and Materials			
 Multichard and multichard and multicha	1.	THE "MISS UTILITY LAW" REQUIRES FOR THE CONTRACTOR TO CALL 811 AT LEAST 3 WORKING DAYS IN ADVANCE OF THE PLANNED WORK TO ALLOW TIME FOR MARKING, THAT THE MARKS RE RESPECTED AND PROTECTED, AND	 DIMENSIONS ARE FROM THE FACE OF CURR, FACE OF BUILDING, FACE OF WALL, AND CENTER LINE OF PAVI MARKINGS, UNLESS OTHERWISE NOTED. 			
<text></text>		THAT EXCAVATION BE COMPLETED CAREFULLY.	2. CURB RADII ARE FIVE (5) FEET TO FACE OF CURB UNLESS OTHERWISE NOTED.			
<text></text>		CONTROL TO A SHALL BE REPORTED AND AN A SECOND AND AND AN AND AN AND AN AND AN AND AND	CUREING SHALL BE VDOT CC-2 WITHIN THE SITE UNLESS OTHERWISE INDICATED ON THE PLANS. SEE ARCHITECTURAL DRAWINGS FOR EXACT BUILDING DIMENSIONS AND DETAILS CONTIGUOUS TO THE B			
<text><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></text>	L	CORPORATIVE WITH THE PEDEAD AND REPEAR WITH DEABILITIES ALL AND WITH STATE AND IDEAL LAWS AND BECLULTIONS (WITHENVER A ROLES STRENGESTI). AREAS DISTURBED DURING CONSTRUCTION AND NOT RESTORED WITH IMPERVIOUS SUBFACES (BUILDINGS,	INCLUDING SUBWALKS, RAMPS, BUILDING, ENHANCES, SLARWATS, UTBLIT PENERAHUNS, UONLREIE DI PARS, COMPACTOR PARD, LOADING, COCKS, BOLLARDES ETC. 5. PROPOSED BOUNDS AND ANY EXISTING PROPERTY LINE MONUMENTATION DISTURBED DURING CONSTRU-			
<text></text>		PAVEMENTS: WALKS, ETC, SHALL FOLLOW DETAIL PROVIDED BY VIECINE BROSION AND SEDMENT CONTROL HANDBOOK FOR SITE SPECIFIC SEDIOR MICTURES IN ACCORDANCE WITH STANDARD & SPECIFICATION 3.32. WITHIN THE HAITS OF THE HIT INFO EXOTOPENT THE CITE CONTRACTOR SHALL DEDUDE ADDRESS	SHALL BE SET OR RESET BY A PROPESSIONAL LICENSED SURVEYOR. 6. PRIOR TO START OF CONSTRUCTION, CONTRACTOR SHALL VERIFY DUSTING PAVEMENT ELEVATIONS AT IN WITH REPORTED PAVEMENTS: AND REVERTIVE CRODING REVERIES ADM/CEDUTION DEMNALCE OFFICERS TO MEDICAL DEPORTS OF DEVICENCE START ST			
<text><text><text><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></text></text></text>		WITHIN THE EMBILS OF THE BOLLENCE POOL NEW, THE BIT CONTENT ON SHALL PERFORM EARTHWORK OPERATIONS REQUERED UT DURGADE ELEVATIONS. WORK WITHIN THE LOCAL RIGHTS-OF-WAY SHALL CONFORM TO LOCAL MUNICIPAL STANDARDS. WORK WITHIN	WITH FROM TRANSITIONS AND PROTECT REAL AND PROPOSED FACILITIES. PROPER TRANSITIONS BETWEEN EXEMPTION AND PROPOSED FACILITIES. 7. SYMBOLS AND LEGENDS OF PROJECT FEATURES ARE GRAPHIC REPRESENTATIONS AND ARE NOT NECESSAI			
<text><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></text>		STATE BEGITS OF WAY SHALL CONFORM TO THE LATEST EDITION OF THE STATE HIGHWAY DEPARTMENTS STANDARE SPECIFICATIONS FOR HERMANS AND BEDGES. UPON AWARD OF CONTRACT, CONTRACTOR SHALL MARE NECESSARY CONSTRUCTION NOTIFICATION AND ABOV ADD AND APAIRMA NET/SOSTER BEDRITS AND VESS ADD ROOT FORVIR ASSOCIATION MANTHER MORE.	SCALED TO THERE ACTUAL DIMENSIONS OR LICATIONS ON THE DRAWINGS THE CONTRACTOR SHALL REP THE DETAIL SHEET DIMENSIONS, MANIFACTORISE L'ITERATIES, SIAP DRAWINGS AND FRED MEASUREM SUPPLIED FRODUCTS FOR LAYOUT OF THE PROJECT FRATURES.			
 Norm Normality Normality		INDECIDED ON THE DRAWINGS. IN THE SPECIFICATIONS. AND IN THE CONTEACT DOCIMENTS. DO NOT CLOSE OR OBSTRUCT ROADWAYS, SIDEWALKS, AND FREE HYDRANTS, WITHOUT APPROPRIATE FERMIN: TRAFFC SIGNAGE AND PAYEMENT MARKINGS SHALL CONFORM TO THE MANUAL OF UNFORM TRAFFC CONTROL.	THAT ARE OBTINUED FROM THE DESIGNERS, BUT SHALL VEETS LOCATION OF PROBET FRATURES IN ACCO WITH THE PAPER COPIES OF THE PLANS AND SPECIFICATIONS THAT ARE SUPPLIED AS PART OF THE CONTR DOCUMENTS.			
<text></text>		DEVICES.	Demolition			
<text></text>	L	AREAS OUTSIDE THE LIMITS OF PROPUSED WORK DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY THE CONTRACTOR TO THEIR ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.	 CONTRACTOR SHALL REMOVE AND DISPOSE OF EXISTING MANMADE SUBFACE PERTURES WITHIN THE LIM WORK INCLIDING BUILDINGS, STRUCTURES, PAVEMENTS, SLABS, CURBING, FENCES, UTILITY POLES, SICIS, UNLESS INDICATED OTHERWISE ON THE DRAMINGS. REMOVE AND DISPOSE OF EXISTING. THITTIES FOUNT 			
<text></text>	10.	IN THE PENT THAT SISPECTED CONTAMINATES SOL, GRONDWATRE, AND OTHER MEDIA, ARE ENCOUNTEED DUENC DECAVATION AND CONSTRUCTION ACTIVITIES BASED ON VISUAL, OLFACTORY, OR OTHER EVEDINCE, THE CONTRACTOR SHALL STOP WORK IN THE VISION OF THE SISPECT MATEBUAL TO AVOID FURTHER SPEADING. OF THE MATEBAL, AND SHALL NOTIFY THE OWNER MANEDIATELY SO THAT THE APPROPRIATE TESTING AND SIREQUENT ACTION CAN BE TAREN.	AND UNSITTABLE MATTERIAL BENEATH AND FOR A DISTANCE OF 10 FEET BEYOND THE PROPOSED BULLEIN FOOTPENT INCLUDING EXTERIOR COLUMNS. 2. EXISTING UTLIFTES SHALL BE TERMINATED, UNLESS OTHERWISE NOTED, IN CONFORMANCE WITH LOCAL, S AND INMIDUAL UTLIFT COMPANY STANDARD SPECIFICATIONS AND DETAILS. THE CONTRACTOR SHALL			
<text></text>	11.	CONTRACTOR SHALL PREVENT DUST, SEDMENT, AND DEBRIS FROM EXITING THE SITE AND SHALL BE RESPONSIBLE FOR CLEANUP, REPARES AND CORRECTIVE ACTION IF SUCH OCCURS.	COORDINATE UTILITY SERVICE DISCONNECTS WITH THE UTILITY REPRESENTATIVES. 3. CONTRACTOR SHALL DISPOSE OF DEMOLITION DEBRIS IN ACCORDANCE WITH APPLICABLE FEDERAL STATI			
<text><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></text>	2.	DAMAGE RESULTING FROM CONSTRUCTION LOADS SHALL BE REPARED BY THE CONTRACTOR AT NO ADDITIONAL COST TO OWNER.	LUCAL REGULATIONS, ORDINANCES AND STATUTES. 4. CONTRACTOR SHALL APPLY FOR AND OBTAIN ALL NECESSARY PERMITS FROM LOCAL AND STATE AUTHOR COMPRETE THE MORE			
 Institution 	3.	CONTRACTOR SHALL CONTROL STORMWATER BUNOFF DUBING CONSTRUCTION TO PREVENT ADVERSE IMPACTS TO OFF SITE AREAS, AND SHALL BE RESPONSIBLE TO REPAIR RESULTING DAMAGES, IF ANY, AT NO COST TO	5. THE DEMOLITION LIMITS DEPICTED IN THE PLANS IS INTENDED TO AID THE CONTRACTOR DURING THE BIL			
<text></text>	14.	OWNER. THIS PROJECT DISTURIES MORE THAN ONE ACEE OF LAND AND FALLS WITHIN THE VIRCINIA STORMWATER MWANCARMY THE PROCEAM (NSMP; CENERAL CONSTRUCTION FEMALE (CP) PROCEAM AS ADMINISTREED BY THE VIRCINIA DEPARTMENT OF DIVISIONMENTIAL QUALITY DEQL/UNDER THE URSCIPLING OF THE FEAL PROJECT TO THE PRANT OF CONSTRUCTIONS IN CONSTRUCTION CONSTRUCTION OF SHEET AND ADMINISTREED BY THE PRANT OF CONSTRUCTIONS IN CONSTRUCTION CONSTRUCTION OF SHEET AND ADMINISTREED BY THE	International substantiation in the state is the tracket is presented to any inter-control (100 DBHK) THE BB AND CONSTRUCTION PROCESS AND IS NOT THYDROB TO BBHTC ELEVANT OF DIAMOUTTIN THE CONTRACTOR IS RESPONSIBLE FOR IDENTIFIIING THE DEFAULD SCOPE OF DIAMOUTTIN HERE'S SUMM IT SIGN PROFESSATION FROM CONTROL FOR DIAMOUTTING THE OPERATION OF A DIAMOUTTING AND SERVICE SUMMITIONAL COMPENSATION FOR CHANGED CONDITIONS OR INFORESSION OR LATENT STIE CONDITIONAL COMPENSATION FOR CHANGED CONDITIONS OF INFORESSION OR LATENT STIE CONDITIONAL RESULT OF A DIAMOUTTING AND A DIAMOUTTING AND SERVICE SUMMITIONAL CONDITIONS DESCOVERED LATING FOR CHANGED CONTROL STATE OF THE WORK.			
 The contract of the problem is the problem is the contract of the problem is the problem	5.	A STORWWATER POLIUTION PREVENTION PLAN IN ACCORDANCE WITH THE VSMP REGULATIONS. ALL CONSTRUCTION METHODS AND MATERIALS WITHIN CITY REGIT-OF-WAYS OR CITY DESIMENTS SHALL CONFORM WITH THE CURRENT SPECIFICATIONS AND STANDARDS OF THE CITY OF NORPOLI DEPARTMENT OF PREUX WORKS, CUTY OF NORPOLIS DEPARTMENT OF UTILINES, AND THE WORKS AD DEPARTMENT OF	6. UNLESS OTHERWISS SPECIFICALLY PROVIDED ON THE FLANS OR IN THE SPECIFICATIONS. THE ENCINERE H PREPARED DESIGNS FOR AND SHALL HAVE NO RESPONSIBILITY FOR THE PRESENCE, DESCOVERY, REMOVIAL ABATEMENT OR DEPICIAL OF HAZARDOIGS MATERIALS, TOXE WASTES OR POLITIANS AT THE PROJECT ENCINERE SHALL NOT BE RESPONSIBLE FOR ANY CLAMIS OF LOSS, DAMAGE, DEPICES, DEALY, DUING OR ARENNE, FOR THE PRESENCE OF HAZARDOIGS MATERIALS, TOXE WASTES OR POLITICATIONS THE PROJECTION ARENNE, FOR THE PRESENCE OF HAZARDOIGS MATERIALS, TOXE WASTES OR POLITICATIONS AT THE PROJECT.			
<text><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></text>	Jt	lities	HARMLESS INE EVALUEE PROM ANT CLAIMS MADE IN CONNEL IDIN THEREWITH. MOREUVEL, THE EVAL SHALL HAVE NO ADMINISTRATIVE ORIGINATIONS OF ANY TYPE WITH REGRET TO ANT CONTRACTOR AMEN INVOLVING THE ESSLES OF PRESENCE, DISCOVERY, REMOVAL, ABATEMENT OR DISPOSAL OF ASBESTOS OR HAZARDOLSI MATEBALIS.			
<text><text><text><text><text><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></text></text></text></text></text>		THE LOCATIONS, SIZES, AND TYPES OF EXISTING UTILITIES ARE SHOWN AS AN APPROXIMATE REPRESENTATION ONLY. THE OWNER OR IT'S REPRESENTATIVES) HAVE NOT INDEPENDENTLY VERIFIED THIS INFORMATION AS	 REFER TO DEMOLITION DRAWINGS FROM OTHER DISCIPLINES FOR ADDITIONAL INFORMATION AND INSTRUCTIONS. 			
 Name of the state of t		SHOWN ON THE PLANS. THE UTILITY INFORMATION SHOWN DOES NOT CLARANTEE THE ACTUAL DESTENCE, SERVICABLITY, OR OTHER DATA CONCERNING THE UTILITIES. NOR DOES IT CLARANTEE ACARANTE THE POSSIBLITY THAT ADDITIONAL UTILITIES MAY HE PRESENT THAT ARE NOT SHOWN ON THE PLANS. PHORE TO OEDEREG, MATERIJAS AND BEGINNEN, CONSTELLIONN, THE CONTACTOR SHALL WERPS, AND DETEMBINE THE PLANT. LIOCATIONS, SZEES, AND BERANDINGS OF THE POINTS OF CONNECTIONS TO DESTING. UTILITIES AND, SHALL CONSTRUCT AND THE REAL BY A NOTIFICIPATION SHALL WERPS UTILITIES AND, SHALL CONSTRUCT AND THE REAL BY A NOTIFICIPATION SHALL WERPS UTILITIES AND, SHALL CONSTRUCT AND THERE AND NOTIFICIPATION SHALL WERPS UTILITIES AND, SHALL CONSTRUCT AND THERE AND NOTIFICIPATION SHALL WERPS UTILITIES AND, SHALL CONSTRUCT AND THERE AND NOTIFICATIONS OF USE TO DESTING. UTILITIES AND THE REALT	8 THE CONTRACTOR SHALL COORDINATE WITH THE OWNER ANY INTERCIPTIONS OF ELECTRICAL, MECHAN PROTECTION, PLUMBING, COMMINICATION AND OTHER SERVICES WHICH MAY APPECT FACILITY OFFER OTHER BUILDINGS NABLER AND INTERSIPTIONS OF THESE SERVICES AND TO BE SCHEDULED IN ADVANCE I ACCORDANCE WITH SPECIFICATION DWISION ONE IN THE PROTECT MANUAL			
<text><list-item><list-item><list-item><list-item><list-item><list-item><list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></text>		INCLUDING BOUTES WITHIN THE PUBLIC RIGHTS OF WAY. WHERE AN EXISTING UTILITY IS ROUND TO CONFLICT WITH THE PROPOSED WORK OR EXISTING CONDITIONS	9. COORDINATE PHASING OF DEMOLITION WORK WITH OWNER PRIOR TO COMMENCING. 10 ANY ITEMS INDICATED TO BE REINED SHALL BE REMOVED SO AS NOT TO DAMAGE THEM ANY SIGH ITEM			
 Longer Linger Linger		HIRDER FROM THOSE SHOWN SUCH THAT THE WORK CONNOT BE COMPLETED AS INTENDED THE LOCATION. BEPARTON, AND SZE OF THE UTILITY SHALL BE ACCURATELY DETEMBAND WITHOUT DELAY BY THE LOCATION. AND THE NORMATION FURNISHED IN WRITING TO THE OWNERS SEPRESANTARE FOR THE RESULTION OF THE CONFLICT AND CONTRACTORS FALLUE TO NOTIFY PEOR TO PERFORMING ADDITIONAL WORK BELEASES OWNER FROM OBLICATIONS FOR ADDITIONAL PAINMENTS WHITH CONTRECT OF DEBRIGATION FOR THE SECONT THE FORM SECONT ACTION FOR THE TAY AND THE STRUCT OF DEBRIGATION FOR THE SECONT FOR THE SECON	ARE DAMAGED SHALL BE REPLACED WITH SDALAR OR COMPARABLE ITEMS AT THE CONTRACTOR'S EXPEN- WITH THE OWNER/SPACINER'S APPROVAL THE EXCRETE R TO REVEW ALL REUSED ITEMS PROR TO REINSTALLATION. CONTRACTOR SHALL STORE REUSABLE ITEMS UNTIL REINSTALLATION.			
 The control transmission of transmisi		CONFLICT.	Existing Conditions Information			
 In proceeding of the process of the proces		SET CALCH BASIN MINS, AND EVERTS OF SEWERS, DRAINS, AND DITCHES IN ACCORDANCE WITH ELEVATIONS ON THE GRADING AND UTILITY PLANS.	 BOSE FLOW. THE PROFERIT LINES SHOWN WHE DELEMINED BI AVAILATED AND SOLVET CONDUCTED AND FROM PLANS OF RECORD. THE TOPOCREMPHY AND PHYSICAL FEATURES ARE BASED ON AN ACTUAL FI SURVEY PERFORMED ON THE GROUND BY VHB IN FEBRUARY 2018. 			
 A NAMENTS AND CONCENTS SERVICES INTER A NAMENTS AND CONCENTS SERVICES INTER A NAMENTS AND CONCENTS INTER AND AND CHEMICANTS AND ALL BARANCE AND AND ALL BARANCE AND AND ALL BARANCE AND ALL BARANCE	L	EIM HEIVATIONS FOR DRAIN AND SEWER MANHOLES, WATHE VALVE COVERS, GAS GATES, ELECTRIC AND TELEPHONE PULL BORES, AND MANHOLES, AND OTHER SUCH ITEMS, ARE APPROXIMATE AND SHALL BE SET/RESET AS FOLLOWS:	 MERIDIAN SOURCE: VIRCINIA STATE PLANE COORDINATE SYSTEM SOUTH ZONE NAD 83(93) HARN AND AB ON CITY OF NOBFOLK CONTROL MONUMENTS LR16, A307, GPS118, GPS026. 			
 1. Surged transformation and mean statements 1. Surged transformation and mean statements and mean statements 1. Surged transform		A. PAVEMENTS AND CONCRETE SURFACES: FLUSH	 TOPOGRAPHY: ELEVATIONS SHOWN HEREON ARE IN FEET AND ARE BASED ON NORTH AMERICAN VERTIC DATUM OF 1988 (NAVD88) AND ARE BASED ON CITY OF NORFOLK CONTROL MONUMENT NO. A307. 			
 AL AND THREE LANDING THE MERIANT ON THE MILLING THREE AND APPROXIMATION OF THREE AND APPROXIM		 ALL SUBPLIES ADVID ACCESSIBLE ROUTES. FLOSH C. LANDSCAPE, TOPSOIL AND SEED, AND OTHER EARTH SUBFACE AREAS: ONE INCH ABOVE SUBROUNDING 	 GEOTECHNICAL DATA INCLUDING TEST PIT AND BORING LOCATIONS AND ELEVATIONS WERE OBTAINED FI SOLUTIONS, INC. 			
 Notes which we have have have have and a balance in the proposed in of a state interface of a state inter	5.	ARE AND TAPE EARTH TO THE BIN LEVATION. THE LOCATION, SEQ DEDRYL, AND SEPERATIONS DIR CONTRICTION OF PROPOSED PRIVATE UTILITY SERVICES SHALL BE INSTALLED ACCOREGNCE TO THE REQUESIONSTS PROVIDED RL, AND APPROVID RY, THE RESPECTIVE UTILITY COMPARY (GAS, TELEPHONE, BECTRE), FREE ALARADE, RCT, TRAN LESSEN LIAIDS AND LOCATIONS TO BE	THE LOCATIONS OF DESIGNATION OF DESIGNATION OF THE SAME AND A DESIGNATION OF THE DESIGNATION OF DESIGNATION OF DESIGNATIONS			
 UTUITY PPE WATEHALS SHALL BE AS FOLLONS, UNLESS OTHERWES NOTED ON THE PLANE. NUTRET PPE SINUL IE CON PC PPE FOR PPE CARETE TIMA Y BUILINET SOUTH FOR PLANE. NUTRET PPE SINUL IE CON PC PPE FOR PPE CARETE TIMA Y BUILINET SOUTH S	L	COORDINATED WITH OWNER AND ARCHITET. THE ORNER STUDIES AND ARCHITET. THE ORNER STUDIES IN ARCHITECTUDE ON A DUBLICATE OF ANY ARCHITECTUDE TO ANY A RELOCATION AND FOR THE ALTRANSING AND ADJUSTMENT OF CASE HEATTER'S THEFANAR THE ALBRA AND ANY OTHER PROVADE UTURES, WHETHER WORKS & PERFORMED BY CONTRACTOR OF BIT THE UTURES COMPANY.	Document Use Inter plans and conservation of the plan and the servation of plans and conservation of the plans and conservation of plans an			
A WATE PIEC SHULL BE OWNY. PIE NO PIECEETETE THAN 'P DANTIFES WATEN'S DEFINITE WATEN'S DANTE PIECEETETE THAN 'P DANTE WATEN'S DANTE PIECEETETES THAN O BALANT TO 'P DANTE PIECEETES SHULL BEST BALAN CARACTERIST BALANT ON THE DANTE PIECEETES SHULL BEST BALANT OR DANTE PIECEETES BALANT OR DANTE P		UTILITY PIPE MATERIALS SHALL BE AS FOLLOWS, UNLESS OTHERWISE NOTED ON THE PLAN:	WITHOUT THE DRPRESSED. WRITING CONSENT OF VHR. ANY UNAUTHORIZED USE, REUSE, MODRICATION, AUTERNATION, INCLUDING AUTOMATED CONVERSION OF THIS DOCUMENT SHALL BE AT THE USER'S SOLE I WITHOUT LIABELITY OR LEGAL EXPOSURE TO VHR.			
		A. WATER PIPES SHALL BE COO PVC PIPE FOR PIPES CREATER THAN 2" DIAMETER WORKING PRESSURE SHALL BE A MINIMUM OF 250 PSL WATER PIPES LESS THAN OR EQUAL TO 2" DIAMETER SHALL BE TYPE 'K' COPPER.				
CONTRUCTOR SIMUL COORNAUT WITH BELTERAL CONTRUCTOR AND SIMUL PERMISSI DE VANDON KONTRUCTOR SIMUL COORNAUT WITH BELTERAL CONTRUCTOR AND SIMUL PERMISSI DE VANDON KONTRUCTOR SIMUL DECANATA HADRABE STRANDER BLATER DIS SICH AS YELL AVAR CONTRUCTOR SIMUL DECANATA AND BACHEL TENDERS IN DEVINORE BLATER DIS SICH AS YELL AVAR CONTRUCTOR SIMUL DECANATA AND BACHEL TENDERS IN DEVINORE WITH GAS COMPANYS BORDBANCS. CONTRUCTOR SIMUL DECANATA AND BACHEL TENDERS IN DEVINORE AND SIMUL PERMISSI DE CONTRUCTOR SIMUL DECANATA AND BACHEL TENDERS IN DEVINORE CONTRUCTOR SIMUL DECANATA AND BACHEL TENDERS IN DEVINORE AL DEDATION SIMUL DECANATA AND BACHEL TENDERS IN DEVINORE AL ALD BANNAS FROM CONTRUCTOR SIMUL DETERMENTS IN Y SIMUL BATTERMEND DY THE MANUSATATER BACHED ON THE PTO CONTRUCTOR SIMUL DETERMENTS IN THE MANUSATATER BACHED ON THE PTO CONTRUCTOR SIMUL DETERMENTS ALL BETS PRE- LICATION OF PTITOLOGICAL DECANATA AND CREATER THE MINIMUM DAMETER SIMUL BET SIMULATER SIMUL DECANATA AND A REPORT ONLY CONTRACTOR SIMUL DETERMENT ALL BETS REPLEMENTS LICATION OF PTITOLOGICAL DECANATA AND CREATER THE MINIMUM DAMETER SIMUL BET SIMULTOR SIMUL DECANATA AND A REPORT ONLY CONTRACTOR SIMUL DETERMENT ALL BETS REPLEMENT LICATION OF PTITOLOGICAL DECAMPTION ONLY CONTRACTOR SIMUL DETERMENT ALL BETS REPLEMENT ONLY CONTRACTOR SIMUL DECOMPONING LICATION OF PTITOLOGICAL DECAMPTION ONLY CONTRACTOR SIMUL DETERMENT ALL BETS REPLEMENT ONLY CONTRACTOR SIMULTARIES ON DELEMENT ONLY LICATION ON MINIMUM DAMETERS AND DAMETER SIMUL DETERMENT ALL BETS REPLEMENT ONLY CONTRACTOR SIMUL DETERMENT ALL BETS REPLEMENT LICATION ON DERING AND DECOMPONING LICATION ON DAMETERS AND DAMETER SIMUL DETERMENT ALL BETS REPLEMENT ON DECOMPONING ON STRACTOR SIMUL DETERMENT ALL BETS REPLEMENT ON DECAMPACE AND DECOMPONING LICATION ON DAMETERS AND DAMETER SIMUL DETERMENT ALL SIX WITH FOUL GRAVELES AND ALL DECOMPONING LICATIONE SIMULTARIES AND DECAMPACE ONTON		IL SANITARY SEWER PIPES SHALL BE SDR 26 PVC PIPE. C. STORM DRAINAGE PIPES SHALL BE CLASS = REINEODOED, CONORETE PIPE (POD).				
DICUSENDENT OF DICT MAKE & REQUERD IN THE LITERY COMPANY AND & SOUCHTE ON THE REMENSE. O CONTRACTOR SHEE DEXINATE AND EXCIPLINE THEOREM FOR CAS IN ACCOUNTRY THIS CASCOMMENTS REQUERNINTS. ALL DEBANCE AND SANTARY STRUCTURE INTERIOR ENGINES IN AND ISOLAL BOOMENTS REQUERNINTS. ALL DEBANCE AND SANTARY STRUCTURE INTERIOR ENGINES IN AND ISOLAL MINING AND	8.	c. STORM DRAINER PIES SHALL BE CLASS III HERMORED CONDICIE PIE (RCP). CONTRACTOR SHALL COORDINAL WITH BELTERGAL CONTRACTOR AND SHALL FURINESH ECUANTON INSTALLATION, AND BACHELLOF BELTERCAL RUNNERD STEWORK RELATED ITEMS SUCH AS PILL ROUXE CONDUCTS, DUCT BANKS, LIGHT PODE BASKS, AND CONCETTE PARS. CONTRACTOR SHALL FURINESH CONCRETE BASK DRAINES AND RUNNERD STATEMENTS IN THE STATEMENT OF DRAINEST CONCRETE RUNNERD STATEMENTS IN THE RESEARCH OF DRAINEST PARS CONCRETE PARS. CONTRACTOR SHALL FURINESH CONCRETE RUNNERD STATEMENTS IN THE RESEARCH ON THE RESEARCH ON THE RUNNERD STATEMENTS IN THE RESEARCH ON THE RUNNERD STATEMENT OF DRAINEST PARS CONCRETE PARS. CONTRACTOR SHALL FURINESH CONCRETE RUNNERD STATEMENTS IN THE RESEARCH ON THE RUNNERD STATEMENT OF DRAINEST RUNNERD STATEMENTS IN THE RUNNERD STATEMENT OF DRAINEST OF DRAINEST RUNNERD STATEMENTS IN THE RUNNERD STATEMENT OF DRAINEST OF DRAINEST RUNNERD STATEMENTS IN THE RUNNERD STATEMENT OF DRAINEST RUNNERD STATEMENT OF DRAINEST OF DRAINEST OF DRAINEST RUNNERD STATEMENT OF DRAINEST OF DRAINEST RUNNERD STATEMENTS IN THE RUNNERD STATEMENT OF DRAINEST RUNNERD STATEMENT OF DRAINEST OF DRAINEST RUNNERD STATEMENT OF DRAINEST OF DRAINEST RUNNERD STATEMENT OF DRAINEST OF DRAINEST RUNNERD STATEMENT OF DRAINES				
ALL DERIVICAS LAN SINUTIARY STRUCTURE INTERNE DIMANTIRES (* VIN), SIALI EL DETERMINDI PI THE MANUELTATURE ALUBIO NUEL REPLY CONVELIENTING VINUEL PLANA AND LACAL MANNERY PREZ. 10. CONTROL FERTINGES MANNER TANA LES PILS INTERNIS DE ALUBIO SIALI DETERMINDI AL INTERNE RECURSION OF FETTINGES SIANNI MERCINA RECONSTRUCTIONE CONTRACTOR SIALI DETERMINE AL INTERNE REQUERIMENTS AND LOCATIONE REMO ALUBIO NOTIFICIO DE ALUBIO SIALI DETERMINE AL INTERNE REQUERIMENTS AND LOCATIONE REMO ALUBIO NOTIFICIO DE CONTRACTOR SIALI DETERMINE AL INTERNE REQUERIMENTS AND LOCATIONE REMO ALUBIO NOTIFICIO DE CONTRACTOR SIALI DETERMINE ALI INTERNE REQUERIMENTS AND LOCATIONE REMO ALUBIO NOTIFICIO DE CONTRACTOR SIALI DETERMINE ALI INTERNE REQUERIMENTS AND LOCATIONE REMO ALUBIO NOTIFICIO DE CONTRACTOR SIALI DETERMINE ALI INTERNE REQUERIMENTS AND LOCATIONE REMO ALUBIO NOTIFICIO DE CONTRACTOR SIALI DETERMINE ALI INTERNE REQUERIMENTS AND LOCATIONE REMO ALUBIO NOTIFICIO DE CONTRACTOR SIALI DETERMINE ALI INTERNE REQUERIMENTS AND LEBERONA ATULI REPLICINSTRUM DE MONITORIS.		ENCASEMENT OF DUCT BANKS IF REQUIRED BY THE UTILITY COMPANY AND AS INDICATED ON THE DRAWINGS. CONTRACTOR SHALL EXCAVATE AND BACKFILL TRENCHES FOR GAS IN ACCORDANCE WITH GAS COMPANY'S more improvements				
LUCIONION OF PITINGS SHOWN HEREIN ARE APPROXIMATE ONLY CONTRACTOR SHALL DETERMINE ALL HITING REQUERMENTS AND LOCATION FROM ACTUAL HERE ONORTHONS. POP LINCHTS SHOWN HEREON ARE FROM CONTENENT OF STRETCHER AND ARE APPROXIMATE CONTRACTOR SHALL DETERMENT ACTUAL PPE LINCHES FROM HERE CONTRACTOR. 3. WIER'S CONTRACT ALL STRUCTURES FROM HERE ON ARE APPROXIMATE ONLY. 4. BUILENTATION REAL ALL STRUCTURES FROM HERE ONLY CONTRACTOR SHALL STRUCTURES RUSSI WITH HISAL CRADE.	0.	ERQUERINGUES ALL DRAINAGE AND SANITARY STRUCTURE INTERIOR DIAMETERS (F. MIN') SHALL EE DETERMINED BY THE MANUFACTERER BASED ON THE PFFC CONFIGURATIONS SHOWN ON THESE PLANS BADI LOCAL MEDIACPAL STRUMENES. TORE MANNOLES THAT HAR THE PHT IN DEPTH AND GEARTHE. THE MANNEM DAMETER SHALL IE 5				
POP LINGTIS SHOWN HEREON ARE FROM CENTERINE TO CENTERINE OF STRUCTURE AND ARE APPROXIMATE CONTENCTOR SHILD BETREMEN ACTULA IPPE LINGTIS ROW FRID CONSTRUME. NUESTS CONTENCE LEIVATIONS AT ALL SERUCTIRES SLOPES AND LINGTIS ARE APPROXIMATE ONLY. NUESTS CONTENCE LEIVATIONS AT ALL SERUCTIRES SLOPES AND LINGTIS ARE APPROXIMATE ONLY. NUESTS CONTENCE LEIVATIONS AT ALL SERUCTIRES ALL SERUCTIRES RESS. NUESTS CONTENCE LEIVATIONS AT ALL SERUCTIRES AND LINGTIS ARE APPROXIMATE ONLY. NUESTS CONTENCE LEIVATIONS AT ALL SERUCTIRES AND LINGTIS ARE APPROXIMATE ONLY. NUESTS CONTENCE LEIVATIONS AT ALL SERUCTIRES AND LINGTIS ARE APPROXIMATE ONLY. NUESTS CONTENCE LEIVATIONS AT ALL SERUCTIRES ALL SERUCTIRES RESS. NUESTS CONTENCE LEIVATIONS AT ALL SERUCTIRES ALL SERUCTIRES RESS. NUESTS CONTENCE LEIVATIONS AT ALL SERUCTIRES ALL SERUCTIRES RESS. NUESTS CONTENCE LEIVATIONS AT ALL SERUCTIRES ALL SERUCTIRES RESS. NUESTS CONTENCE LEIVATIONS AT ALL SERUCTIRES ALL SERUCTIRES RESS. NUESTS CONTENCE LEIVATIONS AT ALL SERUCTIRES RESS. NUESTS RESS. NUESTS RESS. NUESTS RESS. NUESTS RESS.	1.	LOCATION OF FITTINGS SHOWN HEREON ARE APPROXIMATE ONLY. CONTRACTOR SHALL DETERMINE ALL FITTING REQUIREMENTS AND LOCATIONS FROM ACTUAL FIELD CONDITIONS.				
NUMERY CONTROL REVIEWONS AT ALL STRUCTURES, SLOPES AND LENGTES ARE APPROXIMATE ONLY Add EDUCTION SHOWN REPEON ARE APPROXIMATE ONLY. CONTRACTOR SHALL SET ALL STRUCTURES FILLSH MUTH FINAL GAME.	2	PPE LENGTHS SHOWN HEREON ARE FROM CENTRELINE TO CENTRELINE OF STRUCTURE AND ARE APPROXIMATE. CONTRACTOR SHALL DETERMINE ACTUAL PIPE LENGTHS FROM FIELD CONDITIONS.				
4 EIN-IENVILIONS SHOWN HEREIN ARE APPROXIMATE ONLY. CONTRACTOR SHALL SET ALL STRUCTURES RUSH WITH RIVLI CRADE	13.	INVERTS CONTROL ELEVATIONS AT ALL STRUCTURES, SLOPES AND LENGTHS ARE APPROXIMATE ONLY.				
	14.	EM ELEVATIONS SHOWN HEREON ARE APPROXIMATE ONLY. CONTRACTOR SHALL SET ALL STRUCTURES FLUSH WITH RIVAL GRADE.				

City of Norfolk Standard Erosion and Sediment Control Notes

- UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MARITAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VINCENA BOSION AND SEDMENT CONTROL HANDROOK (SIR DEDITON, 1992) AND THE TROL ORDINANCE
- THE CONTRACTOR SHALL CONTACT THE CITY OF NORFOLK, BUREAU OF ENVIRONMENTAL SERVICES (757-684-4388) AT LEAST 48 HOURS PRIOR TO ANY LAND DISTURING ACTIVITY (INCLUDING DEMOLITION) SO THAT A PRECONSTRUCTION CONFERENCE CAN BE SCHEDULED.
- 3. THE CONTRACTOR SHALL APPLY PERMANENT OR TEMPORARY SOIL STABILIZATION TO ALL DENUDED OR DISTUBBED AREAS WITHIN 7 DAYS AFTER INAL GRADE IS BEACHED ON ANY PORTON OF THE STIE. SOIL STABILIZATION MIST ASSO BEAPUED TO DENUEDE OR DISTUBBED ARESS WHICH MAY NOT BEA TRNU CARDU BUT WHICH WILL REMAN UNDISTURBED FOR LONGER THAN 14 DAYS. SOIL STABILIZATION MEASURES INCLUDE VEGETATIVE STRAILISMENT, AND MEASURES INCLUDE OR ANY DEAL OF ANY DEAL ON ANY DEAL ON DEALS OF MEMORY DEAL OR ANY DEAL ON ANY DEAL ON DEALS OF MEMORY DEAL OR ANY DEAL ON ANY DEAL
- ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CONSTRUCTION.
- THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES PERIODICALLY AND AFTER EACH RUNOFF PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES AND CLEMINUP OF SEDMENTATION ARE THE RESPONSIBILITY OF THE CONTRACTOR AND
- THE CONTRACTOR SHALL LIMIT SITE ACCESS BY CONSTRUCTION VEHICLES TO ENTRANCES PROTECTED BY A STONE CONSTRUCTION ENTRANCE (VESCH SITE & SPEC. 302) OR AN APPROVED COMPARABLE CONTROL MEASURE. SEDNENT SHALL BE REMOVED FROM PAVED AREAS ON A DALLY BASIS.
- STOCK PIES OF SOIL AND OTHER ERODIBLE MATERIALS SHALL BE STABILIZED OR PROTECTED WITH SEDIM TRAPPING MEASURES. THE CONTRACTOR IS RESPONSIBLE FOR THE TEMPORARY PROTECTION AND PERMAN STABILIZATION FOR STOCKPEES ON STER AS WELL AS FOR MATERIALS TRANSPORTED FROM THE PRODECT STE.
- THE CONTRACTOR SHALL MONITOR AND TAKE PRECAUTIONS TO CONTROL DUST INCLUDING (BUT NOT LIMITED TO) USE OF WATER. MULCH. OR CHEMICAL DUST ADHESIVES AND CONTROL OF CONSTRUCTION SITE TRAFFIC.
- EFFLUENT FROM DE-WATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDMENT TRAPPING DEVICE, OR BOTH, AND DISCHARGED IN A MANNER THAT DOES NOT ADVERSELY AFFECT ADJACENT PROPERTIES, WETLANDS, WEITREWAYS, OF THIS FOTORM DRAINGER SINTH
- THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION AND MAINTENANCE OF ANY ADDITIONAL CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED NECESSARY BY THE PLAN APPROVING AUTHORTY.
- TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES ARE NOT TO BE REMOVED UNTIL ALL DISTURBED AREAS ARE STABILIZED. AFTER STABILIZATION IS COMPLETE, ALL MEASURES SHALL BE REMOVED WITHIN 30 DAYS TRAPPED DEDIMENTS THALI RE SPERAD AND SEPIDED
- City of Norfolk Right of Way Division Standard Site Plan
- Excavation and Restoration in the Right of Way
- ALL WORK WITHIN THE ERGHT-OF-WAY SHALL COMPLY WITH THE CITY OF NORFOLK RECHT-OF-WAY EXCAVATION & RESTORATION MANULL (ORDINANCE NO. 40.778), DEPARTMENT OF PUBLIC WORKS RECHT-OF-WAY DISCON. DOWNLOAD AT <u>HTTP://WWW.NORFOLK.GOV/DOCUMENTICENTER/WEW778</u>, IT IS MIPORTANT THAT CONTRACTORS FAMILIARZE THEMBELI'SS WITH THE REQUEREMENTS OFTIMED IN THE MANUL, FALLIPE TO DO SO MAY IMPACT PROJECT COSTS. ALSO SEE "OTHER" IN THIS SECTION. EXCEPTIONS MAY BE PERMITTED. A REVIEW MEETING WITH RIGHT-OF-WAY IS REQUIRED. PLEASE CONTACT PUBLIC WORKS AT PWROW@NORFOLK.GOV TO SCHEDULE
- ALL WORK WITHIN THE BERHT-OF-WAY SHALL COMPLY WITH THE CITY OF NORFOLK DESIGN STANDARDS. DOWNLOAD AT HTTP://WWW.NORFOLK.GOV/NDEX.SPX7NID-81B. EXCEPTIONS MAY BE PREMITTED. A REVIEW MEDING, WITH REATE-OF-WAY IS REQUIRED. PLASE CONTACT PUBLIC WORKS AT <u>WINOW-MORFOLK.GOV</u> TO SCHEDULE.
- FLOWABLE FILL IS NOT AN APPROVED MATERIAL FOR USE IN THE CITY OF NORFOLK FOR BACKFILL WITHOUT PRIOR APPROVAL. THE SELECT MATERIAL AND 21A STONE SHALL BE IN ACCORDANCE WITH THE 2002 'NOT ROAD AND BREGE SPECIFICATIONS FOR BACKFILL AROUND THE PHP EUS SELECT MATERIAL ISETION 2007. "TYPE IAND 20 CBR COMPACTION. FOR THE SUB BASE MATERIAL USE 6' MIN. VDOT 21A STONE IN ACCORDANCE WITH SECTION 208.
- 4. NEW DEVELOPMENTS, CONSTRUCTION, AND ADDITIONS REQUIRE NEW SIDEWALK, CURR, GUTTER, AND DRIVEWARS, EXCEPTIONS MAY BE PREMITTED. A REVIEW MEETING: WITH RIGHT-OF-WAY IS REQUIRED. PLEASE CONTACT PUBLIC WORKS AT PREMOVENOEMICACOV TO SCHEDULE.
- IF APPROVED BY RIGHT OF WAY, WHEN THE CONTRACTORS WORK BEQUIRES THE SAWCUTTING AND/OR PARTIAL DEMONTRON ARMOUNT REMAINANCE AND SECTION OF AN EXERTING APPEND OR SEDEWALK. THE MONORITHE APPEND OR SEDEWALK SENSE EREMOVED TO THE NEARST1ONT. ATLC CONCETTE ESTO ESTAVO OR SEDEWALK SENSE EREMOVED TO THE NEARST1ONT. ATLC CONCETTE ESTO COMMERCIAL APPEND REMAINA APPEND SENSE EREMOVED TO THE NARREST1ONT. ATLC COMMERCIAL APPEND REMAINA APPEND SENSE EREMOVED TO THE NARREST1ONT. ATLC COMMERCIAL APPEND. RESULTATIONAL APPEND SENSE ALL BEFLACED WITH AN APPENDED ESTAVISATION FOR APPENDA AT INFORMATIONAL BEFLACE DWITH AN APPENDED ESTAFUTO-HAVIS.
- 6. UTILITY POLES MUST BE RELOCATED AT THE COST OF THE PROJECT. A COPY OF THE WORK ORDER FOR POLE RELOCATIONS MUST ACCOMPANY RICHT-OF-WAY PERMITS.
- Permits
- A PERMIT AND INSPECTION IS REQUIRED TO PERFORM EXCAVATION AND INSTALLATION WORK OF ANY KIND IN THE RIGHT-OF-WAY. APPLICATIONS: <u>HTTP://WWW.NORFOLK.GOV/INDEXASPX?NID=362</u> A PERMIT AND INSPECTION IS REQUIRED TO SLOW, CLOSE, REDIRECT, DETOUR, OR ALTER VEHICULAR AND PEDESTRIAN TRAFFIC FOR ANY DURATION. APPLICATIONS: <u>HTTP://WWW.NORFOLK.GOV/INDEX.ASPX?NID=382</u>
- 3. A PERMIT AND INSPECTION IS REQUIRED FOR LANE OR SIDEWALK CLOSURES FOR WORK WASHING, GRADING, OR INSTALLING ANY ITEM ABOVE OR UNDERGROUND. APPLICATIONS:
- 4. A PERMIT AND INSPECTION IS REQUIRED TO PLACE ANY OBJECT IN THE CITY RIGHT-OF-WAY. APPLICATIONS: HTTP://WWW.NORFOLK.GOV/INDEXASPX?NID=382
- 5. A PERMIT IS REQUIRED TO HAUL OVERSIZED, OVERWEIGHT, OR OVERHEIGHT LOADS. APPLICATIONS: HTTP://WWW.NORFOLK.GOV/INDEX.ASPX?NID=362
- A PERMIT AND INSPECTION IS REQUIRED WHEN A NEW APRON AND/OR SIDEWALK IS INSTALLED. ALL NEW OR EXISTING UTILITY STRUCTURES SHALL BE INSTALLED AND/OR RELOCATED OUTSIDE THE AREA OF THE NEW APRON AND/OR SIDEWALK APPLICATIONS: WWW.YORFOLG/OV/INDEGASTRYRID=362
- A PERMIT AND INSPECTION IS REQUIRED FOR TEMPORARY BULK WASTE CONTAINERS PLACED IN THE RIGHT-OF-WAY. IF THE CONTAINER IS PLACED ON PRIVATE PROPERTY A PERMIT FROM THE HEALTH DEPARTMENT IS REQUIRED.
- Fees 1. CURRENT RIGHT OF WAY PERMIT FEES: HTTP://WWW.NORFOLK.GOV/DOCUMENTCENTER/VIEW/789
- EXEMPTION: CONTRACTORS PERFORMING WORK UNDER CONTRACT WITH THE CITY OF NORFOLK ARE DEMPT FROM PREMIT FEIS THROUGH JULY 1, 2014. EFFECTIVE JULY 1, 2014. CONTRACTORS PERFORMING WORK UNDER CONTRACT WITH THE CITY OF NORFOLK MILST PAY STERET, LINAR, AND SDEWALK CONSIDER FEIS.
- 3. EXEMPTION: CONTRACTORS PERFORMING WORK UNDER CONTRACT WITH VDOT ARE EXEMPT FROM ALL PERMIT

ALL TRAFFIC CONTROL SHALL COMPLY WITH THE LATEST EDITION OF THE "MANUAL OF UNBFORM TRAFFIC CONTROL DEVICES (MATCH), THE "URGENAU WORK AREA PROTECTION MANUAL" AND THE "CITY OF NORPOLE EDITI OF WATE EXCANTEN AND RESTORATION MANUAL, WIETHING IN PRICE OF NOTA THE THAT OF RESE RESTORMENT OF ANY EDITION OF THE THE OF RESEARCH AND THE TO ANY OF THE THAT OF RESEARCH AND ANY MANUAL AND THE TO ANY OF ANY OF THE THAT OF ANY OF THE TO ANY OF ANY ANY OF AN City of Norfolk Department of Utilities Notes (Updated 4/11/2017) Water and Sewer Utility Notes

City Of Norfolk Notes

FOR CONSTRUCTION IN OR ADJACENT TO ANY ARTERIAL AND/OR COLLECTOR STREETS REQUIRING TEMPORARY LANE OR STREET CLOSURE. THE CONTRACTOR MUST SCHEDULE A MEETING WITH THE CITY'S TRAFFIC MITIGATION TRAM. FLASES CONTRACT FUEL WORKS AT <u>PROMOVEMORPOLICACI</u> TO SCHEDULE.

THE CONTRACTOR WILL BE REQUIRED TO SUBMIT A DETAILED TRAFFIC CONTROL PLAN (MOT) WITH THE CONTRACTOR'S PREMIT APPLICATION TO WORK IN THE RECHT-OF-WAY AT LEAST 14 DAYS IN ADVANCE OF THE START DATE. THE MOT SHALL BE A DRAWING OR ABELLA PHOTO WITH SITE SPECIFIC DETAILS. THESE SHALL INCLUDE BUT ARE NOT LIMITED TO: TRAFFC SIGNA DRECTONAL SIGNA DESTINATION SIGNACE CHANNELIZION ADVILUE BUT ARE NOT LIMITED TO: TRAFFC SIGNA DRECTONAL SIGNA DESTINATION SIGNACE CHANNELIZION CONTRACTOR DE ADVILIMIETO TO TRAFFC SIGNA DRECTONAL SIGNA DESTINATION SIGNACE CHANNELIZION CONTRACTOR DE ADVILIMIETO TO TRAFFC SIGNA DRECTONAL SIGNA DESTINATION SIGNACE CHANNELIZION CONTRACTOR DE ADVILIMIETO TO TRAFFC SIGNA DRECTONAL SIGNA DESTINATION SIGNACE CHANNELIZION CONTRACTOR DE ADVILIMIETO TO TRAFFC SIGNA DRECTONAL SIGNA DESTINATION SIGNACE CHANNELIZION CONTRACTOR DE ADVILIMIETO DE ADVILIMIENTO DE ADVILIMIENTO DE ADVILIMIENTO DE ADVILIMIETO DE ADVILIMIETO DE ADVILIMIETO DE ADVILIMIENTO DE ADVILIMIETO DE ADVILIMIENTO DE ADVILIMIETO DE ADVILIMIENTO DE ADVILIMIENTO DE ADVILIMIENTO DE ADVILIMIENTO DE ADVILIMIENTO DE ADVILIMIENTO DE ADVILIMIENTE DE ADVILIMIENTO DE ADVILIMIENTE DE ADVILIMIENTO DE ADVI

INCLUDE BIT ARE NOT LIMITED TO: TRAFFIC SIGNS, DIRECTIONAL SIGNS, DISTINATION SIGNAGE, CHANNELZING, DEVICES WATER-FILLED BARBIES, PORTABLE MESSAGE BOARDS WITH MESSAGES TO BE DISPLAYED AND TIMES AND DURATIONS OF DISPLAYED MESSAGES. ADDITIONALIT THE MOT SHALL DISPLAY THE EXACT LOCATION OF ALL SIGNS AND/OR DEVICES INCLUDING, SPACENG FOR EACH SIGN AND/OR DEVICE, SPACENG BEING APPROPRIATE FOR THE WORK SONE LOCATION AND FORSED SPEED LIMITS. ALL MAINTENANCE OF TRAFFIC MONT PLANS THAT

FOR THE WORK ZONE LOCATION AND POSIED SPEDI LIMTS. ALL MAINTENANCE OF TRAFFIC (MOT) PLANS SHALL CONFORM TO THE CURRENT ISSUE OF "THE VIRGINA WORK AREA PROTECTION MANUAL COPIES OF REPRODUCTIONS OF STANDARD WWAPM TTC PLANS MAY NOT BE SUFFICIENT. CONTRACTORS SHOLL CONSIDER THESE THEAS WHEN BEDDING FOR CONSTRUCTION AS IT MAY AFFECT COSTS.

NORFOLK POLICE REQUIRES OFF-DUTY OFFICERS FOR TRAFFIC CONTROL IN ANY SIGNALIZED INTERSECTION AND AS REQUIRED BY PERMIT. OFF-DUTY OFFICERS ARE INDEPENDENT CONTRACTORS. THE COST FOR OFF-DUTY OFFICIENTS AS CONTRACTOR/OWNER REPORTORIUTY

THE CONTRACTOR, OWNER, OR DEVELOPER WILL BE REQUIRED TO POST A CASH, CHECK, OR SURETY BOND OR LETTER OF CREDIT TO EXCAVATE IN THE RIGHT OF WAY. DOWNLOAD THE FORM <u>HTTP-WWWNOROBUCKONCOCCMENTERVENTION</u>

BOND AMOUNT MUST INCLUDE 100% TOTAL COST OF ROW INSTALLATION INCLUDING STREETLIGHTS, WATER, SENER, STORM, BANK, ROADWAR, SIDENNAL, CURR, GUTTER AS WELL AS ANY STORAMWATER INFRASTRUCTURE WORK BEING DONE ON THE PRIVATE PROPERTY SDE. AN ADDITIONAL AMOUNT MAY BE SET AT THE DISCRETION OF THE DIRECTOR OF PHALE WORKS AND/OR ROW MANAGER.

BOND WILL BE REDUCED DOWN TO 10% FROM THE DATE OF FINAL INSPECTION FOR A 2 YEAR WARRANTY TERM A STPARATE WARRANTY BOND IS ACCEPTABLE IN LEU OF A BOND REDUCTION. A LETTRE REQUESTING RELEA OR REDUCTION MUST BE SENT TO THE REGITTO-FWARMS OFFER LEWIS ANALLA IT PROVINGINGATIONS (CON-

ALL CITY PRODUCTS AND SECIAL UTILITY PROJECTS. ALS DETEMANED BY THE DOW ADMINISTRATOR CANNOT BE BUT INTEL UTILITIES ARE BELCACHED OF RARMANEST MAN BEN COORDINATION BY THE CITYS PRODET MANAGER, AC, AND BERT-OF-WAY DIVISION. FLESSE PROVIDE A LIST AND DRAWINGS OF ALL UTILITIES NEEDING, ERACOMING TO BERT-OF-WAY DIVISION. TO RESIDE PROVIDE A LIST AND DRAWINGS OF ALL UTILITIES NEEDING, ERACOMING TO BERT-OF-WAY DIVISION. TO RESIDE PROVIDE A LIST AND DRAWINGS OF ALL UTILITIES

PROJECT DESIGNERS MUST INCLUDE A DETAILED TRAFFIC CONTROL PLAN FOR UTILITY WORK WITHIN THE BEHT-OF-WAI IN THE PLANS. FOR CONSTRUCTION IN OR ADJACENT TO ANY ARTBRUA AND/OR COLLECTOR STRETS AS DEPEND IN THE INFLANS. WORK AREA PROTECTION MANUAL REQUERNS, TRAFFICARTE LIAN CO STRET CLOSHE, THE CONTRACTOR MIST SCHEDULE A MEETING WITH THE CITY'S TRAFFIC MITIGATION TRAM. PLAGE CONTACT, TUBLIC WORK ARE AT <u>WRITE WORK OF TO CHILD CONTACT</u>.

6. ANY DEVIATION FROM THE CITY'S ROW EXCAVATION & RESTORATION MANUAL THAT IS BEING REQUESTED MUST BE MARKED ON THE PLANS. ALSO, A DETAILED LIST OF THE DEVIATIONS MUST BE PROVIDED AS WELL.

2. DETAILED STAMPED DRAWINGS FOR SHORING AND SCAFFOLDING WILL BE REQUIRED AS PART OF THE RIGHT-OF-WAY PERMIT PROCESS.

FULL CURB TO CURB RESURFACING WILL BE REQUIRED IF ROADWAY PORTION IS CUT WITHIN THE FIRST 5 YEARS AFTER RESURFACING, AN ADMINISTRATIVE FEE OF \$500 WILL BE ASSESSED IN ACCORDANCE WITH CITY CODE.

AS PART OF THE CONTRACTOR'S PREMIT APPLICATION TO WORK IN THE RIGHT-OF-WAY, THE CONTRACTOR MLIST SUBMIT A MAP IDENTIFING THE PROJECT'S STORAGE AND LAY DOWN AREA. THE CITY DOES NOT ALLOW STORAGE STAREN OR LAY DOWN AREAS WITHIN THE REVIEW-OWAY. CONTRACTORS ARE RECORRECTLY MARE REMARKEDING TO STORE MATERIALS AND LAY DOWN ON PRIVATE PROPERTY OR THEI MLIST RE STORED WITHIN CONSTICUTION STRE

ALL MISS UTILITY MARKINGS IN THE RIGHT-OF-WAY ARE REQUIRED TO BE ERADICATED AT THE COMPLETION O THE PROJECT IN ACCORDANCE WITH THE CITY'S ROW EXCAVATION & RESTORATION MANUAL LOCATED A WWW.NORFORK.GOVINDEA.RPY/NID-382

7. DESIGNERS ARE RESPONSIBLE TO CHECK IN-FIELD GRADES AND TO CONSULT WITH THE PROPER CITY O LISBANDES ARE RESPUNDENTE TO CHECK IN-HELD GRADES AND TO CONSULT WITH THE FROPPER CITY OF NORTOKI STAFF FIBER ARE QUESTIONS OR CONCERN. DESCRIBES MUST SHART A NOTECH VIA BAHAI TO THE BICHT-OF-WAY DIVISION AT <u>PWROW@NORFOLK GOV</u> VERIFYING THAT GRADES HAVE BEEN CHECKED AND ARE CORRECT.

8. A CONSTRUCTION FENCE MAY BE REQUIRED FOR YOUR SITE. IN DOWNTOWN, CONCRETE BARRIERS AND WOOD PANELS ARE REQUIRED IN MOST CASES. IN SOME CASES, CHAIN LINK FENCE IS ACCEPTABLE. A REVIEW BY BIGHT-OF-WAY IS REQUIRED TO DETERMINE THE TYPE OF FENCE PLACE CONTACT PUBLIC WORKS AT

1. NOTIFICATION MUST BE APPROACHED FROM 3 LIVES OR TIME FOCUSING ON THOSE APPECTED BY THE CONSTRUCTION. CONTRACTORS AND/OR PROJECT SPONSOR ARE REQUIRED TO MOTH RESIDENTS AND BUSINSSES IN THE BAMEDIATE AREA THAT WILL BE AFFECTED BY THE CONSTRUCTION. DOOR HAVGESM MIST BE PLACED AT LISAST 48 HOUSE PROOF TO CONSTRUCTION AND MUST INCLUIDE A 24 HOUR CONTLACT PHONE NUMBER FOR EMERCINCES. UPDATES MUST BE FROVIDED TO RESIDENTS AND BUSINESSES ON A BI-WEBRLY OR MONTHLY MASS OPENDING ON THE FOLLOWING:

A. IMMEDIATE IMPACT - BUSINESS OR RESIDENTS WITHIN THE CONSTRUCTION ZONE WHO WILL BE AFFECTED BY ACCESS RESTRICTIONS. NOISE DIRT AND DUST. USE OF PROPERTY DIRECTLY ADJACENT TO THEM. ETC.

B. AREA IMPACT - THOSE WHO TRAVEL THROUGH OR WILL BE DETOURED AROUND LOCAL OR COLLECTOR STREETS, AFFECTED BY CONSTRUCTION INCLUDING CIVIC LEAGUES, BUSINESS ASSOCIATIONS AND PROPERTY OWNERS.

C. CITYWIDE IMPACT - THOSE WHO ARE AFFECTED BY VEHICULAR OR PEDESTRIAN ACCESS ON ARTERIAL STREETS OR IN BUSINESS OR OTHER PUBLIC ACTIVITY AREAS ISCHOOLS. UNIVERSITIES, GOVERNMENT FACILITIES, ETC.)

PLEASE INCLUDE A SEQUENCE OF CONSTRUCTION IN THE PLANS. (REFER TO SHEET C1.02)

3. ANY EXCAVATION IN THE ROADWAY MUST BE PATCHED WITH ASPHALT. STONE IS NOT ACCEPTABLE.

NOTES TO CITY AND SPECIAL UTILITY PROJECT A/E DESIGNERS AND CONTRACTORS:

Traffic Control

Bonds

Other

PWROW@N

Notifications

- ANY TIE-INS TO EXISTING LINES THAT WILL RESULT IN INTERRUPTION OF SERVICE TO ANY CUSTOMER MUST BE COORDNATED WITH THE CITY OF NORFOLK AS TO ACCEPTABLE TIME AND DURATION OF INTERRUPTION. SCHEDULED INTERRUPTIONS OF SERVICE (TIE-NAS, ARADIOMMENT, FEC) REQUEED 3 DAYS ADVANCE NOTICE.
- ALL TEES, BENDS, PLUGS, AND VALVES SHALL BE PROVIDED WITH MECHANICAL THRUST RESTRAINT AND RESTRAINED TO PROPER LENGTH. PLUGS INSTALLED ON ACTIVE WATER MAINS SHALL BE RESTRAINED. ENDS OF FUNTING UNES TO BE ARANDONED SHALL BE CAPPED WATER.TICHT
- WHERE WATER MAINS PASS OVER SERVER MAINS, THEY MLIST BE 18 INCHES ABOVE, OR THE SERVER MLIST BE A 20 FOOT SECTION OF AWWA APPROVED PRESSURE PIPE. WHERE WATER LINES PASS BELOW SERVER, 18 INCHES OF CLEARANCE IS REQUIRED AND SEWER MLIST BE CONSTRUCTED OF AWWA APPROVED PIPE (18 FOOT LONG PIECE MRIMALING, INCHERED ON WATER MAIN PIPE SECTION.
- NEOPRENE PADS SHALL BE USED BETWEEN PROPOSED AND EXISTING UTILITIES AT CROSSINGS WHERE THE VERTICAL CLEARANCE IS LESS THAN SIX (6) INCHES.
- RIGHT-OF-WAY PIPE MATERIAL SHALL BE PVC SDR 26 OR CLASS 52 DL ALL SANITARY SEWER DUCTILE IRON PIPE SHALL BE LINED WITH PROTECTO 401 OR APPROVED EQUAL
- THE LOCATIONS OF EXISTING AND OR PROPOSED SEWIE LATERALS, PRIVATE PROPERTY LINE CLEAN-OUTS AND WATER METER BRUCATIONS SHOWN ON THE DRAWINGS ARE APPROXIMATE BASED ON CLERENT BRUCORDS AND PRELIMMARY PRED INVESTIGATIONS. THE CONTEXCTOR SHALL BERSONSER FOR LOCATING ALL METER ROXES, WHERE APPLICABLE AND AT THE RESIDENCE PROR TO COMPLETING ANY BEHAB OR BRULCADINTY WORK.
- PRIOR TO CONSTRUCTION OR EXCAVATION, CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES. CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIR TO ALL DAMAGED UTILITIES AT HIS
- UTILITIES FIELD ENGINEERING OFFICE SHALL BE CONTACTED AT 757-823-1001 FIVE (5) DAYS PRIOR TO START OF WORK TO SCHEDULE AN INSPECTOR AND PRECONSTRUCTION CONFERENCE. APPROVED SUBMITTALS ARE REQUIRED FOR ALL INSPECTOR MATERIALS.
- ALL CITY BICHT-OF-WAY AND CITY UTILITY EXISTENT WATER AND SANTARY SEWER WORK SHALL BE PERCEMEND IN ACCORDANCE WITH THE LATIST HAMPTON ROADS FLANDING DISTRET COMMISSION BECOMAL SPECIFICATIONS, CITY OF NORFOLK MODIFICATIONS TO THE HERDON STANDARDS, AND THE VIECTION DEPARTMENT OF HEALTH REGULATIONS. APPROVED SUBMITTALS ARE REQUIRED REPORE UTILITY WORK CAN PROCEED.
- RIGHT-OF-WAY METER INSTALLATIONS:
- ALL TAPE, PRPIC, SERVET UNES VALVES, VALVE BOXES, METRE ROXES AND REW INDEANTS SHALL BE INSTALLED BY THE DRIVID/DRFS CONTRACTOR AND DRIFFED FIT HE DFRAFMONT OF UTILITIES.
 CITY CREWS SHALL ROSTALL ALL METRES, AND DETECTOR CHERCS AT DEVELOPER'S EXPENSE. SUCH ITEMS SHALL BE INSTALLED WITHIN 90 DATES FORM FAILUNT OF FESS.
- DOMESTIC TAPS 4 INCHES OR GREATER AND ALL FIRE SERVICE LINES TAPS SHALL BE A MINIMUM OF 5 FEET FROM ANY PIPE JOINT.
- 12. FOR JOINTS BETWEEN SANITARY SEWER MANHOLE SECTIONS. "RAM NECK" OR EQUIVALENT SHALL BE USED
- ALL MANHOLE CASTINGS IN PAVED AREAS SHALL BE ADJUSTABLE TYPE. SUBFACE FRATURES SUCH AS MANHOLE COFRES, VALUE BOX COVERS, METER BOX COVERS, SEWER CLEAN-OUTS, AND VENTS SHALL BE RE-ESTABLISHED TO FINISH GRADE.
- 14. ALL SANITARY SEWER MANHOLES GREATER THAN 12 FEET IN DEPTH SHALL BE 60' IN DIAMETER BELOW SIX FEET OF MANHOLE DEPTH. ABOVE SIX FEET OF MANHOLE DEPTH THE MANHOLE DIAMETER SHALL BE 48'.
- LOCATION AND DEPTH OF ALL PUBLIC UTLITIES SHALL BE FIELD VERIFED BY DEVELOPER'S CONTRACTOR WITH A NORFOLK DEPARTMENT OF UTLITIES RESPECTOR PRESENT. CONTRACTOR SHALL CONTACT THE UTLITIES FIELD ENCANERDING OFFICE TELEPHONE 75:453-1010. ATLENATZ TE HOLES PRIOR TO EXCAVATION TO ABRANCE FOR A NORFOLK DEPARTMENT OF UTLITIES INSPECTOR TO BE PRESENT.
- 16. RIGHT-OF-WAY SANITARY SEWER INSTALLATIONS SHALL BE PERFORMED BY THE DEVELOPER'S CONTRACTOR AND INSPECTED BY THE DEPARTMENT OF UTILITIES.
- CONTRACTOR SHALL TAKE THE NECESSARY PRECAUTIONS TO PROTECT EXISTING UTILITIES AND MAINTAIN UNINTERRIPTED SERVICES AT ALL TIMES; ANY DAMAGE TO EXISTING UTILITIES SHALL BE IMMEDIATELY REPARED AT THE CONTRACTORS EXPENSE.
- ANY ACTIVITIES THAT WILL RESULT IN INTERRUPTION OF SERVICE TO ANY CUSTOMER MUST BE COORDINATED WITH THE UTILITIES WATER DISTRIBUTION AT 823-1001 AS TO AN ACCEPTABLE THAE AND DURATION OF INTERRUPTION. SCHEDULED INTERRUPTIONS OF SERVICE REQUESE SWORKING DAYS ADVANCE NOTICE.
- ALL UTILITIES SURFACE FEATURES SUCH AS SEWER MANHOLE COVERS, VALVE BOX COVERS, METER BOX COVERS, AND SEWER CLEANOUT LIDS WITHIN THE PROJECT AREA ARE TO BE REESTABLISHED TO FINISH GRADES.
- 20. EXISTING FIRE HYDRANTS LOCATED IN THE PROJECT AREA SHALL BE VISIBLE AND ACCESSIBLE AT ALL TIMES. AT LEAST 95% STANDARD PROCTOR COMPACTION SHALL BE ACHIEVED FOR THE BACKFILL OF THE OPEN CUTS FOR THE WATER SEWER MAIN TRENCHES.
- DUBING CONSTRUCTION, PROVIDE ADEQUATE PIPE PROTECTION, RESTRAINT, AND SUPPORT BETWEEN PROPOSED UTILITIES AND EXISTING WATER AND SANITARY SEWER MAINS WHIER VERTICAL SEPARATION IS LESS THAN 12 RICHES. CONTRACTOR SHALL SUMMIT DETAIL TO CITY OF NORFOLGY REIOR TO INSTALLATION.
- FOR REQUIRED WATER MAIN SHUTDOWNS, THE CONTRACTOR SHALL COORDINATE IN ADVANCE WITH THE DPRARTMENT OF UTILITIES INSPECTOR. THIS IS TO ENSURE PREREQUISITE REQUIREMENTS AND PRECAUTIONS TAKE PLACE AND ARE SATESFED.
- PARALLEL ELECTRONIC CABLING SHALL NOT BE INSTALLED WITHIN 4 FEET OF EDGE OF RAW WATER AND FINISH WATER TRANSMISSION MAINS
- 25. HAND DIGGING IN VICINITY OF RAW WATER MAINS IS REQUIRED WHEN INSTALLING OTHER CROSSING UTILITIES
- 26. CONTRACTOR SHALL EXERCISE EXTREME CARE WHILE DEMOLISHING EXISTING STREET PAVEMENT AROUND RAW WATER LINES.
- 27. NO MATERIALS SHALL BE STORED WITHIN 15 FEET OF RAW WATER MAINS.
- 28. CONTRACTOR IS REQUIRED TO PROVIDE CITY UTILITY INSPECTOR AS BUILT DRAWINGS. AS BUILT INFORMATION SHALL BE PERFORMED UNDER THE SUPERVISION OF A CITY INSPECTOR.
- 29 WATER SERVICE LINES:
- A WHER MATE SERVICE LINE MUST CROSS OVER STIMES STOOM BRUNC OG GAS UNDS, THE SERVICE IN MUST BE LIAD AT LOCA IN LERANDARY THAT THE DOTTOM OF THE SERVEC IN IS AT LESS TO BETTER 1 IB NOTHER AROUT THE TOP OF THE SERVICE DO COTTER PIPE. THIS VERTICAL SEPARATION MUST BE MANTANED TOOR THAT TOORTION ON THE SERVICE DAWN WITHIN TERS, TERS THE HORZONTALLY OF ANY SERVE LINE ATHAT IT CROSSES, MEASURED AS THE CLEARANCE FROM THE SERVICE LINE TO THE SERVER OR OTHER PIPE. MINIMUM COVER OF 24 NOTES THE DIRCH NAVES HAUL BE MANTANED.
- 8. SHOULD TEMPORAPY WATER SERVICE LINE REMOVAL BECOME NECESSARY DUE TO LAYING OF SERVIES, STORM DRAIN PIPES AND GAS LINES, THE WATER SERVICE LINE SHALL BE REFLACED IN TIS ENTERTY BETWEEN THE CORPORATION STOF AND METER STORY CUTTING AND SPECIFIC WATER SERVICE FOR ENSOLVING UTILITY CONVELCTS IS NOT PREMITTED. WATER SERVICE REFLACEMENT WORK SHALL BE PERFORMED IN THE PRESENCE OF A DEPARTMENT OF UTILITIES THED DECORRESING OFFER SINGHCES.



S.B. BALLARD

2828 SHIPPS CORNER ROAD RGINIA BEACH, VIRGINIA 23453 TELEPHONE: 757.440.5555 FACSIMILE: 757.451.2873

NILES BOLTON ASSOCIATES

ATION WITH : Commonwealth





REVISIO

DATE



EARLY E&S AND STORMWATER PLA 3/30/1 CITY OF NORFOLK

GENERAL NOTES

XXX-XXXXX-X

C1.01



NILES BOLTON

Vhb 👬

THOMPSON

Ľ

ASSOCIATES

Erosion And Sediment Control Notes

Erosion and Sediment Control Notes (VHB)

- PRIOR TO STARTING ANY OTHER WORK ON THE SITE. THE CONTRACTOR SHALL NOTIFY APPROPRIATE AGENCIES AND SHALL INSTALL BEOSION CONTROL MEASURES AS SHOWN ON THE PLANS AND AS IDENTIFIED IN FEDERAL. STATE AND LOCAL APPROVAL DOCUMENTS PRETAINING TO THIS PROJECT. 1.
- CONTRACTOR SHALL INSPECT AND MAINTAIN EROSION CONTROL MEASURES, AND REMOVE SEDMENT THEREFROM ON A WERKIY BASIS AND WITHIN TWELVE HOURS AFTER EACH STORM RYENT AND DEPOSE OF SEDMENTS IN AN UPLAND AREA SUCH THAT THEY DO NOT ENCUMBER OTHER DRAINAGE STRUCTURES AND PROTECTED AREAS.
- CONTRACTOR SHALL PERFORM CONSTRUCTION SEQUENCING SUCH THAT EARTH MATERIALS ARE EXPOSED FOR A MINIMUM OF TIME BEFORE THEY ARE COVERED, SEEDED OR OTHERWISE STABILIZED TO PREVENT EROSION.
- UPON COMPLETION OF CONSTRUCTION AND ESTABLISHMENT OF PERMANENT GROUND COVER, CONTRACTOR SHALL REMOVE AND DISPOSE OF EROSION CONTROL MEASURES AND CLEAN SEDIMENT AND DEBRIS FROM ENTIRE DRAINGE AND SEWER SYSTEMS.
- EROSION CONTROL STRUCTURES SHALL REMAIN IN PLACE UNTIL ALL DISTURBED EARTH HAS BEEN SECURELY STABILZED. AFTER REMOVAL OF STRUCTURES, DISTURBED AREAS SHALL BE REGRADED AND STABILZED AS NECESSARY.
- Minimum Standard Notes
- UNLESS OTHERWISE SPECIFIED, ALL TREES AND SHRUBS WITHIN THE PROJECT LIMITS SHALL BE CLEARED, GRUBBED, AND DISFOSED OF OFFSTIE. VOIDS FROM THEE STUMPS SHALL BE BACKFILLED WITH SELECT MATERIAL OR AS DIBECTED BY THE OWNER OF THERE REPRESENTATIVE.
- ALL SILT FENCING MUST BE INSTALLED OUTSIDE THE CRITICAL ROOT ZONE (CRZ-CROWN SPREAD) TO AVOID ROOT DAMAGE DURING INSTALLATION. 3.
- ALL EXCAVATED MATERIAL SHALL BE STORED USING APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES AND DISPOSED OF IN A LAWFUL MANNER.
- IN COMPLIANCE WITHIN MS-1, PERMANENT OR TEMPORARY SOL STABILIZATION SHALL BE APPLED TO DENUDED AREAS WITHIN SVEN DATS AFTER INAL GRADE IS REACHED ON ANY FORTION OF THE SITE TEMPORARY SOL STABILIZATION STALL BE APPLEED WITHIN SVEN DATS TO DENUDED BAREST THAT MAY ONE FAR FINAL GRADE BUT WILL REMAIN DOBMANT FOR LOCKED THAN 14 DAYS. PERMANENT STABILIZATION SHALL BE APPLED TO AREAS THAT ARE TO BE LEFT DOBMANT FOR MOLET HAN ONE TEAM. 4.
- 5. IN COMPLIANCE WITHIN MS-2, DURING CONSTRUCTION OF THE PROJECT, SOIL STOCKPILES AND BORROW AREAS SHALL BE STABILIZED OR PROTECTED WITH SEDIMENT TRAPPING MEASURES.
- IN COMPLIANCE WITHIN MS-3, A PERMANENT VEGETATIVE COVER SHALL BE ESTABLISHED ON DENUDED AREAS NOT OTHERWISE PERMANENTLY STABILIZED.
- IN COMPLIANCE WITHIN NS-4, SEDMENT BASINS AND TRANS, PERIMETRE DEES, SEDMENT BARBERES AND DIMER MEXISTERS INTENDED TO TRAY SEDMENT SHALL BE CONSTRUCTED AS A PRET STEP N ANY LIAND-DISTURENCE ACTIVITY AND SHALL BE MADE FUNCTIONAL BEFORE UNCOPE LAND DISTURBANCE TRANS FLACE.
- 8. IN COMPILANCE WITHIN MS-5. STABILIZATION MEASURES SHALL BE APPLIED TO EARTHEN STRUCTURES SUCH AS DAMS, DIKES, AND DIVERSIONS IMMEDIATELY AFTER INSTALLATION.
- DIMNS, MEM, ADVIENDOUS BUTLEMOUS BUTLEMOUS THAT'S AND BASINGS SHALL BE DESCRIED AND CONSTRUCTED BASED UPON THE TOTAL DRAINGE AREA TO BE SERVED BY THE TRAP OR BASIN, SEDMENT TRAPS SHALL ONLY CONTROL DRAINGE AREA ISES THAN THERE ACRES WITH A MINIMUM STORAGE CAPACITY OF ISI CUERC VARISS PER ACRE OF DRAINGE AREA. SEDMENT BASINS SHALL ONLY CONTROL DRAINGE AREAS GEATER THAN OR EQUAL TO THERE ACRES WITH A MINIMUM STORAGE CAPACITY OF 154 CUERC YARGE AREA AND THE CONTROL SYSTEM STORAGE CAPACITY OF 154 CUERC YARGE PRACE OF DRAINGE AREAS DUBING A THEORY THE TRANS STORAGE OF ACTION TO 154 CUERC YARGE PRACE OF DRAINGE AREA AND THE CONTROL SYSTEM STORAGE OF ACTION TO 154 CUERC YARGE PRACE OF DRAINGE AREA AND THE CONTROL SYSTEM STORAGE OF ACTION TO 154 CUERC YARGE PRACE OF DRAINGE AREA AND THE CONTROL SYSTEM STORAGE OF ACTION TO 154 CUERC YARGE DRAINGE DUBING A THEORY THE TRANS STORAGE OF ACTION DRAINGER THE STRUCTURAL INTEGENT OF THE BASEN DUBING A THEORY THE TRANS STORAGE OF ACTION DRAINGER.
- IN COMPLIANCE WITH MS-7 AND 8 THE CONTRACTOR SHALL CONSTRUCT SLOPES TO MINIMIZE EROSION AND PROVIDE MEASURES TO PREVENT CONCENTRATED RUNOFF. SLOPES FOUND TO BE ERODING SHALL BE REPAIRED WITH PERMANENT STABILIZATION.
- 11. IN COMPLIANCE WITH MS-9 ADEQUATE DRAINAGE SHALL BE PROVIDED TO PROTECT WATER SEEPS FROM A SLOPE FACE.
- 12. IN COMPLIANCE WITH MS-10 ALL OPERATIONAL STORMWATER INLETS MUST BE PROTECTED
- IN COMPLIANCE WITH MS-11 ADEQUATE OUTLET PROTECTION AND REQUIRED TEMPORARY OR PERMANENT CHANNEL LINING SHALL BE INSTALLED IN BOTH THE CONVEYANCE CHANNEL AND THE RECEIVING CHANNEL BEFORE NEWLY CONSTRUCTED STORMWATER CONVEYANCE CHANNELS OR PIPES ARE MADE OPERATIONAL
- IN COMPLIANCE WITH MS-12, WHEN WORK IN A LIVE WATERCOURSE IS PERFORMED: A. PREAUTIONS SHALL BE TAREN TO MINIMUZE ENCROACHMENT, CONTROL SEDMENT TRANSPORT, AND STRABLZET HE WORK AREA TO THE GRAFTST ETREVENT POSSIBLE DURING, CONSTRUCTION B. NONRODBLE MATERIAL SHALL BE USED DOR THE CONSTRUCTION OF CALSEMARS AND COPERDAMAS C. EARTINE PHIL LAY BE USED FOR THESE STRUCTURES FOR ADMINISTRES FARMORED BY NORRODBLE COVER MATERIALS
- 15. IN COMPLIANCE WITH MS-13 AND MS-14. A TEMPORARY VEHICULAR STREAM CROSSING CONSTRUCTED OF NONRROBRIE MATERIAL SHALL BE PROVIDED IF A UNF WATERCOURSE MIST BE CROSSED BY CONSTRUCTION VEHICLES MORE THAN TWICE IN A SIX-MONTH PERIOD. ALL APPLICABLE FEDERAL STATE AND LOCAL RECULATIONS MIST FE MET.
- 16. IN COMPLIANCE WITH MS-15, WATERCOURSE BEDS AND BANKS SHALL BE STABILIZED IMMEDIATELY AFTER WORK IN THE WATERCOURSE IS COMPLETED
- IN COMPLIANCE WITH Nex. 1, THE CONTRICTOR SHALL A. OPEN NO MORE THAN SHOLE C. OF UTERIT TRENCH AT A TIME B. PLACE EXCLUNTED TERENCH MATERIAL ON HIGH SHE OF THENCH C. TRITES RIFE STULIONT WITH NA APPROVED SUBMONT TRAPPING DEVICE D. BLACKHLI TRENCHS WITH PROPER COMPLATION TO MINIMIZE EBOSION SEED SOD DEVILUEED AREA WITHIN (7) DANS OF REALINICE FRAL CRADE
- 18. IN COMPLIANCE WITH MS-17, WHERE CONSTRUCTION VEHICLE ACCESS ROUTES INTERSECT PAVED OR PUBLIC
- ADS: MINMIZE VEHICULAR SEDIMENT TRACKING ONTO THE PAVED SUBFACE CLEAN THE ROAD SUBFACE THOROUGHLY AT THE ROAD OF FACH DAY SEDIMENT SHALL BE REMOVED BE TSOVENICE OF SWEEPING AND THEN TRANSPORTED TO A SEDIMENT CONTROL DISPOSAL AREA. STREET WASHING SHALL BE ALLOWED ONLY AFTER SEDIMENT IS REMOVED IN THIS MANNEE.
- 19. IN COMPLIANCE WITH MS-18, ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO. LONGER NEEDED, UNLESS OFTERWISKA ATITOIORY TARAPTIOS STUDIESTIC NATO THE DESTURBED SOLI AREAS RESULTING FROM THE DESPOSITION OF TEMPORARY MEASURES SHALL BE PERMANENTLY STABILIZED TO PERSIVE TEMPERE REGISION AND SEDIMENTATION.
- IN COMPLANCE WITH INS-19 PROPERTIES AND WATEWARE DOWNSTREAM FROM DEVELOPMENT SITES SHALL BE PROTECTED FROM STDIMENT DEPOSITION, DESCON AND DAMAGE DIF TO INCERSES IN VOLUME VENOCITY, AND PEAK FLOW EATE OF STORMWATER RUNOFF, CONCENTRATED STORMWATER RUNOFF LEAVING. A DEVELOPMENT STE SHALL BE DEGENARED BIEGENTY INTO AN ADQUITE NATURAL OF MAN-MADE RESERVING CHANNEL, PIPE, OR STORM SEWER SYSTEM
- 21. INLET PROTECTION FOR INLETS SCHEDULED TO BE CAPPED MAY BE REMOVED UPON MODIFICATION OF EXISTING STRUCTURE

Erosion And Sediment Control Narrative

Project Description

THE EXISTING SITE CONSISTS OF APPROXIMATELY 6.10 ACRES LOCATED AT THE NORTHEAST QUADRANT OF THE NSU CAMPUS IN THE CITY OF NORFOLK, VIRGINA. THE BUILDING SITE IS CURRENTLY AN EXISTING GRAVE. PARKING IOT AND FORMERLY NORFOLG CITY HOSTRILA & PORTON OF THE PROJECT SITE IS ENCLIMBERED BY A LEASE LINE FOR THE BENEFIT OF SPARTAN SUITES APARTMENTS. THE PROPOSED PROJECT CONSISTS OF TWO BESIDENCE HALLS (NORTH HALL AND SOUTH HALL) EACH WITH 302 BEDS FOR A TOTAL OF 604 BEDS AND A CENTRAL AMENITY AREA.

THE SITE IS BOUND BY CORPREW AVENUE TO THE NORTH. CAMPUS PARKING LOTS AND MAJESTIC AVENUE THE SHE IS BOUND IN CONFRENCE AVENUE TO THE WORTH CAMPOSITION SHOULD AND MARGINE AVENUE TO THE EAST, PARTANA SUBTER APARTMENTS TO THE SOUTH, AND THE NORTH AS THE UNIVERSITY FOLCE BUILDING. TO THE WEST, THE SUBPOSITIONING LAND COVER IS MOSTLY IMPERVIOUS AND CONSISTS OF BUILDINGS, DEVICE ASLES, CARLES LARKING AREAS AND PEDESTRIAN WALKWAYS.

Existing Site Conditions

THE EXISTING TERRAIN OF THE SITE IS RELATIVELY FLAT WITH SLOPES AROUND 1-2%. SITE FLEVATIONS (BASED ON NAVD88(92)(CITY OF NORFOLK 2000), VERTICAL DATUM) RANGE FROM APPROXIMATELY 12.4 FEET AT THE SOUTH END OF THE SITE TO 15.7 FEET IN THE CENTER OF THE SITE THE SITE GENERALLY DRAINS FROM THE CENTER TO THE PERIMETER OF THE PROPERTY. EXCAVATION AND FILLING OF THE SITE WILL BE NECESSARY FOR THE PROPOSED PROJECT. IMPACTS TO EXISTING TOPOGRAPHY ARE EXPECTED TO FILL TH SITE ON AVERAGE 1-3 FEET.

THE FINISHED FLOOR ELEVATION WILL BE SET AT ELEVATION 15.5 FEET: THEREFORE. THE FINISHED FLOOR IS THE PRINEND FLOOR ELEVATION WILL BE SET AT LEVATION 15.5 FET, THEREFORE, THE FINSHED FLOOR E APPROMANTLY ING (2) FET AGOVE THE AVERAGE STIC GADE DELAVION. SPARTAN SUITS AVAILMENT FINSHED FLOOR IS AT ELEVATION 14.5 FET, THE CLOSE FROMMITY OF SPARTAN SUITS TO THE SOUTH HALL BUILDING WILL BE CONSIDERED WITH THE SITE GRADING DESIGN. THE FOLCE PREINCT FINISHED FLOOR S ALSO AT ELEVATION 14.5 FET AND THE ADJACENT ROADWAY IS AT ELEVATION 12.0 FET.

Adjacent Areas

THE PROJECT IS BOUNDED BY CORPREW AVENUE TO THE NORTH, CAMPUS PARKING LOTS AND MAJESTIC AVENUE TO THE EAST, SPARTAN SUITES APARTMENTS TO THE SOUTH, AND THE NORFOLK STATE UNIVERSIT POLICE BULLIONG TO THE WEST.

Soils

PLEASE REFER TO SHEETS B1.00 AND B1.01 FOR THE SOIL BORING LOG LOCATION PLAN AND BORING LOGS WHICH ARE REFERENCED IN THE "REPORT OF SUBSURFACE EXPLORATION AND GEOTECHNICAL SERVICES" PREPARED BY GET SOLUTIONS, INC. AND DATED MARCH 12, 2018.

Offsite Areas

THERE ARE NO OFFSITE AREAS TO BE DISTURBED WITH THIS PROJECT. IF OFFSITE LAND DISTURBENG ACTIVITY IS FOUND TO BE NECESSARY, IT SHALL BE CONDUCTED UNDER A SEPARATE, APPROVED EROSION AND SEDIMENT CONTROL PLAN.

Critical Erosion Areas

THERE ARE NO CRITICAL EROSION AREAS IDENTIFIED ON THE PROJECT SITE WITH RESPECT TO HIGHLY ERODIBLE SOILS OR STEEP SLOPES.

Erosion and Sediment Control Measures

DUST AND EROSION CONTROL WILL BE CONSIDERED AN INTEGRAL PART OF ALL DESIGN. ALL STRUCTURAL DIST AND EROSION CONTROL WILL BE CONSIDERED AN INTEGRAL PART OF ALL DESIGN ALL STRUCTURAL ADD VEGETATIVE BORSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINAL REGISTON AND SEDIMENT CONTROL HANDBOOK, 1992 THE FOLLOWING EGSISTON AND SUBMENTATION CONTROLS WILL BE EMPLOYED DURING. THE RANTINVOR AND CONSTRUCTION PHASES OF THE PROJECT, BUT ARE NOT ILMITED EMPLOYED DURING. THE ARXIVER, SALD PROFE THE PROTECTION AND SEDIMENT CONSTRUCTION. FILL BASE, SALD PROFE THERE PROTECTION SALD FEED EMPLOYED DURING. THE ARXIVER, SALD PROFE THERE PROTECTION SALD FEED ENDING TO AND ADDRESS AND ADDRESS AND ADDRESS TO ADDRESS AND ADD

SAFETY FENCE (STD. 3.01)

SAFETY FENCE WILL BE INSTALLED AROUND THE SITE PERIMETER TO PREVENT UNWANTED ACCESS TO THE

TEMPORARY CONSTRUCTION ENTRANCE/EXIT (STD. 3.02)

A TEMPORARY CRUSHED-STONE CONSTRUCTION ENTRANCE/EXIT WILL BE CONSTRUCTED. A CROSS SLOPE A IEMPORATI CROSHED-SIDNE CONSTRUCTOR VIEWARDE DATI WIE DE CONSTRUCTED A CROSS SETTION MULL DE PLACED IN THE ENTRANCE TO DRECOT RUNOFF TO A PROTECTED CATCH BASIN INTEL OR SETTION AREA. IF DEEMED NECESSARY AFTER CONSTRUCTION BEGINS, A WASH PAD MAY BE INCLUDED TO WASH OF VEHICLE WHEEDS BERORE LEAVING THE PROJECT STRE

SILT FENCE (STD. 3.05)

SILT FENCE WILL BE PLACED ALONG THE PERIMETER OF THE SITE WHERE OTHER SEDIMENT CONTROL MEASURES ARE NOT IN PLACE (EX. DIVERSION DIRES). THE SILT FENCE WILL BE REPARED OR REPLACED AS DETERMINED BY FERIODIC FELD INSPECTIONS.

STORM DRAIN INLET PROTECTION (STD. 3.07)

NEWLY CONSTRUCTED AND EXISTING STORM DRAIN INLETS WILL BE PROTECTED WITH SEDIMENT FILTERS AND/OR SILT FENCE BARRIERS THROUGHOUT CONSTRUCTION.

TREE PROTECTION (STD. 3.38)

TREE PROTECTION FENCING OR OTHER SUITABLE DEVICES SHALL BE PLACED ALONG THE LIMITS OF CLEARING TO PROTECT DESIRABLE TREES FROM MECHANICAL AND OTHER INJURY DURING LAND DISTURBING AND CONSTRUCTION ACTIVITY.

VEGETATIVE PRACTICES

TOPSOIL SHALL BE STRIPPED FROM AREAS TO BE GRADED AND STOCKPILED FOR LATER USE. CONTACTOR SHALL STOCKPILE TOPSOIL IN AN APPROPRIATE MANNER IF NO LOCATION IS INDICATE THE SITE PLANS. SUIF FINCE SHALL BE PLACED ALONG THE PERMITER OF THE STOCKPILE. ION IS INDICATED ON

ALL DISTURBED AREAS SHALL BE SEEDED WITH FAST-GERMINATING. TEMPORARY VEGETATION IMMEDIATEL ALL DISTORED AREAS SHALL BE SELECT WITH FAST-GRANIKATING, TRATORAM YEARATION IMMUNICAT FOLLOWING CARNING OR WHERE EXPOSED SOIL SUFFACES WILL NOT BENOCHTT OF NALL CRADE FOR A PERIOD OF TIME EXCEEDING IS DATS. SELECTION OF THE APPROPRIATE SEED MITTURE AS RECOMMENDED BY THE VIECUNA RESIGNON AND SEMENTIC ONTROL HANDBOOK, 1982 WILL DEPEND ON THE THE THE OF FERE IT IS TO BE APPLIED. ESTABLISHMENT OF TEMPORARY VEGETATIVE COVER MAY BE ESTABLISHED BY UNDED ACTEMPT

VEGETATIVE SLOPE STABILIZATION WILL BE USED TO MINIMIZE EROSION ON SLOPES OF 3:1 OR FLATTER. EROSION CONTROL MATTING SHALL BE USED ON SLOPES STEEPED THAN \$-1

PERMANENT STABILIZATION WILL BE COMPLETED WITH THE PLANTING OF PERENNAL GRASSES OR LEGUMES, ESTABLISHMENT OF FERMANENT VEGETATIVE COVER MAY BE ESTABLISHED BY HYDRO SEDDING. OR SODDING, A SUITABLE TOPSOL GOOD SEEDBED PERPARATION, AND ADEQUATE ILME, FERTILIZE AND WATER SHALL BE PROVIDED FOR EFFECTIVE ESTABLISHMENT OF THESE VEGETATIVE STABILIZATION METHOLS, STABA MULCH SHALL BE USED AFTER PERMANENT SEDDING TO PROTECT SOL DURING. SEED

Stormwater Management:

IN THE EXISTING CONDITION, MUCH OF THE SITE DRAINS VIA OVERLAND FLOW TO A CLOSED STORM DRAINAGE SYSTEM ON THE SOUTH END OF THE SITE, WHICH ULTIMATELY DISCHARCES TO THE EAST. THROUGH THE CAMPUS STOREM DRAINAGE SYSTEM. THE ERAINADRE OF THE SITE DRAINS TOWARDS CORPERN AVENUE. THE PROPOSED DEVELOPMENT WILL DECREASE THE IMPROVIDUS AREA OF THE SITE BY MORE THAN 20% AND WILL DECREASE THE AMOUNT OF RUNOFF FLOWING OVERLAND ONTO CORPERN AVENUE.

AVENUL STORMWATER WILL BE REVIEWED FOR BOTH WATER QUANTITY (9VAC25-870-66) AND WATER QUALITY (9VAC25-870-63). WATER QUANTITY WILL BE ADDRESSED FOR CHANNEL PROTECTION CHANNEL PROTECTION CHANNEL PROTECTION WILL BE ADDRESSED FOR VANALYING (HI & 2/PAR STORM SYSTEM FOR PROTECTION. CHANNEL PROTECTION WILL BE ADDRESSED FOR CHANNEL PROTECTION. PRUTE-LION. CHANNEL PROTECTION WILL BE ADDRESSED BY ANALYZING THE 2-YEAR STORM SYSTEM FOR BOSION WHILE FLOOP PROTECTION BE ADDRESSED BY ANALYZING THE 10-YEAR STORM FOR CAPACITY AND FLOODING. WATER QUALITY WILL BE ADDRESSED VIA THE VIRGINIA RUNOFF REDUCTION METHOD FOR REDVELOPMENT STIPS PUANCE IS ACHIEVED BY REDUCING THE IMPERVIOUS COVER OF THE SITE BY ADDING

WATE QUALITY COMPLIANCE IS ACHIEVED BY REDUCING THE IMPERVIOUS COVER OF THE STF BY ADDING. LIAWN AND LANDSCAPING, REAS AROUND THE NOW RESIDENCE HALLS. THE REDUCTION OF IMPERVIOUS COVER ALSO REDUCES THE NET RUNNOF FROM THE SITE BELOW THE EXISTING CONDITION. THE TWO DISCHARGE FORMS IN TO THE SOUTH OF THE SITE BELOW THE EXISTING CONDITION. THE TWO DISCHARGE FORMS IN TO THE SOUTH OF THE SITE BELOW THE EXISTING CONDITION. THE TWO MANDADE CONCERTE CULVEREST THAT DO NOT DAVILIENT TO A NATURAL CHANNEL UNIT. THE CAMPUSS STORM SERVER SYSTEM ULTIMATELY DISCHARGES TO OHIO CREEK (A WATEBENHED OF OVER 280 ACRES). BECAUSE THE NOT HOW FROM THE SITE S REDUCING FOR THE POST-DIVEDPED CONDITION, THE STROLE WILL NOT RESULT IN AN INCREASE IN FLOW AT THE OUTFALL TO OHIO CREEK THEREFORE, THERE IS NO RISK OF CHANNEL EGOSION.

B. BALLARD CONSTRUCTION COMPANY OMMONWEALTH ARCHITECTS ILES BOLTON ASSOCIATES SPEIGHT MARSHALL FRANCIS THOMPSON CONSULTING ENGINEERS

NOROLK STATE UNIVERSITY

AL FACILITY UNIVERSITY 13-17818-000 RESIDENTIAL I FOLK STATE UN #21



CODE:

PROJECT



XXX-XXXXX-X EARLY E&S AND STORMWATER PLA 3/30/1

C1.02

EROSION & SEDIMENT CONTROL NOTES AND NARRATIVE

Copyright O 2018 COMM

TRUE PROJECT










S.B. BALLARD





SB. BALLARD VECNA FACH. VECNA 2453 TELEPHONE 757.40.555 FACSMET 757.40

S IVRINA L. GA

REVISION

XXX-XXXXX-XX EARLY E&S AND STORMWATER PLAN 3/30/18

C6.00

UTILITY PLAN

inter 🔿 2011

DATE



SPORAL MERCI vhb THOMPSON Consulting Engineers

COMMONWEALTH ARCHITECTS ARCHITECT OF BECORD NILES BOLTON ASSOCIATES ARCHIECT OF DESIGN SPEIGHT MARSHALL FRANCIS THOMPSON CONSULTING ENGINEERS

NEW RESIDENTIAL FACILITY NORFOLK STATE UNIVERSITY PROJECT CODE: #213-17818-000







UTILITY PLAN

C6.01

er Structure Schedule Storm Sewer Structure Schedule

Structure	Schedule	Sto]

Storm Sewer

Number

A1 A2 A3

A4 A5 A6 A7

A8 A9 A10

A11 A12

A13 A14

A15

A16 A17

B1

82 B3 SDC0 45

Storm Sewer Pipe Schedule

Start Str. End Str. Size Material Length Slope Start Inv. End Inv.

Туре	Top	Height	Numb
SDC0	15.18	3.05	STM-10
SDC0	15.49	2.91	STM-10
45	15.47	3.03	STM-10

15.38 15.25

14.78

14.60 4.52

17.66 3.35 5.08

14.12 5.49

11.73 2.04

16.41 7.58 13.96 5.99

 204
 3.29

 13.75
 3.50

 11.33
 2.42

 10.86
 4.54

 13.15
 3.92

 13.77
 5.28

3.50 3.78

3.91 4.43 14.80

3.29

Storm Sewer Pipe Schedule

Start Str. End Str. Size Material Length Slope Start Inv. End Inv.

Top	Height	Number

Height	Number	Ty

Height	Number	

_			
	Height	Number	

Height	Number	

Гор	Height	Number	

op	Height	Numb	er

Height	Number	1

edule	Storm	Storm Sewer S		

84 85 86 87 88 89 810 811

B12 EX-1

EX-2

EX-3

EX-112

EX-115

STM-104

EX-4

STM-100 STM-101

STM-102 STM-103

Type
 Type
 Top
 Height

 S000
 15.50
 1.91

 45
 15.49
 2.24

 S000
 15.40
 2.42

 S000
 15.40
 2.42

 S000
 15.40
 2.42

 S000
 15.40
 2.85

 S000
 15.41
 1.86

 S000
 15.21
 1.26

 S000
 15.40
 2.89

 S000
 15.41
 3.38

 S000
 15.43
 3.33

 S000
 15.40
 3.60

 S000
 15.40
 3.00

 S000
 15.40
 3.33

 S000
 15.40
 3.30

 S000
 15.40
 3.60

 S000
 15.20
 3.00

 S000
 15.20
 3.27

 S000
 15.36
 2.42

 S000
 15.36
 2.42

 S000
 15.36
 2.42

 S000
 15.36
 2.42

 S000
 15.38
 2. SDC0 45

.

SDC0 SDC0 SDC0

SDC0

45

SDC0 Existing Combination Inlet Existing Combination Inlet

Existing Combination Inlet

Existing YDI

Existing MH

es-1 Ydi

YDI ES-1

SDMH TOP

Sanitary Sewer Structure Schedule Height Number Туре 3.52 4.17 4.32 SS-1 SS-2

SS-3

SS-4

SS-9

SS-10

SS-8

Top Height 6.39 9.70 5.38 EX SS 14.00 SSMH 17.75 SSMH CS_09 14.32 5.17 CS_09 14.47
 SS-5
 6" STUB

 SS-6
 SSMH

 SS-7
 CS_09
 SS-5 5.83 5.74

4" STUB

6" STUB

6" STUB

S. B. BALLARD CONSTRUCTION COMPANY VHB CIVIL ENGINEER

NOROLK STATE UNIVERSITY OWNER

JECT TEAM

Sanitary Sewer Pipe Schedule

Start Str. End Str. Size Material Length Slope Start Inv. End Inv
 SS-2
 SS-1
 6
 PVC
 65,442
 0.665
 8.05
 7.61

 SS-3
 SS-2
 6
 PVC
 130.893
 0.665
 8.94
 8.05

 SS-4
 SS-3
 6
 PVC
 52.682
 0.665
 9.30
 8.94

 SS-4
 SS-3
 6
 PVC
 15262
 0.685
 9.30
 8.94

 SS-5
 SS-4
 6
 PVC
 14.986
 0.685
 9.40
 9.30

 SS-5
 SS-3
 6
 PVC
 30.723
 0.685
 9.40
 9.30

 SS-6
 SS-3
 6
 PVC
 30.723
 0.685
 9.40
 9.30

 SS-7
 SS-6
 4
 PVC
 20.505
 1.045
 9.46
 9.25

 SS-8
 SS-7
 4
 PVC
 11.486
 1.045
 9.56
 9.46

 SS-8
 SS-6
 6
 PVC
 71.746
 0.687
 11.00
 10.46

 SS-10
 SS-2
 6
 PVC
 21.220
 0.683
 11.50
 11.36

 Start Str.
 End Str.
 Size
 Material
 Length
 Slope
 Start Inv.
 End Inv.

 B7
 B8
 10
 PvC
 25
 1.23t
 11.43
 11.57

 B8
 B9
 10
 PvC
 39
 1.23t
 11.47
 10.99

 B9
 B9
 100
 PvC
 26
 1.23t
 11.67
 10.99

 B1
 D1
 PvC
 22
 1.23t
 10.89
 10.45

 B10
 B1
 D1
 PvC
 22
 1.23t
 10.08
 8.07

 B11
 S1M-103
 10
 PvC
 22
 1.23t
 10.08
 8.07

 B12
 B7
 8
 PvC
 28
 1.67t
 12.51
 10.05

 Dr.-1
 ErC-3
 24
 RCP
 88
 0.41t
 8.99
 6.63

 Dr.-1
 ErC-3
 24
 RCP
 100
 0.50t
 8.63
 8.03

 SIM-101
 SIM-101
 2.6P
 7
 0.63t

 Start Str.
 End Str.
 Size
 Material
 Length
 Slope
 Start Inv.
 End Inv.

 A1
 A2
 6
 PrC
 7
 1658
 13.59
 13.46

 A2
 A3
 6
 PrC
 24
 1.858
 13.49
 13.06

 A3
 A5
 6
 PrC
 24
 1.685
 13.48
 13.06

 A3
 A5
 6
 PrC
 22
 1.858
 12.48
 12.25

 A4
 A3
 6
 RPC
 22
 2.585
 13.64
 13.08

 A5
 S19-106
 6
 RPC
 22
 1.585
 12.44
 12.05

 A6
 A7
 10
 PrC
 26
 0.645
 13.25
 13.10

 A7
 A8
 10
 PrC
 36
 0.6505
 12.74
 12.81

 A8
 A9
 10
 PrC
 36.6505
 12.74
 12.81

 A10
 10
 PrC
 36.6505
 12.74
 12.55

Type

YDI Di-1 Di-1

 SIM-10//
 UII-1
 14.75

 STM-108
 DMH
 15.30

 STM-109
 YDI
 13.93

 STM-110
 VOOT DI-1
 11.55

 STM-111
 VOOT DI-1
 11.32

 STM-113
 YDI
 13.36

 STM-114
 YDI
 12.57

STM-106

STM-107

Top

11.50 13.15 14.75

4.05 3.87 5.39 5.67 7.26 5.08

REVISION

xxx-xxxxx-xx

Notes PLANIMETRICS AND UTILITIES OUTSIDE SURVEY LIMITS BASED ON AS-BUILTS, OS, AND NORFOLK STATE UNIVERSITY RECORDS COMPILED FOR COORDINATION PURPOSES.

0 15 30 60 Feet

TRUE PROJECT opyright O 2018





C7.00 vright 🖸 2018

xxx-xxxxx-x

3/30/1

EARLY E&S AND STORMWATER PL4

S.B. BALLARD

ION WITH :

vhb

SPECER PARENA FRANC





















S.B. BALLARD OMPANY 2828 SHIPPS CORNER ROAD VIRGINIA BEACH. VIRGINIA 23453 TELEPHONE: 757 440 5555 FACSIMILE: 757.451.2873 IATION WITH : Commonwealth

NILES BOLTON

Vhb 🏭

THOMPSON

S. B. BALLARD CONSTRUCTION CO

COMMONWEALTH ARCHITECTS

NILES BOLTON ASSOCIATES ARCHIECT OF DESIGN

SPEIGHT.MARSHALL FRANCIS SECTURAL ENGINEER

NOROLK STATE UNIVERSITY

THOMPSON CONSULTING ENGINEERS

PROJECT CODE: #213-17818-000

ASSOCIATES



Legend APPROXIMATE LOCATION OF SOIL TEST BORING

TRUE PROJECT

Copyright 2018 COMMONWEALTH ARCHITECTS

B1.01



12

Depth (ft)

Sample Type(s):

55 - Split Spoor



S.B. BALLARD OMPANY CMPANY 2828 SHIPPS CORNER ROAD VIRGINIA BEACH, VIRGINIA 23453 TELEPHONE: 757.440.5555 FACSIMILE: 757.451.2873 CIATION WITH : Commonwealth-

NILES BOLTON

Vhb 🏭

MTHOMPSON Constant

CT TEAM

VHB

S. B. BALLARD CONSTRUCTION COM

COMMONWEALTH ARCHITECTS ARCHITECT OF RECORD

NILES BOLTON ASSOCIATES ABCHIECT OF DESCN

SPEIGHT.MARSHALL FRANCIS SECTURAL ENGINEER

THOMPSON CONSULTING ENGINEERS NOROLK STATE UNIVERSITY

ASSOCIATES

BORING ID 18B-05

PAGE 2 OF 2





xxx-xxxxx-EARLY E&S AND STORMWATER PLA 3/30/1

BORING LOGS

TRUE PROJECT

Legend APPROXIMATE LOCATION OF SOIL TEST BORING

B1.02 Copyright () 2018 COMMONWEALTH ARCHITECTS



B. BAILARD CONSTRUCTION C

COMMONWEALTH ARCHITECTS

NILES BOLTON ASSOCIATES ABCHERCT OF DESIGN

SPEIGHT.MARSHALL FRANCIS SECTURAL ENGINEER THOMPSON CONSULTING ENGINEER

NOROLK STATE UNIVERSITY

S.B. BALLARD MPANY 2828 SHIPPS CORNER ROAD VIRGINIA BEACH, VIRGINIA 23453 TELEPHONE: 757.440.5555 FACSIMILE: 757.451.2873 CIATION WITH :

General Notes

THE EXISTING CONDITIONS SHOWN ON THIS PLAN ARE BASED UPON AN ACTUAL ON-THE-GROUND INSTRUMENT SURVEY PERFORMED BY VHB IN FEBRUARY 2018.

2. THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES SHOWN ON THIS PLAN ARE BASED ON FIELD OBSERVATIONS, DESIGNATIONS MARKED BY OTHERS AND INFORMATION OF RECORD. THEY ARE NOT WARRANTED TO BE EXACTLY LOCATED NOR ISIT WARRANTED THAT ALL UNDERGROUND UTILITIES OR OTHER STRUCTURES ARE SHOWN ON THIS FLAN.

MERIDIAN SOURCE: VIRGINIA STATE PLANE COORDINATE SYSTEM SOUTH ZONE (NAD 83/93) AND ARE BASED ON CITY OF NORFOLK CONTROL MONUMENTS LR16, A307, GPS118 AND GPS026

ELEVATIONS SHOWN HEREON ARE IN FEET AND ARE BASED ON NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVO88)(92)(CITY OF NORFOLK 2000) AND ARE BASED ON CITY OF NORFOLK CONTROL MONUMENT NO. A307.

5. ALL UTILITY INVERTS SHOWN ARE DEPICTED ACCORDING TO RECORD AND NOT FIELD VERIFIED.

6. THIS EXISTING CONDITIONS TOPOGRAPHIC SURVEY WAS COMPLETED UNDER THE DIRECT AND RESPONSIBLE CHARGE OF DAVID W. ANDREA FROM AN ACTUAL I_ GCUND. OR I_ ARBORNE SURVEY MADE UNDER WY SUFFEXISION; THAT THE UNACERY AND/OR ORIGNAL DATA WAS OBTAINED ON FEBRUARY 20-26, 2018; AND THAT THIS FLAT WHO PO BIGTIAL GEOSPATILE DATA INCLUDING WETADATA MEETS MINIMUM ACCURACY STANDARDS UNLESS OTHERWISE NOTED.

THIS PROPERTY IS IN FLOOD ZONE X (AREAS OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN) AS INDICATED ON THE FLOOD INSURANCE RATE MAP FOR THE CITY OF NORFOLK, VIRGNIA HAVING COMMUNITY PANEL NUMBER 510104 0057H, DATED FEBRUARY 17, 2018.

Ab	hrow	intro	anc
Δv		aur	JUS

ACCESSABLE CURB RAMP CHERRY TREE CRAPE MYRILE TREE DEPICTED ACCORDING TO RECORD INSTRUMENT TREE (UNKNOWN SPECIES)

ACR CHY CM DATR INST TR

Ι	Legend		
O IRF	IRON ROD FOUND	•	BOLLARD
O IRS	IRON ROD SET		STREET SIGN
DHS	DRILL HOLE SET	õ	MONITORING WELL
O NLS	NAIL SET	۲	BORING LOCATION
•	PROPERTY ANGLE POINT		TEST PIT LOCATION
Φ	STORM SEWER MANHOLE	0	WELL
CDI	CURB DRAIN INLET (CDI)		EDGE OF PAVEMENT
	DRAIN INLET (YDI)		CONCRETE CURB
•	FLARED END SECTION		CONCRETE CURB & GUTTER
S	SANITARY SEWER MANHOLE		GUARD RAIL
0	SEWER CLEANOUT	<u> </u>	CHAIN LINK FENCE
e	ELECTRIC MANHOLE		STORM SEWER LINE
Ū	TELEPHONE MANHOLE		SANITARY SEWER LINE
۲	WATER MANHOLE		OVERHEAD WIRE
0	MANHOLE	E	UNDERGROUND ELECTRIC
۲	WATER VALVE	——-T—	TELEPHONE LINE
۰	FIRE HYDRANT	-CATV	CABLE TV
M.	WATER METER	G	GAS LINE
**	SIAMESE CONNECTION	w	WATER LINE
PIV	POST INDICATOR VALVE (PIV)	000000	STONE WALL
്ല	GAS VALVE		HEDGEROW
623	GAS METER		50-FT RMA LINE
E	ELECTRIC BOX		100-FT RPA LINE
	ELECTRIC METER		100-FT BUFFER ZONE
	HH – HANDHOLE	MLW · · · ·	LIMIT MEAN LOW WATER
□ TPED	TELEPHONE PEDESTAL	BF1-100	LIMIT OF BANK
DCATV	CABLE TV BOX	wF1-100	VEGETATED WETLAND BOUND
8	TRAFFIC SIGNAL		
s	SIGNAL BOX	2	MINOR CONTOUR
I	TRANSFORMER PAD		MAJOR CONTOUR
0	LIGHT PULE UN CONC BASE		CONC. PAVEMENT
. ~	UTILITY POLE	101 1210H	RIP RAP
Ģ—⇔	UTILITY POLE W/LIGHT		HANDICAP WARNING STRIP
_	GUY WIRE	112	
PD	PEDESTRIAN PEDESTAL	KIIIII	BUILDING W/OVERHANG
			-



NEW RESIDENTIAL FACILITY NORFOLK STATE UNIVERSITY PROJECT CODE: #213-17818-000



Copyright O 2011

TRUE PROJECT

Sv-1

0 15 30 60 Feet



Appendix L Amendment Log



SWPPP Amendment Log

Instructions: Include additions of new BMPs, replacement of failed BMPs, significant changes in the activities or the timing of the project, changes in personnel, changes in inspection and maintenance procedures, and updates to site maps, etc.

Date Changed	Concern	Actions Taken	Completed By	Signature

BURE	CITY AU OF E		RFOLK	ICES		
Erosion	and Sedi	ment Contro	Inspection	Report		
700 Park Ave						
Address: 700 Park Ave.				CGP: No	#:	_
Inspection Date: <u>7/28/17</u> Inspection Time: <u>1118</u> am	Stage of Co Utility W/	onstruction: ork Demo	Pre-Con _*Bldg Const.	Clearing F. Grading	Rough F. Stabi	Grading lization
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance G	1					
Inlet Protection (P)	1					
Outlet Protection						×
Silt Fence 🕼	1		x			
Sediment Trap/Basin (5)						x
Soil Stabilization (33)	1					
Soil Stockpile Stabilization 🐵	1					
Tree Protection 👘						×
Dewatering Structure						×
Concrete Washout						
Hay Bales	1					x
The inspection reveals that de The following actions are req V CE IP SF SPS Hay Bales "Installed Correctly - Maintain un	eficiencie uired to c	s are present correct the de	in the above ficiencies:	e categories.		_
indiana a contractory indiana and	in ourround	ing area to blac	meou			
SF - Install SF IMMEDIATELY						
SF - Install SF IMMEDIATELY **NW of site						
SF - Install SF IMMEDIATELY **NW of site						_
SF - Install SF IMMEDIATELY **NW of site						
SF - Install SF IMMEDIATELY **NW of site						
SF - Install SF IMMEDIATELY **NW of site						
SF - Install SF IMMEDIATELY **NW of site Targeted Re-inspection Date / Co	mpliance	Time: _7_ cal	lendar days fr	om the receip	ot of this n	otice.
SF - Install SF IMMEDIATELY **NW of site Targeted Re-inspection Date / Co Reported to Nef Lopez	ompliance	Time: <u>7</u> cal	endar days fr	om the receip	ot of this n	otice.
SF - Install SF IMMEDIATELY **NW of site Targeted Re-inspection Date / Co Reported to Nef Lopez A. Print Name	mpilance	Time: _7_ cal	endar days fr	om the receip ay D. Coley Print Name	ot of this n	otice.
SF - Install SF IMMEDIATELY **NW of site Targeted Re-inspection Date / Co Reported to Nef Lopez Print Name Additional Signature Signature	mpliance	Time: _7_ cal	endar days fro pector: JaonTra	om the receip ay D. Coley Print Name	ot of this n	otice.
SF - Install SF IMMEDIATELY **NW of site Targeted Re-inspection Date / Co Reported to Nef Lopez Print Name Signature Signature	ompliance	Time: 7_ cal	endar days fro	om the receip ay D. Coley Print Name Signature	ot of this n	otice.

Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>8/3/17</u> Inspection Time: <u>1100</u> am	Stage of Co Utility Wo	tage of Construction:Pre-Con Utility Work DemoBldg Const.		Clearing ▲F. Grading	Rough Gradin F. Stabilization	
E & S Control Practices	Effective	Effective	Not Installed	Violation	Remove	N/A
Construction Entrance	1					
nlet Protection (P)	1					
Dutlet Protection @						x
ilt Fence 🕼	1		×			
ediment Trap/Basin 🗊						×
oll Stabilization 💿	1		×			
oil Stockpile Stabilization 🐵	1					
ree Protection 💮						x
Newatering Structure 🛛 🔞						x
oncrete Washout 😡						x
Hay bales	1		×			
rash/Debris on Site: <u>No</u> ediment Leaving Site: <u>Yes</u> <u>(</u> 'he inspection reveals that d 'he following actions are red	Continue swe eficiencies quired to c	eping daily s are present orrect the de	in the above	e categories		_
rash/Debris on Site: <u>No</u> ediment Leaving Site: <u>Yes</u> <u>C</u> The inspection reveals that d The following actions are req ✓ CE IP SF SPS Hay bales	Continue swe eficiencies juired to c	eping daily s are present orrect the de	in the above eficiencies:	e categories.		_
rash/Debris on Site: <u>No</u> ediment Leaving Site: <u>Yes</u> <u>(</u> The inspection reveals that d The following actions are req V CE IP SF SPS Hay bales "Installed Correctly - Maintain un	Continue swe eficiencies guired to continue to continu	eping daily s are present orrect the de ing area is stal	in the above eficiencies:	e categories.		_
rash/Debris on Site: <u>No</u> ediment Leaving Site: <u>Yes</u> <u>C</u> he inspection reveals that d he following actions are red V CE IP SF SPS Hay bales "Installed Correctly - Maintain un V silt fence installed NW of site	Continue swe eficiencie: guired to c	eping daily s are present orrect the de ing area is stat	in the above ficiencies:	e categories		_
rash/Debris on Site: No ediment Leaving Site: Yes he inspection reveals that d he following actions are red V CE IP SF SPS Hay bales "Installed Correctly - Maintain un V sitt fence installed NW of site SF - Install SF South of site IMME	Continue swe eficiencies guired to c ntil surround	eping daily s are present orrect the de ing area is stat	in the above eficiencies: bilized k pavers	e categories.		
rash/Debris on Site: <u>No</u> ediment Leaving Site: <u>Yes</u> <u>C</u> he inspection reveals that d he following actions are red V CE IP SF SPS Hay bales "Installed Correctly - Maintain un V silt fence installed NW of site SF - Install SF South of site IMME Hay Bales - add more hay bales	Continue swe eficiencies quired to contil surround EDIATELY a to stabilize l	eping daily s are present orrect the de ing area is stal ifter laying bric bare soils SE c	in the above eficiencies: bilized k pavers of site	e categories.		
rash/Debris on Site: <u>No</u> ediment Leaving Site: <u>Yes</u> <u>C</u> The inspection reveals that d The following actions are red ✓ CE IP SF SPS Hay bales "Installed Correctly - Maintain un ✓ silt fence installed NW of site SF - Install SF South of site IMME Hay Bales - add more hay bales -OR-	Continue swe eficiencies quired to contil surround EDIATELY a to stabilize l	eping daily s are present orrect the de ing area is stat ifter laying bric bare soils SE o	in the above eficiencies: bilized k pavers if site	e categories.		
rash/Debris on Site: <u>No</u> ediment Leaving Site: <u>Yes</u> <u>C</u> The inspection reveals that d the following actions are req ✓ CE IP SF SPS Hay bales "Installed Correctly - Maintain un ✓ silt fence installed NW of site SF - Install SF South of site IMME Hay Bales - add more hay bales -OR- SS - Stabilize bare soils with sod	Continue swe eficiencies quired to contil surround EDIATELY a to stabilize l	eping daily s are present orrect the de ing area is stat ifter laying bric bare soils SE o	in the above eficiencies: pilized k pavers if site	e categories.		
Trash/Debris on Site: No Sediment Leaving Site: Yes The inspection reveals that d The following actions are red ✓ CE IP SF SPS Hay bales **Installed Correctly - Maintain un ✓ sitt fence installed NW of site SF - Install SF South of site IMME Hay Bales - add more hay bales -OR- SS - Stabilize bare soils with sod	Continue swe eficiencies quired to contil surround EDIATELY a to stabilize l	eping daily s are present orrect the de ing area is stat ifter laying bric bare soils SE o	in the above eficiencies: pilized k pavers of site	e categories		
rash/Debris on Site: No ediment Leaving Site: Yes The inspection reveals that d The following actions are req ✓ CE IP SF SPS Hay bales **Installed Correctly - Maintain un ✓ silt fence installed NW of site SF - Install SF South of site IMME Hay Bales - add more hay bales -OR- SS - Stabilize bare soils with sod	Continue swe eficiencies juired to contil surround EDIATELY a to stabilize i	eping daily s are present orrect the de ing area is stat ifter laying bric bare soils SE o	in the above eficiencies: pilized k pavers if site	e categories.		
rash/Debris on Site: No ediment Leaving Site: Yes the inspection reveals that d the following actions are req CE IP SF SPS Hay bales "Installed Correctly - Maintain un sitt fence installed NW of site SF - Install SF South of site IMME Hay Bales - add more hay bales -OR- SS - Stabilize bare soils with sod	Continue swe eficiencies quired to contil surround EDIATELY a to stabilize l	eping daily s are present orrect the de ing area is stat ifter laying bric bare soils SE o	in the above eficiencies: pilized k pavers if site	e categories		
rash/Debris on Site: No ediment Leaving Site: Yes he inspection reveals that d he following actions are red V CE IP SF SPS Hay bales "Installed Correctly - Maintain un V sitt fence installed NW of site SF - Install SF South of site IMME Hay Bales - add more hay bales OR- SS - Stabilize bare soils with sod	Continue swe eficiencies quired to contil surround EDIATELY a to stabilize l	eping daily s are present orrect the de ing area is stal ifter laying bric bare soils SE o	in the above eficiencies: bilized k pavers if site	e categories.	pt of this n	otice.
rash/Debris on Site: No ediment Leaving Site: Yes he inspection reveals that d he following actions are req V CE IP SF SPS Hay bales "Installed Correctly - Maintain un V silt fence installed NW of site SF - Install SF South of site IMME Hay Bales - add more hay bales OR- SS - Stabilize bare soils with sod	Continue swe eficiencies quired to contil surround EDIATELY a to stabilize l	eping daily s are present orrect the de ing area is stat ifter laying bric bare soils SE o Time: <u>5</u> ca	in the above eficiencies: pilized k pavers if site	e categories.	pt of this n	otice.
rash/Debris on Site: No ediment Leaving Site: Yes the inspection reveals that d he following actions are req V CE IP SF SPS Hay bales "Installed Correctly - Maintain un V silt fence installed NW of site SF - Install SF South of site IMME Hay Bales - add more hay bales OR- SS - Stabilize bare soils with sod	Continue swe eficiencies quired to contil surround EDIATELY a to stabilize i	eping daily s are present orrect the de ing area is stal ifter laying bric bare soils SE o Time: <u>5</u> ca	in the above eficiencies: bilized k pavers if site	e categories.	pt of this n	otice.
rash/Debris on Site: No ediment Leaving Site: Yes The inspection reveals that d the following actions are req V CE IP SF SPS Hay bales "Installed Correctly - Maintain un V silt fence installed NW of site SF - Install SF South of site IMME Hay Bales - add more hay bales -OR- SS - Stabilize bare soils with sod argeted Re-inspection Date / C eported to; Nef Lopez With There are a source of the second sec	Continue swe eficiencies juired to contil surround EDIATELY a to stabilize l Compliance	eping daily s are present orrect the de ing area is stat ifter laying bric bare soils SE o Time: <u>5</u> ca	in the above eficiencies: bilized k pavers of site	e categories. om the receip ay D. Coley Print Name	pt of this n	otice.
rash/Debris on Site: No ediment Leaving Site: Yes The inspection reveals that d the following actions are req ✓ CE IP SF SPS Hay bales **Installed Correctly - Maintain un ✓ silt fence installed NW of site SF - Install SF South of site IMME Hay Bales - add more hay bales -OR- SS - Stabilize bare soils with sod argeted Re-inspection Date / C eported to: Nef Lopez Add Add Signature	Continue swe eficiencies quired to contil surround EDIATELY a to stabilize i	eping daily s are present orrect the de ing area is stal ifter laying bric bare soils SE of Time: <u>5</u> ca	in the above eficiencies: oilized k pavers of site	e categories.	pt of this n	

Project Name: Not Brown Hall						
Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>8/9/17</u> Inspection Time: <u>10:35</u> am E & S Control Practices	Stage of Construction:Pre-Con Utility Work DemoBldg Const. Installed Installed Not Effective Effective Not Installed		Clearing F. Grading Violation	Rough Gradin F. Stabilizatio Remove N/A		
Construction Entrance (E)	1					
Inlet Protection	1	x	x			
Outlet Protection @				-		x
Silt Fence SF	1					
Sediment Trap/Basin (57)						X
Soil Stabilization (33)	1					
Soil Stockpile Stabilization 🐵		X				
Tree Protection 🔞						x
Dewatering Structure						x
Concrete Washout 👦		2				x
The inspection reveals that d	ficioncio	eping daily	t in the show	catogorios		_
The inspection reveals that de The following actions are req V CE IP SF **Installed Correctly - Maintain un	eficiencie uired to c	s are present correct the de	t in the above eficiencies:	e categories		_
The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un	eficiencies uired to c	eping daily s are present correct the de ling area is sta	t in the above eficiencies: bilized	e categories		_
The inspection reveals that de The following actions are req V CE IP SF **Installed Correctly - Maintain un IP - Install IP IMMEDIATELY **IP missing W of site	eficiencie uired to c	s are present correct the de	t in the above eficiencies: bilized	e categories		
The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Install IP IMMEDIATELY **IP missing W of site IP - Beinstall IP within 24 hours	eficiencie: uired to c	eping daily s are present correct the de ling area is sta	t in the above eficiencies: bilized	e categories		
The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Install IP IMMEDIATELY **IP missing W of site IP - Reinstall IP within 24 hours **Drop inlet protection, fabric need	eficiencie: uired to c til surround	eping daily s are present correct the de ling area is sta	t in the above eficiencies: bilized	e categories		
The inspection reveals that de The following actions are req V CE IP SF **Installed Correctly - Maintain un IP - Install IP IMMEDIATELY **IP missing W of site IP - Reinstall IP within 24 hours **Drop inlet protection, fabric need SPS - Install SPS within 24 hours	eficiencie uired to c til surround	eping daily s are present correct the de ling area is sta	t in the above eficiencies: bilized	e categories		
The inspection reveals that de The following actions are req V CE IP SF **Installed Correctly - Maintain un IP - Install IP IMMEDIATELY **IP missing W of site IP - Reinstall IP within 24 hours **Drop inlet protection, fabric need SPS - Install SPS within 24 hours **need new hay bales for stockoil	eficiencie uired to c til surround ds to be rei	s are present correct the de ling area is sta	t in the above eficiencies: bilized	e categories		
The inspection reveals that de The following actions are req V CE IP SF **Installed Correctly - Maintain und IP - Install IP IMMEDIATELY **IP missing W of site IP - Reinstall IP within 24 hours **Drop inlet protection, fabric need SPS - Install SPS within 24 hours **need new hay bales for stockpil Targeted Re-inspection Date / Co	eficiencie uired to c til surround ds to be rei e stabilizati	install properly	t in the above eficiencies: bilized	e categories	pt of this r	notice.
The inspection reveals that de The following actions are req V CE IP SF **Installed Correctly - Maintain un IP - Install IP IMMEDIATELY **IP missing W of site IP - Reinstall IP within 24 hours **Drop inlet protection, fabric need SPS - Install SPS within 24 hours **need new hay bales for stockpil Targeted Re-inspection Date / Co Reported to: Carlton Bitgood	eficiencie uired to c til surround ds to be rei e stabilizati	install properly	t in the above eficiencies: bilized bilized	e categories	pt of this r	notice.
The inspection reveals that de The following actions are req V CE IP SF **Installed Correctly - Maintain und IP - Install IP IMMEDIATELY **IP missing W of site IP - Reinstall IP within 24 hours **Drop inlet protection, fabric need SPS - Install SPS within 24 hours **need new hay bales for stockpil Targeted Re-inspection Date / Co Reported to: Carlton Bitgood Print Name	eficiencie uired to c til surround ds to be rei e stabilizati	install properly	t in the above eficiencies: bilized bilized	e categories	pt of this r	notice.
The inspection reveals that de The following actions are req V CE IP SF **Installed Correctly - Maintain und IP - Install IP IMMEDIATELY **IP missing W of site IP - Reinstall IP within 24 hours **Drop inlet protection, fabric need SPS - Install SPS within 24 hours **need new hay bales for stockpil Targeted Re-Inspection Date / Co Reported to: Carlton Bitgood Print Name Signature	eficiencie uired to c til surround ds to be rei e stabilizati	install properly	t in the above eficiencies: bilized bilized	e categories	pt of this r	notice.
The inspection reveals that de The following actions are req √ CE IP SF **Installed Correctly - Maintain und IP - Install IP IMMEDIATELY **IP missing W of site IP - Reinstall IP within 24 hours **Drop inlet protection, fabric need SPS - Install SPS within 24 hours **need new hay bales for stockpil Targeted Re-Inspection Date / Co Reported to: Carlton Bitgood Print Name Signature	eficiencie uired to c til surround ds to be rei e stabilizati ompliance	install properly	t in the above eficiencies: bilized bilized	e categories	pt of this r	notice.

Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>8/11/17</u> Inspection Time: <u>1:55</u> pm	Stage of Co Utility W/o	nstruction: ork Demo	Pre-Con Bldg Const.	Clearing F. Grading	Rough F. Stabi	Grading
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance 🕞	1					
Inlet Protection (P)	1		x			
Outlet Protection @						x
Silt Fence SF	1					
Sediment Trap/Basin 🗊						x
Soil Stabilization 🚯						x
Soil Stockpile Stabilization 🚱		×	×			
Tree Protection (79)						x
Dewatering Structure 🛛 🔞						x
Concrete Washout						X
Frash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req	eficiencie uired to c	s are present	in the above	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req √CEIP SF	eficiencie uired to c	s are present correct the de	in the above ficiencies:	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un	eficiencie uired to c til surround	s are present correct the de	in the above ficiencies:	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Repair IP IMMEDIATELY (dro	eficiencie uired to c til surround	s are present correct the de ling area is stat ection E of site	in the above eficiencies: bilized needs to be re	e categories. paired)	·	_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Repair IP IMMEDIATELY (dro IP - Install IP IMMEDIATELY	eficiencie uired to c til surround op inlet prot	s are present correct the de ling area is stat ection E of site	in the above ficiencies: bilized needs to be re	e categories paired)		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Repair IP IMMEDIATELY (dro IP - Install IP IMMEDIATELY **install gutter buddy NW of site	eficiencie uired to c til surround op inlet prot	s are present correct the de ling area is stat ection E of site	in the above eficiencies: bilized needs to be re	e categories		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Repair IP IMMEDIATELY (dro IP - Install IP IMMEDIATELY **install gutter buddy NW of site SPS - Install SPS NE of site IMME	eficiencie uired to c til surround op inlet prot	s are present correct the de ling area is stat ection E of site	in the above ficiencies: bilized needs to be re	e categories		
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Repair IP IMMEDIATELY (dro IP - Install IP IMMEDIATELY **install gutter buddy NW of site SPS - Install SPS NE of site IMME	eficiencie uired to c til surround op inlet prot	s are present correct the de ling area is stat ection E of site	in the above eficiencies: bilized needs to be re	e categories. paired)		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Repair IP IMMEDIATELY (dro IP - Install IP IMMEDIATELY **install gutter buddy NW of site SPS - Install SPS NE of site IMME	eficiencie uired to c til surround op inlet prot	s are present correct the de ling area is stat ection E of site	in the above eficiencies: bilized needs to be re	e categories		
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Repair IP IMMEDIATELY (dro IP - Install IP IMMEDIATELY **install gutter buddy NW of site SPS - Install SPS NE of site IMME	eficiencie uired to c til surround op inlet prot	s are present correct the de ling area is stat ection E of site	in the above eficiencies: bilized needs to be re	e categories		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Repair IP IMMEDIATELY (dro IP - Install IP IMMEDIATELY **install gutter buddy NW of site SPS - Install SPS NE of site IMME	eficiencie uired to c til surround op inlet prot	s are present correct the de ling area is stat ection E of site	in the above eficiencies: bilized needs to be re	e categories.		
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Repair IP IMMEDIATELY (dro IP - Install IP IMMEDIATELY **install gutter buddy NW of site SPS - Install SPS NE of site IMME SPS - Install SPS NE of site IMME	eficiencie uired to c til surround op inlet prot EDIATELY	s are present correct the de ling area is stat ection E of site	in the above eficiencies: bilized needs to be re	e categories paired) om the receip	pt of this n	otice.
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Repair IP IMMEDIATELY (dro IP - Install IP IMMEDIATELY **install gutter buddy NW of site SPS - Install SPS NE of site IMME SPS - Install SPS NE of site IMME	eficiencie uired to c til surround op inlet prot EDIATELY	s are present correct the de ling area is stat ection E of site	in the above eficiencies: bilized needs to be re lendar days fro pector: JaonTra	e categories paired) om the receip	pt of this r	otice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Repair IP IMMEDIATELY (dro IP - Install IP IMMEDIATELY **install gutter buddy NW of site SPS - Install SPS NE of site IMME SPS - Install SPS NE of site IMME	eficiencie uired to c til surround op inlet prot EDIATELY	s are present correct the de ling area is stat ection E of site	in the above eficiencies: pilized needs to be re lendar days fro pector: JaonTra	e categories paired) om the receip ay D. Coley Print Name	pt of this r	otice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that do The following actions are req ✓ CE IP SF **Installed Correctly - Maintain un IP - Repair IP IMMEDIATELY (dro IP - Install IP IMMEDIATELY (dro IP - Install IP IMMEDIATELY **install gutter buddy NW of site SPS - Install SPS NE of site IMME	eficiencie uired to c til surround op inlet prot EDIATELY	s are present correct the de ling area is stat ection E of site	in the above eficiencies: bilized needs to be re lendar days fro pector: Jaon Tra	e categories paired) om the receip ay D. Coley Print Name Signature	pt of this r	

	CITY	OF	NORFOLK
_			

Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>8/15/17</u> Inspection Time: <u>2:00</u> pm E & S Control Practices	tage of Construction:Pre-Con Utility Work DemoBldg Const. Installed Installed Not Effective Effective Not Installed			Clearing F. Grading Violation	Rough Gradir _*F. Stabilization Remove N/A	
Construction Entrance	1					
Inlet Protection (P)	1					
Outlet Protection @						x
Silt Fence SF	1					
Sediment Trap/Basin 🗊						x
Soll Stabilization (35)	1		×			
Soil Stockpile Stabilization 🐵	1	×				
Tree Protection (79)						x
Dewatering Structure 🛛 🔞						x
Concrete Washout 😡						x
Hay Bales	1					
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>Yes</u> The inspection reveals that de The following actions are req	Shovel / Swe eficiencie: uired to c	eep pavement a s are present correct the d	djacent to site t in the above eficiencies:	e categories		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>Yes</u> The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS Hay Bales	Shovel / Swe eficiencies uired to c	eep pavement a s are present correct the d	djacent to site t in the above eficiencies:	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>Yes</u> The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS Hay Bales **Installed Correctly - Maintain un	Shovel / Swe eficiencies uired to c	eep pavement and s are present correct the de ling area is sta	djacent to site t in the above eficiencies: bilized	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>Yes</u> The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS Hay Bales **Installed Correctly - Maintain un ✓ IP reinstalled correctly	Shovel / Swe eficiencie: uired to c til surround	eep pavement and s are present correct the de ling area is sta	djacent to site t in the above eficiencies: bilized	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>Yes</u> The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS Hay Bales **Installed Correctly - Maintain un ✓ IP reinstalled correctly ✓ stockpile S of site has been covered with pla SS - Stabilize bare soils (finish pure	Shovel / Swe eficiencie: uired to c til surround	s are present correct the de ling area is sta	djacent to site t in the above eficiencies: bilized	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>Yes</u> The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS Hay Bales **Installed Correctly - Maintain un ✓ IP reinstalled correctly ✓ stockpile S of site has been covered with pla SS - Stabilize bare soils (finish pu	Shovel / Swe eficiencies uired to c til surround stic tting down s	s are present and s are present and s orrect the deling area is stated and s area is stated at a sod S & E of signated billing at a bil	djacent to site t in the above eficiencies: bilized	e categories		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>Yes</u> The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS Hay Bales **Installed Correctly - Maintain un ✓ IP reinstalled correctly ✓ stockpile S of site has been covered with pla SS - Stabilize bare soils (finish pu **keep silt fence installed until all SRS_ stabilize SRS_within 24 hourse	Shovel / Swe eficiencie: uired to c til surround stic tting down s bare areas	s are present correct the de ling area is sta sod S & E of si are stabilized	djacent to site t in the above eficiencies: bilized	e categories		
Trash/Debris on Site: No	Shovel / Swe eficiencies uired to c til surround stic tting down s bare areas (pile of san	eep pavement and s are present correct the de ling area is sta sod S & E of si are stabilized id used for bric	djacent to site t in the above eficiencies: bilized ite	e categories		
Trash/Debris on Site: No Sediment Leaving Site: Yes The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS Hay Bales **Installed Correctly - Maintain un ✓ IP reinstalled correctly ✓ stockpile S of site has been covered with pla SS - Stabilize bare soils (finish pu **keep silt fence installed until all SPS - repair SPS within 24 hours *Shovel / Sweep brick area S of si	Shovel / Swe eficiencies uired to c til surround stic tting down s bare areas (pile of san ite IMMEDI.	eep pavement and s are present correct the de ling area is sta sod S & E of si are stabilized id used for bric ATELY	djacent to site t in the above eficiencies: bilized ite	e categories		
Trash/Debris on Site: No Sediment Leaving Site: Yes The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS Hay Bales **Installed Correctly - Maintain un ✓ IP reinstalled correctly ✓ stockpile S of site has been covered with pla SS - Stabilize bare soils (finish pu **keep silt fence installed until all SPS - repair SPS within 24 hours *Shovel / Sweep brick area S of s	Shovel / Swe eficiencies uired to c til surround stic tting down s bare areas (pile of san ite IMMEDI.	eep pavement and s are present correct the de ling area is sta sod S & E of si are stabilized id used for bric ATELY	djacent to site t in the above eficiencies: bilized ite k pavers, S of s	e categories ite)	pt of this n	
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>Yes</u> The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS Hay Bales **Installed Correctly - Maintain un ✓ IP reinstalled correctly ✓ stockpile S of site has been covered with pla SS - Stabilize bare soils (finish pu **keep silt fence installed until all SPS - repair SPS within 24 hours *Shovel / Sweep brick area S of s Targeted Re-inspection Date / C Reported to: <u>Carlton Bitgood</u> Print Name	Shovel / Swe eficiencies uired to c til surround stic tting down s bare areas (pile of san ite IMMEDI.	eep pavement ad s are present correct the de ling area is sta sod S & E of si are stabilized id used for bric ATELY Time: <u>3</u> ca	djacent to site t in the above eficiencies: bilized ite k pavers, S of s elendar days fr	e categories ite) om the receip ay D. Coley Print Name	pt of this n	
Trash/Debris on Site: No Sediment Leaving Site: Yes The inspection reveals that de The following actions are req V CE IP SF Sod SPS Hay Bales **Installed Correctly - Maintain un V IP reinstalled correctly V stockpile S of site has been covered with pla SS - Stabilize bare soils (finish pu **keep silt fence installed until all SPS - repair SPS within 24 hours *Shovel / Sweep brick area S of si Targeted Re-inspection Date / C Reported to: Carlton Bitgood Print Name	Shovel / Swe eficiencies uired to c til surround stic tting down s bare areas (pile of san ite IMMEDI.	s are present correct the de ling area is sta sod S & E of si are stabilized id used for bric ATELY	djacent to site t in the above eficiencies: bilized ite k pavers, S of s elendar days fr	e categories site) om the receip ay D. Coley Print Name	pt of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: Yes The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS Hay Bales **Installed Correctly - Maintain un ✓ IP reinstalled correctly ✓ stockpile S of site has been covered with pla SS - Stabilize bare soils (finish pu **keep silt fence installed until all SPS - repair SPS within 24 hours *Shovel / Sweep brick area S of si Fargeted Re-inspection Date / C Reported to: Carlton Bitgood Print Name Signature	Shovel / Swe eficiencies uired to c til surround stic tting down s bare areas (pile of san ite IMMEDI.	eep pavement ad s are present correct the de ling area is sta sod S & E of si are stabilized id used for bric ATELY Time: <u>3</u> ca	djacent to site t in the above eficiencies: bilized ite k pavers, S of s elendar days fr	e categories ite) om the receip ay D. Coley Print Name Signature	pt of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: Yes The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS Hay Bales **Installed Correctly - Maintain un ✓ IP reinstalled correctly ✓ stockpile S of site has been covered with pla SS - Stabilize bare soils (finish pu **keep silt fence installed until all SPS - repair SPS within 24 hours *Shovel / Sweep brick area S of s Targeted Re-inspection Date / C Reported to: Carlton Bitgood Print Name Signature	Shovel / Swe eficiencies uired to c til surround stic tting down s bare areas (pile of san ite IMMEDI. ompliance 8/15/17	s are present correct the de ling area is sta sod S & E of si are stabilized id used for bric ATELY	djacent to site t in the above eficiencies: bilized ite k pavers, S of s elendar days fr spector: JaonTr 0-0839	e categories ite) om the receip ay D. Coley Print Name Signature	pt of this n	otice.

Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>8/18/17</u> Inspection Time: <u>2:00</u> pm	Stage of Co Utility Wo	nstruction: ork Demo	Pre-Con _*Bldg Const.	Clearing F. Grading	Rough F. Stabl	Grading
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance @	1					
Inlet Protection (P)	1	×				
Outlet Protection @						x
Silt Fence 🕼	1					
Sediment Trap/Basin 🗊						x
Soil Stabilization 33	1		×			
Soll Stockpile Stabilization 👦	1					
Tree Protection 🔞						x
Dewatering Structure 😡						x
Concrete Washout						x
The inspection reveals that de	eficiencie:	eping daily s are present correct the de	in the above	categories		_
The inspection reveals that de The following actions are req V CE IP SF Sod SPS	eficiencie: uired to c	eping daily s are present orrect the de	in the above eficiencies:	e categories.		_
The inspection reveals that de The following actions are req V CE IP SF Sod SPS **Installed Correctly - Maintain unt	eficiencie: uired to c	eping daily s are present orrect the de ing area is stal	in the above eficiencies:	e categories.		_
The inspection reveals that de The following actions are req v CE IP SF Sod SPS **Installed Correctly - Maintain unt SS - Stabilize bare soils within 7 d	eficiencie: uired to c til surround	eping daily s are present forrect the de ing area is stal	in the above eficiencies:	e categories.		_
The inspection reveals that de The following actions are req V CE IP SF Sod SPS **Installed Correctly - Maintain unt SS - Stabilize bare soils within 7 d **finish install sod E of site	eficiencie: uired to c til surround ays	eping daily s are present correct the de	in the above eficiencies:	e categories.		
The inspection reveals that de The following actions are req V CE IP SF Sod SPS **Installed Correctly - Maintain uni SS - Stabilize bare soils within 7 d **finish install sod E of site IP - Reinstall IP within 24 hours	eficiencie: uired to c til surround ays	eping daily s are present orrect the de ing area is stal	in the above eficiencies:	e categories.	•	
The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS **Installed Correctly - Maintain uni SS - Stabilize bare soils within 7 d **finish install sod E of site IP - Reinstall IP within 24 hours **reinstall drop inlet protection, fal	eficiencie: uired to c til surround ays	eping daily s are present forrect the de ing area is stal	in the above eficiencies:	e categories.		
The inspection reveals that de The following actions are req V CE IP SF Sod SPS **Installed Correctly - Maintain uni SS - Stabilize bare soils within 7 d **finish install sod E of site IP - Reinstall IP within 24 hours **reinstall drop inlet protection, fal	eficiencie: uired to c til surround ays bric to IP E	eping daily s are present correct the de ing area is stal	in the above eficiencies:	e categories.		
The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS **Installed Correctly - Maintain uni SS - Stabilize bare soils within 7 d **finish install sod E of site IP - Reinstall IP within 24 hours **reinstall drop inlet protection, fal	eficiencie: uired to c til surround ays	eping daily s are present forrect the de ing area is stal	in the above eficiencies: bilized	e categories.		
The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS **Installed Correctly - Maintain uni SS - Stabilize bare soils within 7 d **finish install sod E of site IP - Reinstall IP within 24 hours **reinstall drop inlet protection, fal	eficiencie: uired to c til surround ays bric to IP E	eping daily s are present orrect the de ing area is stal of site	t in the above	e categories.		
The inspection reveals that de The following actions are req V CE IP SF Sod SPS **Installed Correctly - Maintain unt SS - Stabilize bare soils within 7 d **finish install sod E of site IP - Reinstall IP within 24 hours **reinstall drop inlet protection, fall Fargeted Re-Inspection Date / Co	eficiencie: uired to c til surround ays bric to IP E	of site	in the above eficiencies: bilized	e categories.	pt of this n	otice.
The inspection reveals that de The following actions are req V CE IP SF Sod SPS **Installed Correctly - Maintain uni SS - Stabilize bare soils within 7 d **finish install sod E of site IP - Reinstall IP within 24 hours **reinstall drop inlet protection, fal	bric to IP E	of site	in the above eficiencies: bilized bilized	om the receip	pt of this n	otice.
The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS **Installed Correctly - Maintain uni SS - Stabilize bare soils within 7 d **finish install sod E of site IP - Reinstall IP within 24 hours **reinstall drop inlet protection, fal Fargeted Re-Inspection Date / Co Reported to: Net Lopez Y CE IP SF Sod SPS	eficiencie: uired to c til surround ays bric to IP E	of site	in the above eficiencies: bilized	e categories.	pt of this n	otice.
The inspection reveals that de The following actions are req V CE IP SF Sod SPS **Installed Correctly - Maintain uni SS - Stabilize bare soils within 7 d **finish install sod E of site IP - Reinstall IP within 24 hours **reinstall drop inlet protection, fal Targeted Re-Inspection Date / Co Reported to: Net Lopez Print Name Signature	bric to IP E	of site	in the above eficiencies: bilized	e categories.		otice.
The inspection reveals that de The following actions are req ✓ CE IP SF Sod SPS **Installed Correctly - Maintain uni SS - Stabilize bare soils within 7 d **finish install sod E of site IP - Reinstall IP within 24 hours **reinstall drop inlet protection, fal Targeted Re-Inspection Date / Co Reported to: Net Lopez Print Name Signature	bric to IP E	of site	in the above eficiencies: bilized	e categories.	pt of this n	otice.

HI - 3./3" 8/29

CITY OF NORFOLK
BUREAU OF ENVIRONMENTAL SERVICES



Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>8/30/17</u> Inspection Time: <u>1t16</u> am	n Date: <u>8/30/17</u> Stage of Constru- n Time: <u>1116</u> amUtility Work		Pre-Con Bidg Const.	Clearing F. Grading	Rough Gradin F. Stabilizatior	
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance	1					
Inlet Protection (P)	1		×			
Outlet Protection @						×
Silt Fence (sr)	1					
Sediment Trap/Basin (37						x
Soil Stabilization (3)	1					
Soil Stockpile Stabilization	1		1			
Tree Protection (P)					-	x
Dewatering Structure 6	-					x
Concrete Washout						x
Sediment Leaving Site: Yes	Continue sw leficiencie quired to d	eeping daily s are present correct the de	t in the above eficiencies:	e categories.		_
Sediment Leaving Site: Yes The inspection reveals that d The following actions are rec V CE IP SF SPS **Installed Correctly - Maintain ur	Continue swi leficiencie quired to o	eeping daily s are present correct the de ding area is stal	t in the above eficiencies: bilized	e categories.		_
Sediment Leaving Site: Yes The inspection reveals that d The following actions are red V CE IP SF SPS **Installed Correctly - Maintain un	Continue swi leficiencie quired to d	eeping daily s are present correct the de ding area is stal	t in the above eficiencies: bilized	e categories.		
Sediment Leaving Site: Yes The inspection reveals that d The following actions are red V CE IP SF SPS **Installed Correctly - Maintain un V stockpile is removed V sod installed E of site	Continue swe leficiencie quired to o	eeping daily s are present correct the de ding area is stal	t in the above eficiencies: bilized	e categories.		
Sediment Leaving Site: Yes The inspection reveals that d The following actions are red V CE IP SF SPS **Installed Correctly - Maintain un V stockpile is removed V sod installed E of site	Continue swe leficiencie quired to o	eeping daily s are present correct the de ding area is stal	t in the above eficiencies: bilized	e categories.		
Sediment Leaving Site: Yes The inspection reveals that d The following actions are red V CE IP SF SPS **Installed Correctly - Maintain un V stockpile is removed V sod installed E of site IP - Install IP W of site IMMEDIAT	Continue swe leficiencie quired to d ntil surround	eeping daily s are present correct the de ding area is stal	t in the above eficiencies: bilized	e categories.		
Sediment Leaving Site: Yes The inspection reveals that d The following actions are rec V CE IP SF SPS **Installed Correctly - Maintain un V stockpile is removed V sod installed E of site IP - Install IP W of site IMMEDIAT **clean debris from inside of stor	Continue swe leficiencie quired to d ntil surround	eeping daily is are present correct the de ding area is stal	t in the above eficiencies: bilized	e categories.		
Sediment Leaving Site: Yes The inspection reveals that d The following actions are red V CE IP SF SPS **Installed Correctly - Maintain un V stockpile is removed V sod installed E of site IP - Install IP W of site IMMEDIAT **clean debris from inside of stor *Shovel / Sweep sediment W of site	Continue swi leficiencie quired to d ntil surround	eeping daily s are present correct the de ding area is stal	t in the above eficiencies: bilized	e categories.		
Sediment Leaving Site: Yes The inspection reveals that d The following actions are red V CE IP SF SPS **Installed Correctly - Maintain un V stockpile is removed V sod installed E of site IP - Install IP W of site IMMEDIAT **clean debris from inside of stor *Shovel / Sweep sediment W of s	Continue swe leficiencie quired to d ntil surround FELY mdrain ite IMMEDI	eeping daily s are present correct the de ding area is stal ding area is stal ATELY	t in the above eficiencies: bilized	e categories.	ot of this n	 otice.
Sediment Leaving Site: Yes The inspection reveals that d The following actions are red V CE IP SF SPS **Installed Correctly - Maintain un V stockpile is removed V sod installed E of site IP - Install IP W of site IMMEDIAT **clean debris from inside of stor *Shovel / Sweep sediment W of s Fargeted Re-inspection Date / C Reported to fiel Lopez	Continue swe leficiencie quired to o ntil surround TELY mdrain tite IMMEDI	eeping daily s are present correct the de ding area is stat ding area is stat ATELY Time: _2_ ca	t in the above eficiencies: bilized bilized	e categories.	ot of this n	 otice.
Sediment Leaving Site: Yes The inspection reveals that d The following actions are red V CE IP SF SPS **Installed Correctly - Maintain un V stockpile is removed V sod installed E of site IP - Install IP W of site IMMEDIAT **clean debris from inside of stor *Shovel / Sweep sediment W of s Fargeted Re-inspection Date / C Reported to fiel Lopez Print Name	Continue swe leficiencie quired to o ntil surround	eeping daily s are present correct the de ding area is stal ding area is stal ATELY Time: _2_ ca	t in the above eficiencies: bilized bilized	e categories. om the receip ay D. Coley Print Name	ot of this n	otice.
Sediment Leaving Site: Yes The inspection reveals that d The following actions are red V CE IP SF SPS **Installed Correctly - Maintain un V stockpile is removed V sod installed E of site IP - Install IP W of site IMMEDIAT **clean debris from inside of stor *Shovel / Sweep sediment W of s Targeted Re-inspection Date / C Reported to fiel Lopez Print Name Signature	Continue swe leficiencie quired to d ntil surround	eeping daily as are present correct the de ding area is stal ding area is stal ATELY a Time: _2_ ca	t in the above eficiencies: bilized bilized	e categories.	ot of this n	otice.
Sediment Leaving Site: Yes The inspection reveals that d The following actions are red V CE IP SF SPS **Installed Correctly - Maintain un V stockpile is removed V sod installed E of site IP - Install IP W of site IMMEDIAT **clean debris from inside of stor *Shovel / Sweep sediment W of s Fargeted Re-inspection Date / C Reported to Alef Lopez Print Name Signature Signature	Continue swe leficiencie quired to o ntil surround	eeping daily s are present correct the de ding area is stal ding area is stal ATELY Time: _2_ ca	t in the above eficiencies: bilized lendar days from spector: Jaon Tra	e categories.	ot of this n	otice.

CIT	YC)F I	NO	RFO	LK	
 		-				

Project Name. 100 brown has						
Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>9/1/17</u> S Inspection Time: <u>9:56</u> am _	tage of Cor _Utility Wo Installed	nstruction: rk Demo Installed Not Effective	Pre-Con Bidg Const. Not Installed	Clearing F. Grading Violation	Rough F. Stabi Remove	Grading lization N/A
Construction Entrance	1	Enecuve				
nlet Protection (P)	1				1.1	
Outlet Protection OP						x
Silt Fence SF	1					
ediment Trap/Basin 🗊						X
Soll Stabilization (SS)						X
oil Stockpile Stabilization 🜚	1					
Tree Protection m						×
Dewatering Structure 🛛 🔞						x
Concrete Washout 😡						×
				-		
rash/Debris on Site: <u>No</u> ediment Leaving Site: <u>Yes</u> <u>S</u> The inspection reveals that de	hovel / Swe	ep pavement ad	ljacent to site	categories.		_
Trash/Debris on Site: <u>No</u> S Sediment Leaving Site: <u>Yes</u> S The inspection reveals that de The following actions are requ ✓ CE IP SF SPS	hovel / Swe ficiencies vired to co	ep pavement ad are present orrect the de	ljacent to site in the above eficiencies:	categories.		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>Yes</u> <u>S</u> The inspection reveals that de The following actions are requ ✓ CE IP SF SPS **Installed Correctly - Maintain unti	hovel / Swe ficiencies uired to co il surroundi	ep pavement ad are present orrect the de ng area is stat	ljacent to site in the above eficiencies: pilized	categories.		
Trash/Debris on Site: <u>No</u> ediment Leaving Site: <u>Yes</u> <u>S</u> The inspection reveals that de The following actions are requ ✓ CE IP SF SPS **Installed Correctly - Maintain unti ✓ Inlet protection reinstalled	hovel / Swe ficiencies uired to co	ep pavement ad are present orrect the de	ljacent to site in the above eficiencies: pilized	categories.		
Trash/Debris on Site: <u>No</u> S ediment Leaving Site: <u>Yes</u> S The inspection reveals that de The following actions are requ ✓ CE IP SF SPS **Installed Correctly - Maintain unti ✓ Inlet protection reinstalled	hovel / Swe ficiencies lired to co	ep pavement ad are present orrect the de	ijacent to site in the above eficiencies: pilized	categories.		
Trash/Debris on Site: <u>No</u> S rediment Leaving Site: <u>Yes</u> S The inspection reveals that de The following actions are required ✓ CE IP SF SPS **Installed Correctly - Maintain unti ✓ Inlet protection reinstalled	hovel / Swe ficiencies uired to co	ep pavement ad are present orrect the de	ljacent to site in the above eficiencies: pilized	categories.		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>Yes</u> S The inspection reveals that de The following actions are required ✓ CE IP SF SPS **Installed Correctly - Maintain unti	hovel / Swe ficiencies lired to co	ep pavement ad are present orrect the de ng area is stat	ljacent to site in the above eficiencies: pilized	categories		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>Yes</u> S The inspection reveals that de The following actions are requ ✓ CE IP SF SPS **Installed Correctly - Maintain unti ✓ Inlet protection reinstalled	hovel / Swe ficiencies lired to co	ep pavement ad	ljacent to site in the above eficiencies: pilized	categories		
Trash/Debris on Site: <u>No</u>	hovel / Swee	ep pavement ad are present orrect the de ng area is stat	ljacent to site in the above eficiencies: bilized	categories.	ot of this n	 otice.
Trash/Debris on Site: <u>No</u>	hovel / Swe ficiencies lired to co il surroundi	ep pavement ad are present orrect the de ng area is stat ng area is stat	ijacent to site in the above eficiencies: bilized lendar days fro pector: JaonTra	e categories.	ot of this n	otice.
Trash/Debris on Site: <u>No</u>	hovel / Swee	ep pavement ad are present orrect the de ng area is stat ng area is stat	ijacent to site in the above eficiencies: pilized lendar days fro pector: JaonTra	e categories. om the receip ay D. Coley Print Name	ot of this n	 otice.
Trash/Debris on Site: <u>No</u>	hovel / Swee	ep pavement ad are present orrect the de ng area is stat ng area is stat	ljacent to site in the above eficiencies: bilized lendar days fro pector: JaonTra	e categories.	ot of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: Yes S The inspection reveals that de The following actions are required \checkmark CE IP SF SPS **Installed Correctly - Maintain unti \checkmark Inlet protection reinstalled argeted Re-inspection Date / Co Print Name \qquad Signature \downarrow S \downarrow \downarrow \downarrow \uparrow \uparrow \uparrow \uparrow \downarrow \downarrow	hovel / Swee	ep pavement ad	ijacent to site in the above eficiencies: pilized lendar days fro pector: JaonTra	e categories.	ot of this n	otice.

HI - .8" 9/2

CITY OF NORFOLK

Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>9/6/17</u> Inspection Time: <u>9:18</u> am	Stage of Co Utility W/	onstruction: ork Demo	Pre-Con Bldg Const.	Clearing F. Grading	Rough F. Stabi	Grading
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance	1					
nlet Protection (P)	1				5	
Dutlet Protection @						×
ilt Fence 🕼	1					
ediment Trap/Basin 🗊						x
oil Stabilization 🚯	1	×				
oil Stockpile Stabilization 🚱	1					-
ree Protection 🕞						x
Newatering Structure 😡						x
Concrete Washout						x
Sediment Leaving Site: <u>No</u> <u>C</u> The inspection reveals that de	Continue swe eficiencie	eeping daily s are present	in the above	categories.		_
ediment Leaving Site: <u>No</u> <u>C</u> The inspection reveals that de The following actions are req ✓ CE IP SF SPS	continue swe eficiencie uired to c	eeping daily s are present correct the de	in the above ficiencies:	categories.		_
ediment Leaving Site: <u>No</u> <u>C</u> The inspection reveals that de The following actions are req ✓ CE IP SF SPS **Installed Correctly - Maintain un	continue swe eficiencie uired to c	eeping daily s are present correct the de ling area is stat	in the above ficiencies: pilized	e categories.		_
ediment Leaving Site: <u>No</u> <u>C</u> The inspection reveals that do The following actions are req V CE IP SF SPS **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 d	continue swe eficiencie uired to c til surround	eeping daily s are present correct the de ling area is stat	in the above ficiencies: pilized	categories.		_
ediment Leaving Site: <u>No</u> <u>C</u> The inspection reveals that de The following actions are req ✓ CE IP SF SPS **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 d **install seeding and matting to A	continue swe eficiencie uired to d til surround lays LL bare sol	eeping daily s are present correct the de ling area is stat	in the above ficiencies: pilized	e categories.		
ediment Leaving Site: <u>No</u> <u>C</u> The inspection reveals that de The following actions are req ✓ CE IP SF SPS **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 d **install seeding and matting to A	continue swe eficiencie uired to d til surround lays LL bare so	eeping daily s are present correct the de ling area is stat	in the above eficiencies: bilized	categories.		
ediment Leaving Site: NoC The inspection reveals that de The following actions are req V CE IP SF SPS **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 d **install seeding and matting to A argeted Re-inspection Date / Co	continue swe eficiencie uired to d til surround lays LL bare sol	eeping daily s are present correct the de ling area is stat ils S and E of si	in the above eficiencies: bilized ite	e categories.	ot of this n	otice.
ediment Leaving Site: NoC The inspection reveals that de The following actions are req V CE IP SF SPS **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 d **install seeding and matting to Al argeted Re-inspection Date / Co eported to: Nef Lopez Font Name	continue swe eficiencie uired to d til surround lays LL bare sol	eeping daily s are present correct the de ling area is stat ils S and E of si lis S and E of si Time: _7_ cal	in the above eficiencies: bilized ite lendar days fro pector: JaonTra	e categories.	ot of this n	otice.
ediment Leaving Site: NoC The inspection reveals that de The following actions are req V CE IP SF SPS **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 d **install seeding and matting to A argeted Re-inspection Date / Co eported to: Nef Lopez Fint Name	continue swe eficiencie uired to d til surround lays LL bare sol	eeping daily s are present correct the de ling area is stat ils S and E of si Time: _7_ cal	in the above eficiencies: pilized ite	e categories.	ot of this n	otice.
ediment Leaving Site: NoC The inspection reveals that de The following actions are req ✓ CE IP SF SPS **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 d **install seeding and matting to A **install seeding and matting to A argeted Re-inspection Date / Co eported to: Nef Lopez Fht Name Shatul	continue swe eficiencie uired to d til surround lays LL bare sol	eeping daily s are present correct the de ling area is stat ils S and E of si Time: _7_ cal Ins	in the above eficiencies: Dilized ite	e categories.	ot of this n	otice.

CITY OF NORFOLK
BUREAU OF ENVIRONMENTAL SERVICES

JE I

Address: 700 Park Ave.				CGP: No	#:	_
Inspection Date: <u>9/20/17</u> Inspection Time: <u>10:32</u> am	Stage of Co Utility Wo	nstruction: ork Demo	Pre-Con _*Bldg Const.	Clearing F. Grading	Rough F. Stabi	Grading
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance @	1					
Inlet Protection	1					
Outlet Protection @						x
Silt Fence SF	1					
Sediment Trap/Basin 🕥						x
Soll Stabilization (35)	1					
Soll Stockpile Stabilization 🐵	1					
Tree Protection (P)						x
Dewatering Structure						x
Concrete Washout 👦				1		x
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red	eficiencies juired to c	s are present	in the above	categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red ✓ CE IP SF SPS	eficiencie: juired to c	s are present orrect the de	in the above ficiencies:	categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red V CE IP SF SPS **Installed Correctly - Maintain un	eficiencies juired to c	s are present orrect the de ing area is stat	in the above eficiencies:	categories.		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are req ✓ CE IP SF SPS **Installed Correctly - Maintain un	eficiencies juired to c	s are present orrect the de ing area is stat	in the above ficiencies:	categories		
Trash/Debris on Site: <u>No</u>	eficiencie: juired to c ntil surround	s are present orrect the de	in the above eficiencies:	categories		
Trash/Debris on Site: <u>No</u>	eficiencie: juired to c ntil surround ite	s are present orrect the de ing area is stat	in the above eficiencies: pilized	categories.		
Trash/Debris on Site: <u>No</u>	eficiencie: juired to c ntil surround ite	s are present orrect the de ing area is stat Time: <u>14</u> ca	in the above eficiencies: pilized lendar days fro	e categories.	ot of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that d The following actions are red ✓ CE IP SF SPS **Installed Correctly - Maintain un ✓ bare soils are stabilized **stabilize bare soils Far East of s Targeted Re-Inspection Date / C Reported tor Nef Lopez	eficiencie: juired to c ntil surround ite	s are present orrect the de ing area is stat ing area is stat Time: <u>14</u> ca	in the above eficiencies: pilized lendar days fro pector: JaonTra	e categories.	ot of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that d The following actions are red ✓ CE IP SF SPS **Installed Correctly - Maintain un ✓ bare soils are stabilized **stabilize bare soils Far East of s Fargeted Re-Inspection Date / C Reported tor Nef Lopez Print Name Signature	eficiencie: juired to c ntil surround ite	s are present orrect the de ing area is stat ing area is stat Time: <u>14</u> ca	in the above eficiencies: bilized lendar days fro pector: JaonTra	e categories.	ot of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that d The following actions are red ✓ CE IP SF SPS **Installed Correctly - Maintain un ✓ bare soils are stabilized **stabilize bare soils Far East of s Fargeted Re-Inspection Date / C Reported to Nef Lopez Print Name Signature	eficiencie: Juired to c Intil surround	s are present orrect the de ing area is stat Time: <u>14</u> ca Ins	in the above eficiencies: pilized lendar days fro pector: JaonTra	e categories.	ot of this n	otice.

CITY	OF	NORFOLK	

and the second s	EAU OF E	NVIRONME	ENTAL SERV	ICES		-
Erosio	n and Sedi	ment Contro	I Inspection I	Report	1	
roject Name: NSU Brown Hall						_
Address: 700 Park Ave.				CGP: No	#:	
nspection Date: <u>9/25/18</u> nspection Time: <u>1:45</u> pm E & S Control Practices	Stage of Co Utility Wo Installed	nstruction: ork Demo Installed Not	Pre-Con _*Bldg Const. Not Installed	Clearing F. Grading Violation	Rough F. Stabi Remove	Grading lization N/A
onstruction Entrance	Effective	Effective	1			
nlet Protection	1					
Dutlet Protection						x
ilt Fence	1					-
ediment Trap/Basin 🕥						X
oil Stabilization (SS)						X
oil Stockpile Stabilization						x
ree Protection (TP)						x
Dewatering Structure						X
oncrete Washout						X
Wattles	1					
he inspection reveals that of the following actions are re	deficiencie quired to d	s are present	t in the above	e categories		
Violations: Ist □ 2nd ✓ CE IP SF Wattles "Installed Correctly - Maintain u	3rd / St	top Work ling area is stal	bilized			_
Violations: Ist □ 2nd ✓ CE IP SF Wattles "Installed Correctly - Maintain u	Til surround	top Work ling area is stal	bilized			
Violations: Ist □2nd ✓ CE IP SF Wattles "Installed Correctly - Maintain u argeted Re-inspection Date / 0	Compliance	top Work ling area is stal	bilized	rom the recei	pt of this r	 notice.
Violations: Ist 2nd ✓ CE IP SF Wattles "Installed Correctly - Maintain u argeted Re-inspection Date / O eported to: Nef Lopez Print Name Automature	Compliance	top Work ling area is stal	bilized bilized alendar days fr spector: JaonTr	om the recei	pt of this r	notice.

CITY OF NORFOLK	
BUREAU OF ENVIRONMENTAL SER	VICES
Erosion and Sediment Control Inspection	n Report

				CGP: No	#:	
Inspection Date: <u>9/10/18</u> Inspection Time: <u>12:44</u> am	9/10/18 Stage of Construction:Pre-Con 2:44 amUtility WorkDemo _*Bldg Const.		Clearing F. Grading	Rough Gradin F. Stabilization		
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance	1					
Inlet Protection	1					
Outlet Protection @						x
Silt Fence SF	1					
Sediment Trap/Basin 🗊	1					
Soil Stabilization (33)	1					
Soil Stockpile Stabilization 🚱	1					
Tree Protection 🕝						x
Dewatering Structure						x
Concrete Washout						x
The following actions are req Violations: Ist 2nd	uired to a	correct the de	eficiencies:	e categories		
The following actions are req Violations: ☑1st ☐ 2nd ✓ CE IP SF SPS ST	uired to d U 3rd / St	correct the de top Work	eficiencies:	categories		
The following actions are req Violations: Ist 2nd V CE IP SF SPS ST **Installed Correctly - Maintain un	til surround	correct the de top Work	bilized	categones		_
The following actions are req Violations: ☑1st ☑ 2nd ✓ CE IP SF SPS ST **Installed Correctly - Maintain un	til surround	ing area is stal	bilized			
The following actions are req Violations: ☑1st ☑2nd ✓ CE IP SF SPS ST **Installed Correctly - Maintain un Fargeted Re-Inspection Date / C Reported to: Nef Lopez Print Name Market	uired to o	e Time: <u>14</u> ca	bilized bilize	rom the receij	pt of this m	notice.
The following actions are req Violations: Ist Ist 2nd V CE IP SF SPS ST **Installed Correctly - Maintain un Finstalled Correctly - Maintain un Targeted Re-Inspection Date / C Reported to: Nef Lopez Print Name Signature	til surround	e Time: <u>14</u> ca	bilized	om the recei ay D. Coley Print Name Signature	pt of this m	notice.
The following actions are req Violations: ⊡1st □2nd ✓ CE IP SF SPS ST **Installed Correctly - Maintain un Targeted Re-inspection Date / C Reported to: Nef Lopez Print Name Signature 7576720522	ompliance	e Time: <u>14</u> ca	bilized bilize	om the recei	pt of this r	notic

t

~

Project Name: NSU Brown Hall						
						_
Address: 700 Park Ave.				CGP: No	#:	
nspection Date: <u>9/4/18</u> nspection Time: <u>10:11</u> pm	Stage of Co Utility W/	nstruction: ork Demo	Pre-Con _*Bldg Const.	_Clearing _F. Grading	Rough F. Stabi	Grading
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance	1					
nlet Protection 🛞	1					
Outlet Protection @						x
Silt Fence 🕼	1					
Sediment Trap/Basin 🗊						x
Soil Stabilization (33)	1	1				
Soil Stockpile Stabilization 🐵	1			1		
Tree Protection 🕝						x
Dewatering Structure 🛛 🔞						x
Concrete Washout 😡						x
The inspection reveals that d	leficiencie quired to d	s are present	in the above	e categories		·
The inspection reveals that d The following actions are red Violations: Ist Ist 2nd	leficiencie quired to c 3rd/St	s are present correct the de top Work	in the above eficiencies:	e categories		·
The inspection reveals that d The following actions are red Violations: Ist 2nd VCE IP SF SPS **Installed Correctly - Maintain un	leficiencie quired to c 3rd/St ntil surround	s are present correct the de top Work ling area is stat	t in the above eficiencies:	e categories		
The inspection reveals that d The following actions are red Violations: Inst Inst Inst Verifies SPS **Installed Correctly - Maintain un	leficiencie quired to d 3rd/St ntil surround	s are present correct the de top Work ling area is stat	t in the above eficiencies: bilized	e categories		
The inspection reveals that d The following actions are rec Violations: Instruction 2nd VCE IP SF SPS **Installed Correctly - Maintain un	leficiencie quired to c D 3rd / St ntil surround	s are present correct the de top Work ling area is stat	t in the above eficiencies: bilized	e categories	pt of this r	notice.
The inspection reveals that d The following actions are rec Violations: Instruction Violations: Instruction Violation Violations: Instruction Violation Violations: Instruction Violation Vi	leficiencie quired to d D 3rd / St ntil surround	s are present correct the de top Work ling area is stat	t in the above eficiencies: bilized bilized	e categories	pt of this n	notice.
The inspection reveals that d The following actions are rec Violations: Installed Correctly - Maintain un Correctly - Maintain un Targeted Re-inspection Date / C Reported to: Nef Lopez With Mame	leficiencie quired to d I 3rd / St ntil surround	s are present correct the de top Work ling area is stat 	t in the above eficiencies: pilized lendar days fr spector: JaonTr	e categories	pt of this n	notice.
The inspection reveals that d The following actions are red Violations: Installed Correctly - Maintain un **Installed Correctly - Maintain un Fargeted Re-Inspection Date / C Reported to: Nef Lopez Print Name Signature	leficiencie quired to c D 3rd / St ntil surround	s are present correct the do top Work ling area is stat Time: <u>14</u> ca	in the above eficiencies: bilized	e categories	pt of this n	notice.
The inspection reveals that d The following actions are rec Violations: Installed Correctly - Maintain un VCE IP SF SPS **Installed Correctly - Maintain un Targeted Re-inspection Date / C Reported to: Nef Lopez Print Name Signature 7576720522	leficiencie quired to d D 3rd / St ntil surround	s are present correct the de top Work ling area is stat Time: <u>14</u> ca	in the above eficiencies: pilized lendar days fr spector: JaonTr	e categories	pt of this m	notice.

BI -	21	15*	8	20
	***		~	**

Erosion	and Sedi	ment Contro	I Inspection	Report		
Project Name: NSU Brown Hall						_
Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>8/21/18</u> Inspection Time: <u>12:11</u> am	Stage of Co Utility W/	onstruction: ork Demo Installed Not	_Pre-Con _*Bidg Const.	_Clearing _F. Grading Violation	Rough F. Stabi	Grading lization
Ediscontorractices	Effective	Effective	Teor mistanea		Keniore	
Construction Entrance (E)	-					
Inlet Protection (P)	1					
Outlet Protection @						×
Silt Fence SF	1					
Sediment Trap/Basin (57)						×
Soil Stabilization (SS)	1					
Soil Stockpile Stabilization 🐵	1					
Tree Protection (79)						x
Dewatering Structure						x
Concrete Washout						x
Violations: □1st □2nd ✓ CE IP SF SPS sod	3rd/S	top Work				
**Installed Correctly - Maintain ur	ntil surround	ling area is sta	bilized			_
						_
Targeted Re-inspection Date / C	ompliance	e Time: <u>14</u> ca	alendar days fi	rom the recei	pt of this r	notice.
Print Name		In	spector: Jaon	Print Name	-	-
			-	~/~		5
Signature			11	Signature	11	
	0/01/4	. //.	0.000	/	/ 0/2	1/19
Phone Number	0/21/1 Da	ate Ph	one Number	0	0/2	Date

	RI	- 3.	72*	8/	11
--	----	------	-----	----	----

Erosion	and Sedi	ment Contro	Inspection	Report		
Project Name: NSU Brown Hall						
Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>8/16/18</u> Inspection Time: <u>1145</u> am	Stage of Co Utility Wo	nstruction: ork Demo	Pre-Con _*_Bldg Const.	Clearing F. Grading	Rough F. Stabi	Grading lization
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance	1					
Inlet Protection	1					
Outlet Protection @						x
Silt Fence (sr)	1					
Sediment Trap/Basin (57)						x
Soil Stabilization (ss)	1					
Soil Stockpile Stabilization	1					
Tree Protection (TP)						x
Dewatering Structure						x
Concrete Washout						x
The following actions are req Violations: 1st 2nd	uired to a	orrect the de op Work	eficiencies:			
**Installed Correctly - Maintain un	til surround	ing area is stal	oilized			
✓ rest of sod has been installed to bare soils N	and NE of site					_
Targeted Re-inspection Date / C Reported to: <u>Nef Lopez</u> Print Name	ompliance	Time: <u>14</u> ca In:	lendar days fr pector: JaonTr	rom the receip ray D. Coley Print Name	pt of this n	notice.
			2	70	1	ſ
Signature		/	///	Signature	//	
	8/16/1	8 62	0-9839	_//	8/1	6/18
Phone Number	Da	te Pho	me Number	0		Date

CITY	OF	NO	RFO	LK

Project Name: NSU Brown Hall Address: 700 Park Ave. CGP: No #:	Erosion	n and Sedii	ment Contro	Inspection	Report	1	
Address: 700 Park Ave. CGP: No #:	Project Name: NSU Brown Hall						
nspection Date: 8/10/18 Stage of Construction: Pre-Con Clearing Rough Gr nspection Time: 11:31 am	Address: 700 Park Ave.				CGP: No	#:	
Construction Entrance Construction Entrance Construction Entrance Construction Entrance Construction Entrance Construction Protection Contract Protection Construction Construct	Inspection Date: <u>8/10/18</u> Inspection Time: <u>11:31</u> am E & S Control Practices	Stage of Con Utility Wo Installed Effective	nstruction: ork Demo Installed Not Effective	Pre-Con _*_Bldg Const. Not Installed	Clearing F. Grading Violation	Rough F. Stabi Remove	Grading lization N/A
Inlet Protection	Construction Entrance	1					
Outlet Protection Image: Still Fence Image: Sti	Inlet Protection (P)	1					
Silt Fence Solt Stabilization Solt Stabiliza	Outlet Protection 🞯						x
Sediment Trap/Basin Image: Sediment Trap/Sediment Trap/Sediment Trap/Basin Image: Sediment Trap/Sediment Trap	Silt Fence SF	1					
Soil Stabilization Soil Stockpile Stabilization Soil Stockpile Stabilization Soil Stockpile Stabilization Tree Protection Dewatering Structure Soil Stockpile Stabilization Dewatering Structure Stabilize Structure Stabilize Structure Stabilize Structure Soil Stockpile Stabilize Stabilize Stabilize bare soils within 7 days ***Inish installing rest of the sod *Shovel / Sweep Corprew Ave. IMMEDIATELY Targeted Re-inspection Date / Compliance Time: 7 calendar days from the receipt of this not Reported to: Nel Lopez Mathematic Signature 75706720522 8/10/18	Sediment Trap/Basin 🗊						x
Soli Stockpile Stabilization @ Tree Protection @ Tree Protection @ Dewatering Structure @ Concrete Washout Concrete the deficiencies: Violations:	Soil Stabilization (33)	1		x			
Tree Protection Dewatering Structure Dewatering Structure Concrete Washout Sediment Leaving Site: Yes Statistic Stati	Soil Stockpile Stabilization 💮						x
Dewatering Structure Image: Structure	Tree Protection 🔞						x
Concrete Washout Image: Section Site: No	Dewatering Structure 🛛 🔞						x
Trash/Debris on Site: No Sediment Leaving Site: Yes Shovel / Sweep pavement adjacent to site The inspection reveals that deficiencies are present in the above categories. The following actions are required to correct the deficiencies: Violations: 1st 1st 2nd 3rd / Stop Work V CE IP SF Sod **Installed Correctly - Maintain until surrounding area is stabilized vd sod has been installed to most bare areas SS - Stabilize bare soils within 7 days **finish installing rest of the sod *Shovel / Sweep Corprew Ave. IMMEDIATELY Targeted Re-inspection Date / Compliance Time: 7_ calendar days from the receipt of this not Reported to: Nef Lopez Inspector: JaonTray D. Coley With Ware Print Name With Ware Signature 75706720522 8/10/18	Concrete Washout 🛛 🐼				1		X
✓ sod has been installed to most bare areas SS - Stabilize bare soils within 7 days **finish installing rest of the sod *Shovel / Sweep Corprew Ave. IMMEDIATELY 'argeted Re-inspection Date / Compliance Time: _7_ calendar days from the receipt of this not teported to: Nef Lopez Print Name Print Name Signature Signature 8/10/18	The following actions are red Violations: □1st □2nd V CE IP SF Sod **Installed Correctly - Maintain un	quired to c 3rd / Sto	orrect the do op Work	eficiencies:	categories		_
SS - Stabilize bare soils within 7 days **finish installing rest of the sod *Shovel / Sweep Corprew Ave. IMMEDIATELY Targeted Re-inspection Date / Compliance Time: _7_ calendar days from the receipt of this not Reported to: Nef Lopez Print Name Print Name Signature 75706720522	\checkmark sod has been installed to most bare areas						_
**finish installing rest of the sod *Shovel / Sweep Corprew Ave. IMMEDIATELY Targeted Re-inspection Date / Compliance Time: 7 calendar days from the receipt of this not Reported to: Nef Lopez Print Name Print Name Signature 75706720522 8/10/18 **finish installing rest of the sod *Shovel / Sweep Corprew Ave. IMMEDIATELY Calendar days from the receipt of this not Inspector: JaonTray D. Coley Print Name Signature 620-0838 8/10/18	SS - Stabilize bare soils within 7 of	days					_
*Shovel / Sweep Corprew Ave. IMMEDIATELY Targeted Re-inspection Date / Compliance Time: 7_ calendar days from the receipt of this not Reported to: Nef Lopez Print Name Print Name Signature 75706720522 8/10/18 *Shovel / Sweep Corprew Ave. IMMEDIATELY	**finish installing rest of the sod						
Targeted Re-inspection Date / Compliance Time: 7_ calendar days from the receipt of this not Reported to: Nef Lopez Inspector: JaonTray D. Coley Print Name Print Name Signature Signature 75706720522 8/10/18	*Shovel / Sweep Corprew Ave. IN	MEDIATEL	Y				
75706720522 8/10/18 620-0838 8/10/1	Targeted Re-inspection Date / C Reported to: <u>Nef Lopez</u> Brint Name Signature	Compliance	Time: <u>7</u> ca _ Ins	ilendar days fr spector: <u>JaonTr</u>	om the receip ay D. Coley Print Name Signature	pt of this n	otice.
Phone Number Date Phone Number Dr	75706720522	8/10/18	62 Ph	0-0838		8/10	0/18 Date

BUREAU OF ENVIRONMENTAL SERVICES

JH.

Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>8/3/18</u> Inspection Time: <u>10:50</u> am	Stage of Co Utility Wo	nstruction: ork Demo	Pre-Con _*Bldg Const.	Clearing F. Grading	Rough F. Stabi	Grading
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance	1					
Inlet Protection (P)	1					
Outlet Protection @						x
Silt Fence 🕼	1					
Sediment Trap/Basin 🗊						x
Soil Stabilization (35)			×			
Soil Stockpile Stabilization 🐵						x
Tree Protection (P)						x
Dewatering Structure 🛛 🔞						x
Concrete Washout						x
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are req	eficiencie uired to d	s are present correct the de	in the above eficiencies:	e categories		_
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are req Violations: 1 st 2 nd	eficiencie juired to c 3rd/St	s are present correct the de top Work	in the above eficiencies:	e categories		_
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are req Violations: □1st □2nd √ CE IP SF **Installed Correctly - Maintain un	eficiencie juired to d] 3rd / Si til surround	s are present correct the de top Work ling area is stat	in the above eficiencies:	e categories		_
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un	eficiencie juired to d] 3rd / St til surround	s are present correct the de top Work ling area is stat	in the above eficiencies: pilized	e categories		_
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 c	eficiencie juired to d] 3rd / Si til surround	s are present correct the de top Work ling area is stat	in the above eficiencies:	e categories		
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 c **all bare soils must be stabilized	eficiencie luired to d 3rd / St til surround days	s are present correct the de top Work ling area is stat	in the above eficiencies: bilized	e categories	-	
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 o **all bare soils must be stabilized	eficiencie Juired to d 3rd / St til surround days	s are present correct the de top Work ling area is stat	in the above eficiencies: bilized	e categories	-	
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 c **all bare soils must be stabilized	eficiencie Juired to d I 3rd / St til surround days	s are present correct the de top Work ling area is stat	in the above eficiencies: bilized	e categories	-	
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 of **all bare soils must be stabilized	eficiencie Juired to d I 3rd / St til surround days	s are present correct the de top Work ling area is stat	in the above eficiencies: bilized	e categories	-	
Sediment Leaving Site: No	eficiencie luired to d l 3rd / St til surround days IMMEDIA	s are present correct the de top Work ling area is stat TELY (sod insta TELY (sod insta	in the above eficiencies: pilized alled or seed ar	e categories		notice.
Sediment Leaving Site: No	eficiencie Juired to d I 3rd / St til surround days IMMEDIA	s are present correct the de top Work ling area is stat TELY (sod insta TELY (sod insta	in the above eficiencies: bilized alled or seed ar	e categories	pt of this r	notice.
Sediment Leaving Site: No The inspection reveals that d The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 c **all bare soils must be stabilized Targeted Re-inspection Date / C Reported to: Nel Lopez ✓ Print Name	eficiencie Juired to d I 3rd / St til surround days IMMEDIA	s are present correct the de top Work ling area is stat TELY (sod insta TELY (sod insta	in the above eficiencies: pilized alled or seed ar	e categories	pt of this r	notice.
Sediment Leaving Site: No The inspection reveals that d The following actions are req Violations: 1st 2nd V CE IP SF **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 c **all bare soils must be stabilized Targeted Re-inspection Date / C Reported to: Nel Lopez Print Name Muthematical Stabilized	eficiencie Juired to d I 3rd / St til surround days IMMEDIAT	s are present correct the de top Work ling area is stat TELY (sod insta TELY (sod insta	in the above eficiencies: bilized alled or seed ar	e categories	pt of this r	notice.
Sediment Leaving Site: No The inspection reveals that d The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un SS - Stabilize bare soils within 7 c **all bare soils must be stabilized Targeted Re-inspection Date / C Reported to: Nel Lopez Print Name Signature	eficiencie Juired to d I 3rd / St til surround days IMMEDIA Compliance	s are present correct the de top Work ling area is stat TELY (sod insta TELY (sod insta TIME: _7_ ca	in the above eficiencies: bilized alled or seed ar	e categories	pt of this r	notice.

	 -	-	
D	 10.0	- 21	
PC -	 		0.00
	A		**

Erosion al Erosion al Erosion al Project Name: NSU Brown Hall Address: 700 Park Ave. State Inspection Date: 7/31/18 State Inspection Date: 7/31/18 State Inspection Date: 7/31/18 State Inspection Date: 7/31/18 State Inspection Time: 10:40 am 10 E & S Control Practices In In State Construction Entrance E Inlet Protection In Op Outlet Protection IP Outlet Protection IP State State State Soil Stabilization SS Soil Stabilization SS State State State State	nd Sedin	ment Contro	I Inspection I Pre-Con Bldg Const. Not Installed	CGP: No Clearing F. Grading Violation	#: Rough F. Stabi Remove	Grading lization N/A
Project Name: NSU Brown Hall Address: 700 Park Ave. Inspection Date: 7/31/18 Sta Inspection Time: 10:40 am E & S Control Practices Ir Construction Entrance (E) Inlet Protection (P) Outlet Protection (P) Silt Fence (SF) Sediment Trap/Basin (ST) Soil Stabilization (SS) Soil Stockpile Stabilization (P3)	age of Col Utility Wo Installed Iffective	nstruction: ork Demo Installed Not Effective X	Pre-Con ≚Bldg Const. Not Installed	CGP: No Clearing F. Grading Violation	#:Rough Rough F. Stabi Remove	Grading lization N/A
Address: 700 Park Ave. Inspection Date: 7/31/18 Sta Inspection Time: 10:40 am E & S Control Practices III E Construction Entrance E Inlet Protection IP Outlet Protection IP Silt Fence SF Sediment Trap/Basin ST Soil Stabilization SS Soil Stockpile Stabilization SS	age of Col Utility Wo Installed Iffective	nstruction: ork Demo Installed Not Effective X	Pre-Con ≚Bldg Const. Not Installed	CGP: No Clearing F. Grading Violation	#:Rough Rough F. Stabi Remove	Grading lization N/A
Address: 100 F dik AV0. Inspection Date: 7/31/18 Sta Inspection Time: 10:40 am E & S Control Practices In Construction Entrance (E) Inlet Protection (P) Outlet Protection (P) Silt Fence (SF) Sediment Trap/Basin (ST) Soil Stabilization (SS)	age of Col Utility Wo Installed	nstruction: ork Demo Installed Not Effective X	Pre-Con <u>*</u> Bldg Const. Not Installed	_Clearing _F. Grading Violation	Rough F. Stabi Remove	Grading lization N/A
Inspection Date: 7/31/18 State Inspection Time: 10:40 am E & S Control Practices In Construction Entrance CE Inlet Protection IP Outlet Protection IP Silt Fence SF Sediment Trap/Basin ST Soil Stabilization SS	age of Con Utility Wo Installed Iffective	nstruction: ork Demo Installed Not Effective X	Pre-Con ≚Bldg Const. Not Installed	Clearing F. Grading Violation	Rough F. Stabi Remove	Grading lization N/A
E & S Control Practices	installed	Installed Not Effective X	Not Installed	Violation	Remove	N/A
Construction Entrance (E) Inlet Protection (P) Outlet Protection (P) Silt Fence (SF) Sediment Trap/Basin (ST) Soil Stabilization (SS) Soil Stockpile Stabilization (P)	v v	×				
Inlet Protection (P) Outlet Protection (P) Silt Fence (SF) Sediment Trap/Basin (ST) Soil Stabilization (SS) Soil Stockpile Stabilization (P)	v	×				
Outlet Protection @P Silt Fence (SF Sediment Trap/Basin (ST Soil Stabilization (SS Soil Stockpile Stabilization (PS)	~					
Silt Fence (SF) Sediment Trap/Basin (ST) Soil Stabilization (SS) Soil Stockpile Stabilization (PS)	V					x
Sediment Trap/Basin (ST) Soil Stabilization (SS) Soil Stockpile Stabilization (PS)						
Soil Stabilization (35) Soil Stockpile Stabilization (99)						×
Soil Stockpile Stabilization 🐵			×			
						×
Tree Protection 🔞						×
Dewatering Structure						×
Concrete Washout						×
The inspection reveals that def The following actions are requi Violations: 1st 2nd 2	iciencie ired to c] 3rd / St	s are present correct the de op Work	in the above eficiencies:	e categories.		
✓ CE SF						
**Installed Correctly - Maintain until	surround	ing area is stat	oilized			
IP - Clean ALL IP's IMMEDIATELY						
IP - Repair/Replace (that need to be) ALL IP	s IMMEDIATE	LY			
SS - Stabilize bare soils within 7 day	vs					
	10					



UT I

Erosion	n and Sedin	ment Contro	I Inspection I	Report		
Project Name: NSU Brown Hall						
Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: 7/18/18 Inspection Time: 2:48 pm	Stage of Con Utility Wo	nstruction: ork Demo Installed Not	Pre-Con _*Bldg Const. Not Installed	_Clearing _F. Grading Violation	Rough F. Stabi Remove	Grading lization N/A
Construction Entrance	Effective	Effective	1	1		
Inlet Protection						
Outlet Protection	v					×
	1					-
Sediment Trap/Basin (9)	v					×
						×
Soil Stockpile Stabilization						-
Tree Protection	1					
Dewatering Structure	v					x
Concrete Washout	1					
	v					
Violations: ☐1st ☐ 2nd ✓ CE IP SF TP CW **Installed Correctly - Maintain un	3rd / St	op Work	bilized			_
✓ silt fence is repaired correctly						_
						_
						_
Targeted Re-inspection Date / 0	Compliance	Time: <u>14</u> ca	alendar days fr	rom the recei	pt of this r	otice.
Reported to: Ner Lopez	1	in	spector: Jaonn	Print Name	-	
Maltal P						-
Signature	f 7		2	Signature	-	7
Signature 7576720522	7/18/1	8 63	20-0839	Signature	61	8/18 Data

BURE	CITY AU OF E	OF NOR	FOLK	ICES		
Erosion	and Sedi	ment Contro	Inspection I	Report		
Project Name: NSU Brown Hall						
Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: 7/17/18 S Inspection Time: 1:34 pm –	tage of Co _Utility W/ Installed Effective	onstruction: ork Demo Installed Not Effective	Pre-Con Bldg Const. Not Installed	Clearing F. Grading Violation	Rough F. Stabi Remove	Grading lization N/A
Construction Entrance (E)	V					_
Inlet Protection (P)	V					
Outlet Protection @						×
Silt Fence (SF)	V	×	×			
Sediment Trap/Basin (ST)						×
Soil Stabilization (SS)						×
Soil Stockpile Stabilization 🙉						×
Tree Protection (P)	~					
Dewatering Structure						×
Concrete Washout	~					
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: Elst E 2nd ✓ CE IP SF TP CW **Installed Correctly - Maintain uni	eficiencie uired to 3rd/S	es are present correct the d top Work ding area is sta	t in the above eficiencies: bilized	e categories		_
SF - Repair SF IMMEDIATELY						
SF - INSTALL SF IMMEDIATELY						
Tailong Corprew Ave.	noiteloi					
*Failure to comply will result in a v	deletion					
*Failure to comply will result in a v	noiauon					
Targeted Re-inspection Date / C	ompliand	ce Time: <u>2</u> c	alendar days f	rom the rece	ipt of this	notice.

Reported to: Nef Lopez		Inspector: JaonTray D. (Coley
With Print Nan	ne	Prin	t Name
Signatur	e	Sign Sign	nature 7/17/18
7576720522	7/17/18 Date	Phone Mupaber	Date

Project Name: NSU Brown Hall						
Address: 700 Park Ave.				CGP: No	#:	
nspection Date: 7/9/18 nspection Time: 2:52 am	Stage of Col Utility Wo	nstruction: ork Demo Installed Not	Pre-Con _*Bldg Const.	_Clearing _F. Grading	Rough F. Stabi	Grading lization
E & S Control Practices	Effective	Effective	Not installed	violation	Remove	
Construction Entrance (E)	1					
nlet Protection (P)	1					
Outlet Protection @						X
Silt Fence (SF)	1					
Sediment Trap/Basin (ST)	-					x
Soil Stabilization (8)						X
Soil Stockpile Stabilization 🚱	1					
Tree Protection (P)	1					
Dewatering Structure						x
Concrete Washout 😡						x
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red	eficiencie quired to c	s are present correct the d	t in the above eficiencies:	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain ur	leficiencie quired to c I 3rd / St ntil surround	s are present correct the de cop Work ing area is sta	t in the above eficiencies: bilized	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain ur	leficiencie quired to c I 3rd / St ntil surround	s are present correct the de cop Work ing area is sta	t in the above eficiencies: bilized	e categories	-	
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that d The following actions are rec Violations: 1st 2nd VIOLATIONS: 1st 2nd VCE IP SF TP **Installed Correctly - Maintain un **Installed Correctly - Maintain un Targeted Re-inspection Date / C Reported to: Nef Lopez Print Name Signature 7576720522	Compliance	s are present correct the de cop Work ing area is sta	t in the above eficiencies: bilized alendar days fr spector: JaonTr	e categories	pt of this r	notice.

000	AU OF E	NVIRONME	INTAL SERV	ICES		
Erosion	and Sedi	ment Contro	I Inspection	Report		
Project Name: NSU Brown Hall						_
Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>6/25/18</u> Inspection Time: <u>2:10</u> pm	Stage of Co Utility Wo	nstruction: ork Demo	Pre-Con Bidg Const.	Clearing F. Grading	Rough F. Stabi	Grading lization
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance	~					
Inlet Protection (P)	~				5	
Outlet Protection @						×
Silt Fence SF	~					
Sediment Trap/Basin 🗊						×
Soil Stabilization (33)						×
Soil Stockpile Stabilization 🐵						×
Tree Protection 💮	~					
Dewatering Structure 🛛 🔞						×
Concrete Washout 😡	~					
				a categories		
The inspection reveals that d The following actions are req Violations: 11st 2nd	eficiencie puired to o 3rd/St	correct the de	in the above eficiencies:	ecategories		
The inspection reveals that d The following actions are req Violations: 1st 2nd	eficiencie juired to o 3rd/Si	correct the de top Work	in the above eficiencies:	e categories		
The inspection reveals that d The following actions are req Violations: ☐1st ☐2nd ✓ CE IP SF TP CW **Installed Correctly - Maintain un	eficiencie juired to d 3rd / Si til surround	is are present correct the de top Work	in the above eficiencies:	e categories		
The inspection reveals that d The following actions are rec Violations: □1st □2nd ✓ CE IP SF TP CW **Installed Correctly - Maintain un	eficiencie juired to d 3rd / Si til surround	ing area is stal	in the above eficiencies: pilized	rom the recei	nt of this :	
The inspection reveals that d The following actions are rec Violations: 1st 2nd V CE IP SF TP CW **Installed Correctly - Maintain un Targeted Re-inspection Date / C	eficiencie juired to d] 3rd / Si til surround	a Time: <u>14</u> ca	in the above eficiencies: pilized	rom the recei	pt of this r	notice.
The inspection reveals that d The following actions are rec Violations: □1st □2nd ✓ CE IP SF TP CW **Installed Correctly - Maintain un 	eficiencie juired to d la 3rd / Si til surround	e Time: <u>14</u> ca	in the above eficiencies: pilized pilized pilendar days fr spector: JaonT	rom the recei	pt of this r	notice.
The inspection reveals that d The following actions are rec Violations: □1st □2nd ✓ CE IP SF TP CW **Installed Correctly - Maintain un Fargeted Re-inspection Date / C Reported to: Nef Lopez Print Name Signature	eficiencie juired to d] 3rd / Si til surround	e Time: <u>14</u> ca	eficiencies: pilized pilendar days fr spector: JaonT	rom the recei	pt of this r	notice.

n -4		444	10.10	
ю	-	.00	60	10

Address: 700 Park Ave.	CGP: No	#:				
Inspection Date: <u>6/11/18</u> Stage of Construct Inspection Time: <u>9:16</u> amUtility Work			Pre-Con noBldg Const.	Clearing F. Grading	Rough Grading F. Stabilization	
E & S Control Practices	Effective	Effective	Not Installed	Violation	Remove	N/A
Construction Entrance @	1					
Inlet Protection (P)	1					
Outlet Protection @						×
Silt Fence (SF)	1					
Sediment Trap/Basin (37)						x
Soll Stabilization (s)						x
Soil Stockpile Stabilization						x
Tree Protection (P)	1					
Dewatering Structure (6)						x
Concrete Washout 😡	1					
Straw Bales	v					
Sediment Leaving Site: <u>No</u>	Continue swo Ieficiencie	eeping daily s are presen	t in the above	e categories		_
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: 1 st 2 nd	Continue swo leficiencie quired to o 3rd/St	eeping daily s are present correct the d top Work	t in the above eficiencies:	e categories		
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: □1st □2nd √ CE IP SF TP CW Straw Bales	Continue swi leficiencie quired to d 3rd / St	eeping daily s are present correct the d top Work	t in the above eficiencies:	e categories		
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: 1 st 2 nd V CE IP SF TP CW Straw Bales **Installed Correctly - Maintain ur	Continue sw leficiencie quired to o 3rd / St ntil surround	eeping daily s are present correct the d top Work ling area is sta	t in the above eficiencies: bilized	e categories		_
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: □1st □2nd ✓ CE IP SF TP CW Straw Bales **Installed Correctly - Maintain ur	Continue swi leficiencie quired to d 3rd / St ntil surround	eeping daily s are presen correct the d top Work ling area is sta	t in the above eficiencies: bilized	e categories		
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: □1st □2nd √ CE IP SF TP CW Straw Bales **Installed Correctly - Maintain un	Continue swi leficiencie quired to d 3rd / St ntil surround	eeping daily s are present correct the d top Work ling area is sta	t in the above eficiencies: bilized	e categories		
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: □1st □2nd ✓ CE IP SF TP CW Straw Bales **Installed Correctly - Maintain un	Continue swi leficiencie quired to d 3rd / St ntil surround	eeping daily s are present correct the d top Work	t in the above eficiencies: bilized	e categories		
Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: □1st □2nd ✓ CE IP SF TP CW Straw Bales **Installed Correctly - Maintain ur	Continue swi leficiencie quired to d 3rd / St ntil surround	eeping daily s are present correct the d top Work	t in the above eficiencies: bilized	e categories		
Sediment Leaving Site: <u>No</u> The inspection reveals that of The following actions are red Violations: □1st □2nd ✓ CE IP SF TP CW Straw Bales **Installed Correctly - Maintain ur	Continue swi leficiencie quired to d 3rd / St ntil surround	eeping daily s are present correct the d top Work	t in the above eficiencies: bilized	e categories		
Sediment Leaving Site: <u>No</u> The inspection reveals that of The following actions are red Violations: □1st □2nd ✓ CE IP SF TP CW Straw Bales **Installed Correctly - Maintain un	Continue swi leficiencie quired to d 3rd / St ntil surround	eeping daily s are presen correct the d top Work	t in the above eficiencies: bilized	e categories		
Sediment Leaving Site: <u>No</u> The inspection reveals that of The following actions are red Violations: □1st □2nd ✓ CE IP SF TP CW Straw Bales **Installed Correctly - Maintain ur	Continue swe leficiencie quired to d 3rd / St ntil surround	eeping daily s are present correct the d top Work	t in the above eficiencies: bilized	e categories		
Sediment Leaving Site: <u>No</u> The inspection reveals that of The following actions are red Violations: 1 st 2 nd V CE IP SF TP CW Straw Bales **Installed Correctly - Maintain ur Fargeted Re-inspection Date / O	Continue swi leficiencie quired to o D 3rd / St ntil surround	eeping daily s are present correct the d top Work ling area is sta	t in the above eficiencies: bilized	e categories		notice.
Sediment Leaving Site: No The inspection reveals that of The following actions are red Violations: □1st □2nd V CE IP SF TP CW Straw Bales **Installed Correctly - Maintain un Targeted Re-inspection Date / C	Continue swe leficiencie quired to o D 3rd / St ntil surround	eeping daily s are present correct the d top W/ork ling area is sta	t in the above eficiencies: bilized	e categories	pt of this r	notice.
Sediment Leaving Site: No The inspection reveals that c The following actions are rec Violations: □1st □2nd V CE IP SF TP CW Straw Bales **Installed Correctly - Maintain ur Targeted Re-inspection Date / C Reported to: Nef Lopez	Continue swi leficiencie quired to d I 3rd / St ntil surround	eeping daily s are present correct the d top Work ling area is sta	t in the above eficiencies: bilized bilized alendar days fr	e categories	pt of this r	notice.
Sediment Leaving Site: <u>No</u> The inspection reveals that c The following actions are red Violations: □1st □2nd ✓ CE IP SF TP CW Straw Bales **Installed Correctly - Maintain ur Targeted Re-inspection Date / C Reported to: <u>Nef Lopez</u> With the following action of the following actions are red Print Name	Continue swi leficiencie quired to d I 3rd / St ntil surround	eeping daily s are present correct the d top Work ling area is sta	t in the above eficiencies: bilized bilized alendar days fr	e categories	pt of this r	notice.
Sediment Leaving Site: No The inspection reveals that c The following actions are rec Violations: □1st □2nd ✓ CE IP SF TP CW Straw Bales **Installed Correctly - Maintain ur Targeted Re-inspection Date / C Reported to: Nef Lopez With Correct Straw Print Name Print Name	Continue swi leficiencie quired to d I 3rd / St ntil surround	eeping daily s are present correct the d top Work ling area is sta	t in the above eficiencies: bilized alendar days fr spector: JaonTr	e categories	pt of this r	notice.
Sediment Leaving Site: No The inspection reveals that c The following actions are red Violations: □1st □2nd ✓ CE IP SF TP CW Straw Bales **Installed Correctly - Maintain ur Signature Fargeted Re-inspection Date / C Reported to: Nef Lopez Signature Signature Signature	Continue swi leficiencie quired to o D 3rd / St ntil surround	eeping daily s are present correct the d top Work ling area is sta	t in the above eficiencies: bilized alendar days fr spector: JaonTr	e categories	pt of this r	notice.

	CITY	OF NOF		ACES		
BURE	AU OF E	:NVIRONME	INTAL SERV	ICES		
Erosion	and Sedi	iment Contro	I Inspection	Report		
Project Name: NSU Brown Hall						
Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>5/24/18</u> Inspection Time: <u>3:07</u> pm	Dection Date: <u>5/24/18</u> Stage of Construction:Pre-Con Dection Time: <u>3:07</u> pmUtility WorkDemoBldg Cons			Clearing F. Grading	Rough Gradin F. Stabilizatior	
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance		X				
Inlet Protection (P)	1					
Outlet Protection						X
Silt Fence SF	1					
Sediment Trap/Basin 57						×
Soil Stabilization (SS)						x
Soil Stockpile Stabilization						×
Tree Protection 🔞						×
Dewatering Structure						×
Concrete Washout						x
The inspection reveals that de The following actions are req Violations: 1st 2nd	eficiencie uired to c 3rd/St	s are present correct the de top Work	in the above eficiencies:	e categories.		
✓ IP SF						
**Installed Correctly - Maintain un	til surround	ling area is stat	bilized			
✓ Inlet protection installed correctly						_
CE - Repair CE IMMEDIATELY						
**install stone to construction entr	rance -OR-	remove sedim	ent to prevent t	racking		
Targeted Re-inspection Date / C	ompliance	Time: <u>7</u> ca	lendar days fr	om the receip	ot of this n	otice.
Reported to: Nef Lopez		Ins	pector: JaonTr	ay D. Coley		
Nel Print Name			1	Print Name	~	1
Signature		- 7		Signature	11	
75706720522	5/24/18	8 620	0-0839	/	5/24	1/18
Phone Number	Da	te Pho	ngNumber	-		Date
	CITY EAU OF E		RFOLK	ICES		
---	---	---	---	------------------------	-------------------	--------
Erosion	and Sedi	iment Contro	Inspection	Report]	
Project Name: NSU Brown Hall						
Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: 4/10/18 Inspection Time: 12:14 pm	Stage of Co Utility W/	onstruction: ork <u>*</u> Demo	Pre-Con Bldg Const.	Clearing F. Grading	Rough F. Stabi	Gradin
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance	~					
Inlet Protection (P)	V					
Outlet Protection @						×
Silt Fence SF	~	×				
Sediment Trap/Basin (37)						
Soil Stabilization (35)						×
Soil Stockpile Stabilization 🐵						×
Tree Protection (TP)	~	x				
Dewatering Structure						x
Concrete Washout 👦						×
Trash/Debris on Site: <u>No</u>						_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd	eficiencie uired to c 3rd/St	s are present correct the de cop Work	in the above ficiencies:	e categories.		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd	eficiencie uired to c 3rd/St	s are present correct the de cop Work	in the above ficiencies:	e categories.		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain unt	eficiencie uired to c 3rd / St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories.		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain unt SF - Repair SF within 24 hours	eficiencie uired to c 3rd/St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories.		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain unt SF - Repair SF within 24 hours **S of site	eficiencie uired to c 3rd/St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories.		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain unt SF - Repair SF within 24 hours **S of site SPS - Install SPS within 7 days	eficiencie uired to c 3rd / St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories.		
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain unt SF - Repair SF within 24 hours **S of site SPS - Install SPS within 7 days TP - Repair TP within 3 days	eficiencie uired to c 3rd/St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories.		
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain unt SF - Repair SF within 24 hours **S of site SPS - Install SPS within 7 days TP - Repair TP within 3 days	eficiencie uired to c 3rd/St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories.		
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain unt SF - Repair SF within 24 hours **S of site SPS - Install SPS within 7 days TP - Repair TP within 3 days	eficiencie uired to c 3rd / St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories.		
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain unt SF - Repair SF within 24 hours **S of site SPS - Install SPS within 7 days TP - Repair TP within 3 days	eficiencie uired to c 3rd/St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies: pilized	e categories.	ot of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain unt SF - Repair SF within 24 hours **S of site SPS - Install SPS within 7 days TP - Repair TP within 3 days TP - Repair TP within 3 days	eficiencie uired to c I 3rd / St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies: pilized	e categories.	ot of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain unt SF - Repair SF within 24 hours **S of site SPS - Install SPS within 7 days TP - Repair TP within 3 days TP - Repair TP within 3 days Cargeted Re-Inspection Date / Constants Print Name	eficiencie uired to c 3rd / St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies: pilized	e categories.	ot of this n	otice.
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd VIOLATIONS: □2nd VIOLATION	eficiencie uired to c 3rd/St til surround	s are present correct the de cop Work ing area is stab	in the above eficiencies: pilized	e categories.	ot of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF TP **Installed Correctly - Maintain unt SF - Repair SF within 24 hours **S of site SPS - Install SPS within 7 days TP - Repair TP within 3 days TP - Repair TP within 3 days	eficiencie uired to c I 3rd / St til surround	s are present correct the de cop Work ing area is stab	in the above eficiencies: pilized	e categories.	ot of this n	otice.

	CITY	OF NO	RFOLK			
BURE	EAU OF L	ENVIRONM	ENTAL SERV	/ICES		
Erosion	and Sed	iment Contro	I Inspection	Report		
Project Name: NSU Brown Hall						
Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: 4/3/18 Inspection Time: 10:27 am	Stage of Co Utility W	onstruction: ork <u>*</u> Demo	Pre-Con Bldg Const.	Clearing F. Grading	Rough F. Stabi	Grading
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance	1					
Inlet Protection (P)	1					
Outlet Protection						x
Silt Fence SF	1	×				
Sediment Trap/Basin (57)						x
Soil Stabilization (SS)						x
Soil Stockpile Stabilization 🐵						x
Tree Protection 🔞	1					
Dewatering Structure 💿						x
Concrete Washout						×
The inspection reveals that d The following actions are req Violations:	eficiencie juired to d 3rd/St	s are present correct the de top Work	in the above ficiencies:	e categories.		
✓ CE IP SF TP						
**Installed Correctly - Maintain un	til surround	ling area is stat	oilized			
SF - Repair SF (minor issues)						
-E of site						
Targeted Re-inspection Date / C	ompliance	Time: 7_ ca	lendar days fr	om the receip	ot of this n	otice.
Reported to: Nef Lopez		Ins	oector: JaonTr	av D. Colev		
Print Name				Print Name	/	/
Nex Iron			1-	2/	1	2
Signature			/	Signature	//	
7576720522	4/3/18	620	0-0839	6	4/3	/18
Phone Number	Da	te Pho	newtumber			Date

CITY OF NORFOLK BUREAU OF ENVIRONMENTAL SERVICES **Erosion and Sediment Control Inspection Report** Project Name: NSU Brown Hall CGP: No Address: 700 Park Ave. #:_____ Clearing Rough Grading Stage of Construction: Pre-Con Inspection Date: 3/13/18 F. Stabilization Utility Work _ Demo __Bldg Const. __F. Grading Inspection Time: 9:26 am Installed Not Installed N/A Not Installed Violation Remove E & S Control Practices Effective Effective Construction Entrance æ 1 Inlet Protection (IP) 1 x **Outlet Protection** OP x Silt Fence (SF) ~ Sediment Trap/Basin x **(ST**) Soil Stabilization (22) × Soil Stockpile Stabilization x **Tree Protection** TP ~ × Dewatering Structure 65 Concrete Washout × (0) V Straw Bales Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that deficiencies are present in the above categories. The following actions are required to correct the deficiencies: □1st □2nd □3rd/Stop Work Violations: ✓ CE IP SF TP Straw Bales **Installed Correctly - Maintain until surrounding area is stabilized IP - Repair IP within 24 hours **replace two drop inlet protection N of site Targeted Re-inspection Date / Compliance Time: 2 calendar days from the receipt of this notice.

Reported to Nef Lopez		Inspector: JaonTray D. Coley	/
A Print Name		Print Nam	
Weller John		6/2	11
Signature		Signature	-//
15710220172	3/13/18	620-0839	343/18
Phone Number	Date	Phone Number	Date

	AUOFE	INVIRONME	ENTAL SERV	ICES		
Transien I	and Cad		Uncoastion	Doport		
Erosion	and Sedi	ment Contro	Inspection	Report		
Project Name: NSU Brown Hall						
Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>3/9/18</u> Inspection Time: <u>10:26</u> am	Stage of Co Utility W/	onstruction: ork <u>*</u> Demo	Pre-Con Bldg Const.	Clearing F. Grading	Rough F. Stabi	Grading
E & S Control Practices	Effective	Effective	Not Installed	Violation	Remove	N/A
Construction Entrance 🛞	1					
Inlet Protection IP	1					
Outlet Protection @						x
Silt Fence 🕼	1					
Sediment Trap/Basin 🗊						x
Soil Stabilization (SS)						X
Soil Stockpile Stabilization 🚱						x
Tree Protection 👘	1					
Dewatering Structure						X
Concrete Washout						X
Straw Bales	1					
Trash/Debris on Site: <u>No</u>						_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd	eficiencie uired to c 3rd/St	s are present correct the de top Work	in the above ficiencies:	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF	eficiencie uired to c □ 3rd / St	s are present correct the de top Work	in the above ficiencies:	e categories		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain unt	eficiencie uired to c 3rd / St til surround	s are present correct the de top Work	in the above ficiencies:	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain unt	eficiencie uired to c 3rd / St til surround	s are present correct the de top Work ling area is stab	in the above ficiencies:	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain unt	eficiencie uired to c I 3rd / St til surround	s are present correct the de top Work ling area is stab	in the above ficiencies:	e categories		
Trash/Debris on Site: <u>No</u>	eficiencie uired to c 3rd/St til surround	s are present correct the de top Work ling area is stab	in the above ficiencies:	e categories		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain unt	eficiencie uired to c I 3rd / St til surround	s are present correct the de top Work ling area is stab	in the above ficiencies:	e categories		
Trash/Debris on Site: <u>No</u>	eficiencie uired to c I 3rd / St til surround	s are present correct the de top Work	in the above ficiencies:	e categories		
Trash/Debris on Site: <u>No</u>	eficiencie uired to c 3rd / St til surround	s are present correct the de top Work	in the above ficiencies:	e categories		
Trash/Debris on Site: <u>No</u>	eficiencie uired to c I 3rd / St til surround	s are present correct the de top Work	in the above ficiencies:	e categories		
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain unt ✓ inlet protection repaired correctly	eficiencie uired to c I 3rd / St til surround	s are present correct the de top Work ling area is stab	in the above ficiencies: bilized	e categories	ot of this n	
Trash/Debris on Site: <u>No</u>	eficiencie uired to c I 3rd / St til surround	s are present correct the de top Work ling area is stab	in the above eficiencies: pilized	e categories	ot of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that de The following actions are req Violations: 1st 2nd ✓ CE IP SF **Installed Correctly - Maintain unt ✓ inlet protection repaired correctly Targeted Re-inspection Date / Co Reported to: Nef Lopez ✓ O ✓ O	eficiencie uired to c I 3rd / St til surround	s are present correct the de top Work ling area is stab	in the above eficiencies: oilized	e categories	ot of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that dependent for the following actions are required to: Dist 2 nd ✓ CE IP SF **Installed Correctly - Maintain unt ✓ Inlet protection repaired correctly ✓ Inlet protection repaired correctly Fargeted Re-inspection Date / Correctly Print Name ✓ Image to the following action by the following actin by the following acting action by the foll	eficiencie uired to d I 3rd / St til surround	s are present correct the de top Work ling area is stab	in the above eficiencies: pilized	e categories	ot of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that dependent of the following actions are required to: Ist I and	eficiencie uired to c 3rd / St til surround	s are present correct the de top Work	in the above eficiencies:	e categories		otice.

	 ~		-	
HCL -	 •		્યા	×.
C 740	 u,	~	~	~

CITY OF NORFOLK BUREAU OF ENVIRONMENTAL SERVICES

Address: 700 Park Ave.				CGP: No	#:	
Inspection Date: <u>3/7/18</u> Inspection Time: <u>12:10</u> pm	Stage of Co Utility Wo	onstruction: ork <u>*</u> Demo	Pre-Con Bldg Const.	Clearing F. Grading	Rough F. Stabi	Grading
E & S Control Practices	Installed Effective	Installed Not Effective	Not Installed	Violation	Remove	N/A
Construction Entrance	1					
Inlet Protection (P)	1	×				
Outlet Protection						×
Silt Fence SF	1					
Sediment Trap/Basin (37)						x
Soil Stabilization (SS)						X
Soil Stockpile Stabilization 🛞						x
Tree Protection 🐨	1					
Dewatering Structure 🛛 🔞						×
Concrete Washout 🞯						x
Straw Bales	1					
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red	eficiencie quired to c	s are present	in the above	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: 1 st 2 nd	eficiencie quired to c 3rd/St	s are present correct the de cop Work	in the above ficiencies:	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: 1st 2nd V CE IP SF **Installed Correctly - Maintain un	eficiencie quired to c 3rd/St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories		_
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: 1st 2nd V CE IP SF **Installed Correctly - Maintain un	eficiencie quired to c 3rd/St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un	eficiencie guired to c 3rd/St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories		
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un IP - Reinstall IP within 24 hours **replace inlet protection to drop	eficiencie guired to c 3rd/St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories		
Trash/Debris on Site: <u>No</u>	eficiencie quired to c 3rd / St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories		
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that d The following actions are red Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un IP - Reinstall IP within 24 hours **replace inlet protection to drop SF - Repair SF (minor issues)	eficiencie guired to c 3rd / St til surround	s are present correct the de top Work ing area is stab	in the above eficiencies:	e categories		
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that d The following actions are red Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un IP - Reinstall IP within 24 hours **replace inlet protection to drop SF - Repair SF (minor issues)	eficiencie guired to c 3rd / St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies:	e categories		
Trash/Debris on Site: <u>No</u>	eficiencie guired to c 3rd / St til surround	s are present correct the de cop Work ing area is stab	in the above eficiencies:	e categories		
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that d The following actions are red Violations:1st2nd VI CE IP SF **Installed Correctly - Maintain un IP - Reinstall IP within 24 hours **replace inlet protection to drop SF - Repair SF (minor issues)	eficiencie guired to c 3rd / St til surround	s are present correct the de cop Work ing area is stab	in the above ficiencies: pilized	e categories.	ot of this n	
Trash/Debris on Site: <u>No</u> Sediment Leaving Site: <u>No</u> The inspection reveals that d The following actions are red Violations: □1st □2nd √ CE IP SF **Installed Correctly - Maintain un IP - Reinstall IP within 24 hours **replace inlet protection to drop SF - Repair SF (minor issues) SF - Repair SF (minor issues)	eficiencie Juired to c I 3rd / St itil surround	s are present correct the de cop Work ing area is stab site	in the above ficiencies: illized lendar days fre pector: JaonTra	e categories om the receip	ot of this n	otice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that d The following actions are red Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un IP - Reinstall IP within 24 hours **replace inlet protection to drop SF - Repair SF (minor issues) SF - Repair SF (minor issues)	eficiencie guired to c 3rd / St til surround inlet NE of s	s are present correct the de top Work ing area is stab site	in the above eficiencies: illized	e categories om the receip ay D. Coley Print Name	ot of this n	notice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that d The following actions are red Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un IP - Reinstall IP within 24 hours **replace inlet protection to drop SF - Repair SF (minor issues) SF - Repair SF (minor issues)	eficiencie Juired to c 3rd / St til surround	s are present correct the de top Work ing area is stab site	in the above eficiencies: illized	e categories	ot of this n	notice.
Trash/Debris on Site: No Sediment Leaving Site: No The inspection reveals that d The following actions are red Violations: □1st □2nd ✓ CE IP SF **Installed Correctly - Maintain un IP - Reinstall IP within 24 hours **replace inlet protection to drop SF - Repair SF (minor issues) SF - Repair SF (minor issues)	eficiencie guired to c 3rd / St til surround inlet NE of s	s are present correct the de cop Work ing area is stab site	in the above eficiencies: pilized lendar days fro pector: JaonTra	e categories		notice.



PROJECT: New Residentail Facility	STATE	PROJECT NO: 2	13-17818-	00
RLD NAME: SB Ballard Construction	DATE:	08/07/2018	TIME:	10:30am
An erosion and sediment control inspection was conducted at the above Work must begin to correct these deficiencies immediately.	referenced	project, and the following	g deficienci	es were found.
□Safety Fence (3.01)□Sediment Trap (3.13)⊠Construction Entrance (3.02)□Sediment Basin (3.14)□Straw Bale Barrier (3.04)□Outlet Protection (3.18)⊠Silt Fence (3.05)□Temporary Seeding (3.3)⊠Storm Drain Inlet Protection (3.07)□Permanent Seeding (3.3)	31) 32)	 Sodding (3.33) Tree Protection Dust Control (3 CW - concrete 	n (3.38) 3.39) washout pi	ts
Comments:				
CE - Rework stone at main Corprew Ave entrance, Provide st	one at all c	other site entry point	S	
Ensure sediment control at full perimeter of site. There are an	eas where	green tubular contr	ol is miss	ing
IP - Provide inlet protection throughout site				
SF - Repair damaged silt fence on east side behind trailer CW - properly maintain concrete washouts				
An erosion and sediment control inspection was conducted a	t the above	e referenced project a	nd no defi	ciencies
Trash/Debris on site: YES ✔ NO Sediment Leaving site: ✔ YES NO Sweep road				
Targeted Re-inspection Date / Compliance Time: 7	_calende	er days from receip	ot of this	notice.
Inspected by: (<i>print</i>) Richard Law (s	signature)_	fit f-	? 	



PROJECT: New Residentail Facility	STATE	PROJECT NO: 21	3-17818-	00
RLD NAME: SB Ballard Construction	DATE:	08/17/2018	TIME:	9:22am
An erosion and sediment control inspection was conducted at the above Work must begin to correct these deficiencies immediately.	referenced p	project, and the following	deficienci	es were found.
 Safety Fence (3.01) Construction Entrance (3.02) Straw Bale Barrier (3.04) Silt Fence (3.05) Storm Drain Inlet Protection (3.07) Sediment Trap (3.13) Sediment Basin (3.14) Outlet Protection (3.18) Temporary Seeding (3.3) Permanent Seeding (3.3) 	1) 2)	 Sodding (3.33) Tree Protection Dust Control (3. 	(3.38) 39)	
Comments:				
Provide inlet protection by Spartan Suites, see image 1				
Provide stone at construction entrance of Corprew Ave. by the	e Police B	uilding, see image 2		
Provide continuous perimeter control, see image 3				
Rework concrete washout station, see image 4				
An erosion and sediment control inspection was conducted at were found.	the above	referenced project an	id no defi	ciencies
Trash/Debris on site: YES NOYES NOYES NOYESNO				
Targeted Re-inspection Date / Compliance Time: 7	_calende	r days from receipt	t of this	notice.
Inspected by: (<i>print</i>) Richard Law (s	ignature) _.	fit		





IMAGE 2





IMAGE 4



PROJECT: New Residentail Facility	STATE PROJECT NO: 213-17818-00	
RLD NAME: SB Ballard Construction	DATE: 08/29/18 TIME: 2:33pm	_
An erosion and sediment control inspection was conducted at the abc Work must begin to correct these deficiencies immediately.	ve referenced project, and the following deficiencies were for	ind.
 Safety Fence (3.01) Construction Entrance (3.02) Straw Bale Barrier (3.04) Silt Fence (3.05) Storm Drain Inlet Protection (3.07) Sediment Trap (3.13) Sediment Basin (3.14) Outlet Protection (3.14) Permanent Seeding 	Sodding (3.33) Image:	
Comments:		
Protect inlet by Spartan Suites, see image 1		
Sweep pavement at Spartan Suites dumpster area, see ima	ge 2	
Provide gravel at southern construction entrance by Sparta	n Suites, see image 3	
Provide inlet protection at walkway, see image 4		
Sweep pavement n Corprew, see image 5		
Install gravel at northwest entrance at Corprew Avenue en	trance, see image 6	_
- The protection on north side of site, see image /		_
		-
		-
		_
		_
		_
		—
		-
		_
An erosion and sediment control inspection was conducted were found.	at the above referenced project and no deficiencies	
Trash/Debris on site: YES NO Sediment Leaving site: YES NO Sweep paven	ent around site	
Targeted Re-inspection Date / Compliance Time: 7	calender days from receipt of this notice.	
Inspected by: (<i>print</i>) Richard Law	(signature)	_







IMAGE 2



IMAGE 3

IMAGE 4







IMAGE 6



PROJECT: New Residentail Facility	STATE	PROJECT NO: 2	13-17818-	00
RLD NAME: SB Ballard Construction	DATE:	09/17/18	TIME:	2:12pm
An erosion and sediment control inspection was conducted at the above Work must begin to correct these deficiencies immediately.	referenced	project, and the following	g deficienci	es were found.
□Safety Fence (3.01)□Sediment Trap (3.13)⊠Construction Entrance (3.02)□Sediment Basin (3.14)□Straw Bale Barrier (3.04)□Outlet Protection (3.18)⊠Silt Fence (3.05)□Temporary Seeding (3.3)⊠Storm Drain Inlet Protection (3.07)□Permanent Seeding (3.3)	31) 32)	 Sodding (3.33) Tree Protection Dust Control (3 CW - concrete 	ı (3.38) .39) washout pi	ts
Comments:				
Provide inlet protection at location of future walkway, see ima	age 1			
Provide gravel at construction entrance by Police Building. S	weep road	l, see image 2		
Fix tree protection throughout site				
FIX SHIT TENCE BY TRAHER OFFICE				
An erosion and sediment control inspection was conducted at were found.	t the above	e referenced project a	nd no defi	ciencies
Trash/Debris on site: YES VO	/ Avenue	by secondary entr	ance	
Targeted Re-inspection Date / Compliance Time: 7	calende	r days from receip	t of this	notice.
Inspected by: (<i>print</i>) Richard Law (s	signature)	fite for		





IMAGE 2